

BOULDER RURAL F.P.D
BOULDER, COLORADO
RESCUE PUMPER, SVI #1168

PRODUCTION SPECIFICATION

Sales Administrator: Jason Kline

Contract Administrator: Jackie Sipres



ROCK SOLID QUALITY

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

LIABILITY INSURANCE

The manufacturer shall furnish with the bid a certificate of insurance for;

Workman's Compensation and Employer's Liability Insurance covering for all employees.

General Liability (each occurrence) of \$1,000,000.00. General Aggregate coverage of \$2,000,000.00. Products Completed / Operations Aggregate coverage of \$2,000,000.00. Medical Expense coverage of \$5,000 (any one person). Personal Injury of \$1,000,000.00.

Automobile liability of \$1,000,000.00 combined single limit (each accident), including any auto, all owned autos, scheduled autos, hired autos, non-owned autos, and garage liability.

Excess Umbrella Liability coverage of \$6,000,000.00 each occurrence, Aggregate of \$6,000,000.00. Garage Keepers Liability coverage of \$6,000,000.00 combined limit.

All insurance policies must be;

- Maintained for the life of the contract,
- Must provide ten (10) days notice before cancellation,
- Must cover all operations of the contractor, or anyone employed by them.

INTERNET IN-PROCESS SITE

The manufacturer shall post and maintain a website where the Boulder Rural Fire Protection District will be able to view digital images of their apparatus as its being built. The digital images shall be posted once a week starting when the body begins production or when the cab/chassis arrives and shall continue until the final completion of unit.

RESPONSIBILITY OF PURCHASER

It shall be the responsibility of the purchaser to specify the details of the apparatus in addition to the requirements in NFPA 1901 needed by the manufacturer to build the apparatus, including:

- 1) Requirements not uniquely specified in NFPA 1901, such as the type of apparatus desired.
- 2) Any features of the apparatus desired in addition to, or in excess of, the requirements in NFPA 1901.

After acceptance of the fire apparatus, the purchaser shall be responsible for ongoing training of personnel to develop and maintain proficiency regarding the proper and safe use of the apparatus and the associated equipment.

RESPONSIBILITY OF CONTRACTOR

The Contractor shall provide a detailed description of the apparatus, a list of equipment to be furnished, and other construction and performance details to which the apparatus shall conform. The detailed description of the apparatus shall include, but shall not be limited to,

1. Estimated In-Service Weight,
2. Wheelbase, Turning Clearance Radius,
3. Principal dimensions, Angle of Approach, Angle of Departure,
4. Transmission, Axle Ratios.

The Contractor's detailed description shall include a statement specifically describing each aspect of the delivered apparatus that will not be fully compliant with the requirements of this standard.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

The purpose of these Contractor specifications shall be to define what the contractor intends to furnish and deliver to the purchaser.

Responsibility for the apparatus and equipment shall remain with the contractor until they are accepted by the purchaser.

VEHICLE STABILITY SUPPLIED WITH CAB/CHASSIS

The cab/chassis shall be equipped with a stability control system. The system shall have, at a minimum, a steering wheel position sensor, a vehicle yaw sensor, a lateral accelerometer and individual wheel brake controls.

FIRE APPARATUS PERFORMANCE

The fire apparatus shall meet the requirements of this standard at elevations of 6,000 ft above sea level.

The fire apparatus shall meet all the requirements of this standard while stationary on a grade of 6 percent in any direction.

The fire apparatus shall meet the requirements of this standard in ambient temperature conditions between 32°F (0°C) and 110°F (43°C).

HIGHWAY PERFORMANCE

The apparatus, when loaded to its estimated in-service weight, shall be capable of the following performance while on dry, paved roads that are in good condition:

- 1) Accelerating from 0 to 35 mph (55 km/hr) within 25 seconds on a 0 percent grade
- 2) Attaining a speed of 50 mph (80 km/hr) on a 0 percent grade
- 3) Maintaining a speed of at least 20 mph (32 km/hr) on any grade up to and including 6 percent

The maximum top speed of fire apparatus with a GVWR over 26,000 lb (11,800 kg) shall not exceed either 68 mph (109 km/hr) or the manufacturer's maximum fire service speed rating for the tires installed on the apparatus, whichever is lower.

If the combined water tank and foam agent tank capacities on the fire apparatus exceed 1250 gal (4732 L), or the GVWR of the vehicle is over 50,000 lb (22,680 kg), the maximum top speed of the apparatus shall not exceed either 60 mph (95 km/hr) or the manufacturer's maximum fire service speed rating for the tires installed on the apparatus, whichever is lower.

SERVICEABILITY

The fire apparatus shall be designed to allow the manufacturer's recommended routine maintenance checks of lubricant and fluid levels to be performed by the operator without lifting the cab of a tilt-cab apparatus or without the need for hand tools.

Where special tools are required for routine service on any component of the apparatus, such tools shall be provided with the apparatus.

Apparatus components that interfere with repair or removal of other major components shall be attached with fasteners, such as cap screws and nuts, so that the components can be removed and installed with ordinary hand tools. These components shall not be welded or otherwise permanently secured into place.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FIRE APPARATUS DOCUMENTATION

The contractor shall supply, at the time of delivery, at least one (1) copy of the following documents:

- 1) The manufacturers record of apparatus construction details, including the following documents:
 - a) Owner's name and address
 - b) Apparatus manufacturer, model, and serial number
 - c) Chassis make, model, and serial number
 - d) GAWR of front and rear axles and GVWR
 - e) Front tire size and total rated capacity in pounds (kilograms)
 - f) Rear tire size and total rated capacity in pounds (kilograms)
 - g) Chassis weight distribution in pounds (kilograms) with water and manufacturer-mounted equipment (front and rear)
 - h) Engine make, model, serial number, rated horsepower and related speed, and governed speed; and if so equipped, engine transmission PTO(s) make, model, and gear ratio
 - i) Type of fuel and fuel tank capacity
 - j) Electrical system voltage and alternator output in amps
 - k) Battery make, model, and capacity in cold cranking amps (CCA)
 - l) Chassis transmission make, model, and serial number; and if so equipped, chassis transmission PTO(s) make, model, and gear ratio
 - m) Ratios of all driving axles
 - n) Maximum governed road speed
 - o) Pump make, model, rated capacity in gallons per minute (liters per minute where applicable), maximum discharge pressure capability rating, and serial number
 - p) Pump transmission make, model, serial number, and gear ratio
 - q) Auxiliary pump make, model, rated capacity in gallons per minute (liters per minute where applicable), and serial number
 - r) Water tank certified capacity in gallons or liters
 - s) Foam tank (if provided) certified capacity in gallons (liters)
 - t) Aerial device type, rated vertical height in feet (meters), rated horizontal reach in feet (meters), and rated capacity in pounds (kilograms)
 - u) Paint manufacturer and paint number(s)
 - v) Company name and signature of responsible company representative
 - w) Weight documents from a certified scale showing actual loading on the front axle, rear axle(s), and overall fire apparatus (with the water tank full but without personnel, equipment, and hose)
- 2) Certification of compliance of the optical warning system (*see 13.8.16*)
- 3) Siren manufacturer's certification of the siren (*see 13.9.1.1*)
- 4) Written load analysis and results of the electrical system performance tests (*see 13.14.1 and Section 13.15*)
- 5) Certification of slip resistance of all stepping, standing, and walking surfaces (*see 15.7.4.5*)
- 6) If the apparatus has a fire pump, the pump manufacturer's certification of suction capability (*see 16.2.4.1*)
- 7) If the apparatus is equipped with a fire pump and special conditions are specified by the purchaser, the pump manufacturer's certification of suction capacity under the special conditions (*see 16.2.4.2*)
- 8) If the apparatus has a fire pump, a copy of the apparatus manufacturer's approval for stationary pumping applications (*see 16.3.1*)
- 9) If the apparatus has a fire pump, the engine manufacturer's certified brake horsepower curve for the engine furnished, showing the maximum governed speed (*see 16.3.2.2*)
- 10) If the apparatus has a fire pump, the pump manufacturer's certification of the hydrostatic test (*see 16.5.2.2*)
- 11) If the apparatus has a fire pump with a maximum discharge pressure capability rating that exceeds the hydrostatic test pressure of 16.5.2.1, the pump manufacturer's certification of the hydrodynamic test
- 12) If the apparatus has a fire pump, the certification of inspection and test for the fire pump (*see 16.13.1.1.5 or 16.13.1.2.4 as applicable*)

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

- 13) If the apparatus is equipped with an auxiliary pump, the apparatus manufacturer's certification of the hydrostatic test (see Section 17.13)
- 14) When the apparatus is equipped with a water tank, the certification of water tank capacity (see Section 18.6)
- 15) If the apparatus has an aerial device, the certification of inspection and test for the aerial device (see Section 19.24)
- 16) If the apparatus has an aerial device, all the technical information required for inspections to comply with NFPA 1911
- 17) If the apparatus has a foam proportioning system, the foam proportioning system manufacturer's certification of accuracy (see 20.10.4.2) and the final installer's certification the foam proportioning system meets this standard (see 20.11.2)
- 18) If the system has a CAFS, the documentation of the manufacturer's pre delivery tests (see Section 21.9)
- 19) If the apparatus has a line voltage power source, the certification of the test for the power source (see 22.15.7.2)
- 20) If the apparatus is equipped with an air system, air tank certificates (see 24.5.1.2), the SCBA fill station certification (see 24.9.6), and the results of the testing of the air system installation (see 24.14.5 and 24.15.4)
- 21) Any other required manufacturer test data or reports

OPERATIONS AND SERVICE DOCUMENTATION

The contractor shall deliver with the fire apparatus complete operation and service documentation covering the completed apparatus as delivered and accepted.

The documentation shall address at least the inspection, service, and operations of the fire apparatus and all major components thereof.

The contractor shall also deliver with the fire apparatus the following documentation for the entire apparatus and each major operating system or major component of the apparatus:

- 1) Manufacturer's name and address
- 2) Country of manufacture
- 3) Source for service and technical information
- 4) Parts replacement information
- 5) Descriptions, specifications, and ratings of the chassis, pump (if applicable), and aerial device (if applicable)
- 6) Wiring diagrams for low voltage and line voltage systems to include the following information:
 - a) Pictorial representations of circuit logic for all electrical components and wiring
 - b) Circuit identification
 - c) Connector pin identification
 - d) Zone location of electrical components
 - e) Safety interlocks
 - f) Alternator-battery power distribution circuits
 - g) Input/output assignment sheets or equivalent circuit logic implemented in multiplexing systems
- 7) Lubrication charts
- 8) Operating instructions for the chassis, any major components such as a pump or aerial device, and any auxiliary systems
- 9) Precautions related to multiple configurations of aerial devices, if applicable
- 10) Instructions regarding the frequency and procedure for recommended maintenance
- 11) Overall apparatus operating instructions
- 12) Safety considerations
- 13) Limitations of use
- 14) Inspection procedures
- 15) Recommended service procedures
- 16) Troubleshooting guide
- 17) Apparatus body, chassis and other component manufacturer's warranties
- 18) Special data required by this standard
- 19) A material safety data sheet (MSDS) for any fluid that is specified for use on the apparatus

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

The contractor shall deliver with the apparatus all manufacturer's operations and service documents supplied with components and equipment that are installed or supplied by the contractor.

NFPA REQUIRED DOCUMENTATION FORMAT - USB FLASH DRIVE

The vehicle construction details and the operations and service documentation as required per NFPA 1901 latest edition shall be provided on a USB Flash Drive. These manuals shall be divided into sections for ease of reference. There shall be two (2) USB flash drives provided with the completed vehicle.

FIRE APPARATUS SAFETY GUIDE

A Fire Apparatus Safety Guide published by Fire Apparatus manufacturer's Association shall be provided with delivered vehicle. This manual includes essential safety information for fire fighters, fire chiefs, apparatus mechanics, and fire department safety officers. The guide is applicable to municipal, wildland, and airport fire fighting apparatus manufactured on either custom or commercial chassis.

STATEMENT OF EXCEPTIONS

The final-stage manufacturer shall deliver with the fire apparatus either a certification that the apparatus fully complies with all requirements of this standard or alternatively, a Statement of Exceptions specifically describing each aspect of the completed apparatus that is not fully compliant with the requirements of this standard at the time of delivery.

The Statement of Exceptions shall contain, for each noncompliant aspect of the apparatus or missing required item, the following information:

- 1) A separate specification of the section of the applicable standard for which compliance is lacking
- 2) A description of the particular aspect of the apparatus that is not in compliance therewith or required equipment that is missing
- 3) A description of the further changes or modifications to the delivered apparatus that must be completed to achieve full compliance
- 4) Identification of the entity that will be responsible for making the necessary post delivery changes or modifications or for supplying and installing any missing required equipment to the apparatus to achieve full compliance with this standard

Prior to or at the time of delivery of the apparatus, the Statement of Exceptions shall be signed by an authorized agent of the entity responsible for final assembly of the apparatus and by an authorized agent of the purchasing entity, indicating mutual understanding and agreement between the parties regarding the substance thereof.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

STATEMENT OF EXCEPTIONS

The Boulder Rural Fire Protection District specified emergency vehicle is NOT fully compliant with the latest NFPA 1901/1906 edition. Listed below are the noncompliant or missing required items that need to be changed to be become fully compliant with latest NFPA 1901/1906 edition;

<u>Change</u>				
<u>Item</u>	<u>Page</u>	<u>Current Description</u>	<u>Changed Description</u>	<u>Responsibility</u>
1		Speed Rating of 68 mph	Top Speed of 75 MPH	Boulder Rural Fire
2				
3				
4				
5				

Prior to, or at the time of, delivery of the apparatus, the Statement of Exceptions shall be signed by an authorized agent of the entity responsible for final assembly of the apparatus and by an authorized agent of the purchasing entity, indicating mutual understanding and agreement between the parties regarding the substance thereof.

SVI Trucks
3842 Redman Drive
Fort Collins, CO 80524

Date: _____

Regional Sales Manager

An apparatus that is delivered subject to a Statement of Exceptions other than a certification of full compliance shall not be placed in emergency service until the apparatus has been modified as necessary to accomplish full compliance with this standard.

Date: _____

On Behalf of Boulder Rural Fire Protection District

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CARRYING CAPACITY

The GAWR and the GCWR or GVWR of the chassis shall be adequate to carry the weight of the completed vehicle when loaded to its estimated in-service weight. The manufacturer shall establish the estimated in service weight during the design of the vehicle.

The estimated in-service weight shall include the following:

1. The chassis, body and tank(s)
2. Full fuel, lubricant, and other chassis or component fluid tanks or reservoirs
3. Full water and other agent tanks
4. *250 lb (114 kg) in each seating position
5. Fixed equipment such as pumps, aerial devices, generators, reels and air systems as installed
6. Ground ladders, suction hose, designed hose load in their hose beds and on their reels
7. An allowance for miscellaneous equipment that is the greatest of the following:
 - a) The values shown for items 1 - 7
 - b) A purchaser-provided list of equipment to be carried with weights
 - c) A purchaser-specified miscellaneous equipment allowance

The manufacturer shall engineer and design the fire apparatus such that the completed apparatus, when loaded to its estimated in-service weight, with all movable weights distributed as close as is practical to their intended in-service configuration, does not exceed the GVWR.

A final manufacturer's certification of the GVWR or GCWR, along with a certification of each GAWR, shall be supplied on a label affixed to the vehicle.

The fire apparatus manufacturer shall permanently affix a high-visibility label in a location visible to the driver while seated.

The label shall show the height of the completed unequipped fire apparatus in feet and inches (meters), the length of the completed fire apparatus in feet and inches (meters), and the GVWR in tons (metric tons).

Wording on the label shall indicate that the information shown was current when the apparatus was manufactured and that, if the overall height changes while the vehicle is in service, the fire department must revise that dimension on the plate.

		Equipment Allowance		
Apparatus Type	Storage Areas	Apparatus Size	lb.	kg.
Pumper Fire Apparatus	Equip. minimum of 40 cu ft (1.1 cu mt) of enclosed compartmentation.	Less than 250 cu ft (7 cu mt) compartment space	2,000	910
	Hose minimum of 30 cu ft (0.8 cu mt) for 2 1/2" (65 mm) or larger fire hose.	250 cu ft (7 cu mt) or more of compartment space	2,500	1,135
	(2) areas for pre-connects each minimum of 3.5 cu.ft. (0.1 cu.mt.) for 1 1/2" (38 mm) or larger fire hose.			
Compartment space for pumpers is calculated based on the inside dimensions of the enclosed compartment.				

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TESTING

ROAD TEST

Each apparatus shall be tested by the manufacturer before delivery to verify that it meets the following criteria;

Tests shall be conducted at a location and in a manner that does not violate local, state or provincial, or federal traffic laws. Tests shall be conducted on a dry, level, paved surface that is free of loose material, oil, or grease. Tests shall be conducted with the water and foam tanks full (water or product).

The apparatus shall accelerate from 0 to 35 mph (55 km/hr) within 25 seconds. The apparatus shall attain a speed of 50 mph (80 km/hr).

The auxiliary braking system, if so equipped, shall function as intended by the auxiliary braking system manufacturer.

The air service brakes shall bring the apparatus to a complete stop from a speed of 20 mph (32.2 km/hr) in a distance not exceeding 35 ft (10.7 m).

The hydraulic service brakes shall bring the apparatus to a complete stop from a speed of 30 mph (48.2 km/hr) in a distance not exceeding 88 ft (26.8 m).

LOW VOLTAGE - ELECTRICAL SYSTEM PERFORMANCE TEST

The vehicles low voltage electrical system shall be third-party, independent, audit-certified through Underwriters Laboratory (UL) to the current edition of NFPA 1901 standard. The certified test results shall be delivered with the completed vehicle. Tests shall be performed when the air temperature is between 0°F and 110°F (−18°C and 43°C).

TEST SEQUENCE

The following three (3) tests shall be performed in the order in which they appear below. Before each test, the batteries shall be fully charged until the voltage stabilizes at the voltage regulator set point and the lowest charge current is maintained for ten (10) minutes. Failure of any of these tests shall require a repeat of the sequence.

1. RESERVE CAPACITY TEST

The engine shall be started and kept running until the engine and engine compartment temperatures are stabilized at normal operating temperatures and the battery system is fully charged. The engine shall be shut off and the minimum continuous electrical load shall be activated for ten (10) minutes.

All electrical loads shall be turned off prior to attempting to restart the engine. The battery system shall then be capable of restarting the engine. Failure to restart the engine shall be considered a test failure of the battery system.

2. ALTERNATOR PERFORMANCE TEST

TEST AT IDLE

The minimum continuous electrical load shall be activated with the engine running at idle speed. The engine temperature shall be stabilized at normal operating temperature. The battery system shall be tested to detect the presence of battery discharge current. The detection of battery discharge current shall be considered a test failure.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TEST AT FULL LOAD

The total continuous electrical load shall be activated with the engine running up to the engine manufacturer's governed speed. The test duration shall be a minimum of two (2) hours. Activation of the load management system shall be permitted during this test.

An alarm sounded by excessive battery discharge, as detected by the warning system required in 13.3.4 or a system voltage of less than 11.8 V dc for a 12 V nominal system, 23.6 V dc for a 24 V nominal system, or 35.4 V dc for a 42 V nominal system for more than 120 seconds shall be considered a test failure.

3. LOW VOLTAGE ALARM TEST

The following test shall be started with the engine off and the battery voltage at or above 12 V for a 12 V nominal system, 24 V for a 24 V nominal system, or 36 V for a 42 V nominal system.

With the engine shut off, the total continuous electrical load shall be activated and shall continue to be applied until the excessive battery discharge alarm activates. The battery voltage shall be measured at the battery terminals.

The test shall be considered a failure if the alarm does not sound in less than 140 seconds after the voltage drops to 11.70 V for a 12 V nominal system, 23.4 V dc for a 24 V nominal system, or 35.1 V for a 42 V nominal system.

The battery system shall then be able to restart the engine. Failure to restart the engine shall be considered a test failure.

LOW VOLTAGE - ELECTRICAL SYSTEM PERFORMANCE TEST

DOCUMENTATION

The manufacturer shall deliver the following with the fire apparatus:

- 1) Documentation of the electrical system performance tests
- 2) A written electrical load analysis, including the following:
 - a) The nameplate rating of the alternator
 - b) The alternator rating
 - c) Each of the component loads specified that make up the minimum continuous electrical load
 - d) Additional electrical loads that, when added to the minimum continuous electrical load, determine the total continuous electrical load
 - e) Each individual intermittent electrical load

UL PUMP CERTIFICATION

The apparatus upon completion shall be tested and certified by Underwriters Laboratories, Inc. (UL). The certification tests shall follow the guide lines outlined in NFPA 1901 "Standard for Fire Apparatus".

If the fire pump has a rated capacity of 750 gpm (3000 L/min) or greater, the pump shall be tested after the pump and all its associated piping and equipment have been installed on the apparatus.

A three (3) hour pumping test from draft shall be completed and certified to perform as listed below;

- 100% of rated capacity at 150 psi (1,000 kPa) net pressure, 2 hours
- 70% of rated capacity at 200 psi (1,400 kPa) net pressure, 1/2 hour
- 50% of rated capacity at 250 psi (1,700 kPa) net pressure, 1/2 hour

The test shall include at least the pumping test, the pumping engine overload test, the pressure control system test, the priming device tests, and the vacuum test.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

The entire pump, both suction and discharge passages, shall be hydrostatically tested to a pressure of 500 psi (3,400 kPa).

The pump shall comply with the applicable requirements of "Standard for Fire Apparatus 1901, latest edition.

The pump shall be capable of producing fire streams that are free from objectionable pulsation under all normal operating conditions.

If the apparatus is equipped with a pump driven by the chassis engine designed for both stationary pumping and pump-and-roll, the test shall verify that the engine speed control at the pump operator's panel cannot be advanced when either of the following conditions exists:

- (1) The chassis transmission is in neutral, the parking brake is off, and the pump shift status in the driving compartment is disengaged.
- (2) The chassis transmission is in any gear other than neutral, the parking brake is on, and the pump shift in the driving compartment is in the "Pump Engaged" or the "OK to Pump-and-Roll" position.

A test plate shall be provided at the pump operator's panel that gives the rated discharges and pressures together with the speed of the engine as determined by the certification test for each unit, the position of the parallel/series pump as used, and the governed speed of the engine as stated by the engine manufacturer on a certified brake horsepower curve.

WARRANTY

A full statement shall be provided of the warranties for the vehicle(s) being bid. Warranties should clearly describe the terms under which the vehicle manufacturer accepts responsibility for the cost to repair defects caused by faulty design, quality of work or material and for the applicable period of time after delivery.

Cost of repairs refers to all costs related thereto including, but not limited to, the cost of materials and the cost of labor.

The Body Manufacturer shall warrant all materials and accessories used on the vehicle(s), whether fabricated by manufacturer or purchased from an outside source and will deal directly with the Boulder Rural Fire Protection District on all warranty work.

GENERAL LIMITED WARRANTY - TWO (2) YEARS

The vehicle shall be free of defects in material and workmanship for a period of two (2) years or 36,000 miles (or 57,936 kilometers), whichever occurs first starting thirty (30) days after the original invoice date.

The Contractor must be the "single source" coordinator of all warranties on the vehicle.

LOW VOLTAGE ELECTRICAL WARRANTY - FIVE (5) YEARS

The vehicle low voltage electrical system shall be free of defects in material and workmanship for a period of five (5) years or 60,000 miles (or 96,561 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date.

STRUCTURAL WARRANTY - TEN (10) YEARS

The body shall be free of structural or design failure or workmanship for a period of ten (10) years, or 100,000 miles (or 160,934 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

UNDERCOAT WARRANTY

The body undercoating shall have a warranty provided by the manufacturer for the lifetime of the vehicle or twenty (20) years, whichever occurs first. The warranty shall be transferable between vehicle owners. Should the undercoating material applied to the underside of the body and wheel wells of the vehicle ever flake off, peel, chip or crack due to drying out, the damaged area shall be re-sprayed without charge to the vehicle owner.

PAINT LIMITED WARRANTY - TEN (10) YEARS

The body shall be free of bubbling or peeling as a result of a defect in the method of manufacture for a period of ten (10) years or 100,000 miles (or 160,934 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date. **Pro-rated warranties will not be acceptable.**

GRAPHICS LIMITED WARRANTY

The 3M graphics installation shall be warranted for a period of two (2) years. The 3M materials installed on completed vehicle shall be warranted for seven (7) years. The 3M Diamond grade film (if specified) shall be warranted for ten (10) years.

WATEROUS FIVE YEAR PUMP WARRANTY

The fire pump shall be warranted by Waterous for a period of five (5) years from the date of delivery to the Boulder Rural Fire Protection District.

STAINLESS STEEL PLUMBING WARRANTY

The stainless steel plumbing shall be free of defects in material and workmanship for a period of ten (10) years, or 100,000 miles (or 160,934 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date.

The contractor shall supply details of their warranty information with their bid submission.

AKRON BRASS FIVE YEAR VALVE WARRANTY

The Akron Brass valves shall be warranted by Akron Brass for a period of ten (10) years from the date of delivery to the Boulder Rural Fire Protection District. The warranty for electronics shall be warranted by Akron Brass for a period of five (5) years from date of delivery to the Boulder Rural Fire Protection District.

POLY WATER TANK WARRANTY

The poly water tank shall be provided with a lifetime material and workmanship limited warranty. The manufacturer shall supply details of their warranty information with their bid submission.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CONSTRUCTION PERIOD

The completed vehicle shall be delivered within four hundred thirty (430) days after receipt of a purchase order or contract.

Contractor shall not be held liable for delays of chassis delivery due to accidents, strikes, floods or other events not subject to their control. Contractor shall provide immediate written notice to Boulder Rural Fire Protection District as to delays and to what extent these delays have in completing vehicle within the stated construction time period.

OVERALL HEIGHT REQUIREMENT

The overall height (OAH) of the vehicle shall be approximately 119" from the ground. This measurement shall be taken on flat ground with the tires properly inflated, in the unloaded condition, at that highest point of the vehicle.

OVERALL LENGTH

The overall length (OAL) of the vehicle shall be approximately 397".

OVERALL WIDTH

The overall width (OAW) of the body at drip rails shall be 102" (8' - 6"), and body shall be 100" (8' - 4").

ANGLE OF APPROACH

The angle of approach for this vehicle shall not be less than eight (8) degrees when it is loaded to the estimated in-service weight as specified by the current edition of NFPA 1901.

ANGLE OF DEPARTURE

The angle of departure for this vehicle shall not be less than eight (8) degrees when it is loaded to the estimated in-service weight as specified by the current edition of NFPA 1901.

PRE-CONSTRUCTION CONFERENCE

A pre-construction conference shall be required at the Contractor's factory for three (3) personnel from the Boulder Rural Fire Protection District to finalize all construction details prior to manufacturing.

The Contractor shall at his/her expense, provide transportation, lodging, rental car and meal expenses during the pre-construction conference. Any travel distance greater than 250 miles shall be by non-stop commercial air travel.

PRE-PAINT CONFERENCE

A pre-paint conference shall be required at the Contractor's factory for three (3) personnel from the Boulder Rural Fire Protection District to inspect the vehicle and construction details prior to the painting process.

The Contractor shall at his/her expense, provide transportation, lodging, rental car and meal expenses during the pre-paint conference. Any travel distance greater than 250 miles shall be by non-stop commercial air travel.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FINAL INSPECTION CONFERENCE

A final inspection conference shall be required at the Contractor's factory for three (3) personnel from the Boulder Rural Fire Protection District to inspect the vehicle and construction details prior to shipment of the completed vehicle. This inspection shall take place after any specified striping and lettering is installed.

The Contractor shall at his/her expense, provide transportation, lodging, rental car and meal expenses during the final inspection conference. Any travel distance greater than 250 miles shall be by non-stop commercial air travel.

DELIVERY AND DEMONSTRATION

The Contractor shall be responsible for the delivery of the completed unit to the Boulder Rural Fire Protection District's location. On initial delivery of the apparatus, the Contractor shall supply a qualified representative to demonstrate the apparatus and provide initial instruction to representatives of the Boulder Rural Fire Protection District regarding the operation, care and maintenance of the apparatus and equipment supplied at Boulder Rural Fire Protection District location.

The Delivery Engineer shall set delivery and instruction schedule with the person appointed by Boulder Rural Fire Protection District.

After delivery of the apparatus, the Boulder Rural Fire Protection District shall be responsible for ongoing training of its personnel to proficiency regarding the proper and safe use of the apparatus and associated equipment.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

MODEL

The chassis shall be a Gladiator model. The cab and chassis shall include design considerations for multiple emergency vehicle applications, rapid transit and maneuverability. The chassis shall be manufactured for heavy duty service with the strength and capacity to support a fully laden apparatus, one hundred (100) percent of the time.

MODEL YEAR

The chassis shall have a vehicle identification number that reflects a 2020 model year.

COUNTRY OF SERVICE

The chassis shall be put in service in the country of United States of America (USA).

The chassis will meet applicable U.S.A. federal motor vehicle safety standards per CFR Title 49 Chapter V Part 571 as clarified in the incomplete vehicle book per CFR Title 49 Chapter V Part 568 Section 4 which accompanies each chassis. Spartan Chassis is not responsible for compliance to state, regional, or local regulations. Dealers should identify those regulations and order any necessary optional equipment from Spartan Chassis or their OEM needed to be in compliance with those regulations.

CAB AND CHASSIS LABELING LANGUAGE

The cab and chassis shall include the applicable caution, warning, and safety notice labels with text to be written in English.

APPARATUS TYPE

The apparatus shall be a pumper vehicle designed for emergency service use which shall be equipped with a permanently mounted fire pump which has a minimum rated capacity of 750 gallons per minute (3000 L/min). The apparatus shall include a water tank and hose body whose primary purpose is to combat structural and associated fires.

VEHICLE TYPE

The chassis shall be manufactured for use as a straight truck type vehicle and designed for the installation of a permanently mounted apparatus behind the cab. The apparatus of the vehicle shall be supplied and installed by the apparatus manufacturer.

VEHICLE ANGLE OF APPROACH PACKAGE

The angle of approach of the apparatus shall be a minimum of 8.00 degrees.

NFPA1901 Angle of Approach definition:

"To determine the angle of approach, place a thin steel strip against the front of the tires where they touch the ground or stretch a tight string from one front tire to the other at the front where they touch the ground. Determine the lowest point (component or equipment) on the vehicle forward of the front tire that would make the smallest angle of approach. Hang a plumb bob from the lowest point and mark the point on the ground where the point of the plumb bob touches. Measure the vertical distance from the ground to the point where the plumb bob was hung (distance V). Measure the horizontal distance from the plumb bob point to the steel strip or string running from front tire to front tire (distance H). Divide the vertical distance by the horizontal distance. The ratio of V/H is the tangent of the angle of approach. If the ratio is known, the angle of approach can be determined from a table of trigonometric functions of angles or from a math calculator. The standard requires a minimum angle of approach of 8.00 degrees: since the tangent of 8.00 degrees is 0.1405, if V divided by H is 0.1405 or larger, the angle of approach is 8.00 degrees or greater."

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AXLE CONFIGURATION

The chassis shall feature a 4 x 2 axle configuration consisting of a single rear drive axle with a single front steer axle.

GROSS AXLE WEIGHT RATINGS FRONT

The front gross axle weight rating (GAWR) of the chassis shall be 20,000 pounds.

This front gross axle weight rating shall be adequate to carry the weight of the completed apparatus including all equipment and personnel.

GROSS AXLE WEIGHT RATINGS REAR

The rear gross axle weight rating (GAWR) of the chassis shall be 24,000 pounds.

This rear gross axle weight rating shall be adequate to carry the weight of the completed apparatus including all equipment and personnel.

PUMP PROVISION

The chassis shall include provisions to mount a drive line pump in the middle of the chassis, behind the cab, more commonly known as the midship location. Chassis driveline pump provisions shall include an interlock feature for automatic setting of the park brake when the vehicle is shifted into pump mode while the transmission is in neutral and the transmission output speed translates to less than 1 mph. When the conditions are met the driver side parking brake valve shall activate. Once shifted to road mode the condition for electric automatic brake engagement is no longer present and the driver's parking brake control valve shall function normally.

WATER & FOAM TANK CAPACITY

The chassis shall include a carrying capacity of up to 750 gallons (2839 liters). The water and/or foam tank(s) shall be supplied and installed by the apparatus manufacturer.

CAB STYLE

The cab shall be a custom, fully enclosed, ELFD model with a 10.00 inch raised roof over the driver, officer, and crew area, designed and built specifically for use as an emergency response vehicle by a company specializing in cab and chassis design for all emergency response applications. The cab shall be designed for heavy-duty service utilizing superior strength and capacity for the application of protecting the occupants of the vehicle. This style of cab shall offer up to ten (10) seating positions.

The cab shall incorporate a fully enclosed design with side wall roof supports, allowing for a spacious cab area with no partition between the front and rear sections of the cab. To provide a superior finish by reducing welds that fatigue cab metal; the roof, the rear wall and side wall panels shall be assembled using a combination of welds and proven industrial adhesives designed specifically for aluminum fabrication for construction.

The cab shall be constructed using multiple aluminum extrusions in conjunction with aluminum plate, which shall provide proven strength and the truest, flattest body surfaces ensuring less expensive paint repairs if needed. All aluminum welding shall be completed to the American Welding Society and ANSI D1.2-96 requirements for structural welding of aluminum.

All interior and exterior seams shall be sealed for optimum noise reduction and to provide the most favorable efficiency for heating and cooling retention.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

The cab shall be constructed of 5052-H32 corrosion resistant aluminum plate. The cab shall incorporate tongue and groove fitted 6061-T6 0.13 & 0.19 inch thick aluminum extrusions for extreme duty situations. A single formed, one (1) piece extrusion shall be used for the "A" pillar, adding strength and rigidity to the cab as well as additional roll-over protection. The cab side walls and lower roof skin shall be 0.13 inch thick; the rear wall and raised roof skins shall be 0.09 inch thick; the front cab structure shall be 0.19 inch thick.

The exterior width of the cab shall be 99.40 inches wide with a minimum interior width of 91.00 inches. The overall cab length shall be 151.10 inches with 74.00 inches from the centerline of the front of the axle to the back of the cab.

The cab interior shall be designed to afford the maximum usable interior space and attention to ergonomics with hip and legroom while seated which exceeds industry standards. The crew cab floor shall be flat across the entire walking area for ease of movement inside the cab.

The cab shall offer an interior height of 57.50 inches from the front floor to the headliner and a rear floor to headliner height of 65.00 inches in the raised roof area, at a minimum. The cab shall offer an interior measurement at the floor level from the rear of the engine tunnel to the rear wall of the cab of 69.88 inches. All interior measurements shall include the area within the interior trimmed surfaces and not to any unfinished surface.

The cab shall include a driver and officer area with two (2) cab doors large enough for personnel in full firefighting gear. The front doors shall offer a clear opening of 40.25 inches wide X 53.50 inches high, from the cab floor to the top of the door opening. The cab shall also include a crew area with up to two (2) cab doors, also large enough for personnel in full firefighting gear. The rear doors shall offer a clear opening of 32.25 inches wide X 61.00 inches high, from the cab floor to the top of the door opening.

The cab shall incorporate a progressive two (2) step configuration from the ground to the cab floor at each door opening. The progressive steps are vertically staggered and extend the full width of each step well allowing personnel in full firefighting gear to enter and exit the cab easily and safely.

The first step for the driver and officer area shall measure approximately 11.50 inches deep X 31.13 inches wide. The intermediate step shall measure approximately 8.50 inches deep X 32.50 inches wide. The height from the first step to the intermediate step and the intermediate step to the cab floor shall not exceed 11.00 inches.

The first step for the crew area shall measure approximately 11.50 inches deep X 20.44 inches wide. The intermediate step shall measure approximately 10.25 inches deep X 22.75 inches wide. The height from the first step to the intermediate step and the intermediate step to the cab floor shall not exceed 12.80 inches.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

OCCUPANT PROTECTION

The vehicle shall include the Advanced Protection System™ (APS) which shall secure belted occupants and increase the survivable space within the cab. The APS shall selectively deploy integrated systems to protect against injuries in qualifying frontal impact, side impact, and rollover events. The increase in survivable space and security of the APS shall also provide ejection mitigation protection.

The system components shall include:

- Driver steering wheel airbag
- Driver dual knee air bags (patent pending) with energy management mounting (patent pending) and officer knee airbag.
- Large driver, officer, and crew area side curtain airbags
- APS advanced seat belt system - retractor pre-tensioners tighten the seat belts around the occupants, securing the occupants in seats and load limiters play out some of the seat belt webbing to reduce seat belt to chest and torso force upon impact as well as mitigate head and neck injuries
- Heavy truck Restraints Control Module (RCM) - receives inputs from the outboard sensors, selectively deploys APS systems, and records sensory inputs immediately before and during a detected qualifying event
- Integrated outboard crash sensors mounted at the perimeter of the vehicle - detects a qualifying front or side impact event and monitors and communicates vehicle status and real time diagnostics of all critical subsystems to the RCM
- Fault-indicating Supplemental Restraint System (SRS) light on the driver's instrument panel

Frontal impact protection shall be provided by the outboard sensors and the RCM. In a qualifying front impact event the outboard sensors provide inputs to the RCM. The RCM activates the steering wheel airbag, driver side dual knee airbags (patent pending), officer side knee airbag, and advanced seat belts for each occupant in the cab.

Rollover, side impact, and ejection mitigation shall be provided by the outboard sensors and the RCM. In qualifying rollover or side impact events the outboard sensors provide inputs to the RCM. The RCM activates the side curtain airbags and advanced seat belts for each occupant in the cab. The RCM measures roll angle, lateral acceleration, and roll rate to determine if a rollover event or side impact event is imminent or occurring.

In the event of a qualifying offset or other non-frontal impact, the RCM shall determine and intelligently deploy the front impact protection system, the side impact protection system, or both front and side impact protection systems based on the inputs received from the outboard crash sensors.

CAB FRONT FASCIA

The front cab fascia shall be constructed of 5052-H32 Marine Grade, 0.13 of an inch thick aluminum plate which shall be an integral part of the cab.

The cab fascia will encompass the entire front of the aluminum cab structure from the bottom of the windshield to the bottom of the cab and shall be the "Classic" design.

The front cab fascia shall include two (2) molded plastic modules on each side accommodating a total of up to four (4) Hi/Low beam headlights and two (2) turn signal lights or up to four (4) warning lights. A chrome plated molded plastic bezel shall be provided on each side around each set of four lamps.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FRONT GRILLE

The front cab fascia shall include a classic box style, 304 stainless steel front grille. The grille shall measure 55.45 wide X 33.50 inches high X 1.50 inches deep. The upper portion of the grille shall be hinged to provide service access behind the grille. The grille shall include a minimum free air intake of 750.00 square inches.

CAB UNDERCOAT

There shall be a rubberized undercoating applied to the underside of the cab that provides abrasion protection, sound deadening and corrosion protection.

CAB SIDE DRIP RAIL

There shall be a drip rail along the top radius of each cab side. The drip rails shall help prevent water from the cab roof running down the cab side.

CAB PAINT EXTERIOR

The cab shall be painted prior to the installation of glass accessories and all other cab trim to ensure complete paint coverage and the maximum in corrosion protection of all metal surfaces.

All metal surfaces on the entire cab shall be ground by disc to remove any surface oxidation or surface debris which may hinder the paint adhesion. Once the surface is machine ground a high quality acid etching of base primer shall be applied. Upon the application of body fillers and their preparation, the cab shall be primed with a coating designed for corrosion resistance and surface paint adhesion. The maximum thickness of the primer coat shall be 2.00 mils.

The entire cab shall then be coated with an intermediate solid or epoxy surfacing agent that is designed to fill any minor surface defects, provide an adhesive bond between the primer and the paint and improve the color and gloss retention of the color. The finish to this procedure shall be a sanding of the cab with 360 grit paper followed by sealing the seams with SEM brand seam sealer.

The cab shall then be painted the specific color designated by the customer with an acrylic urethane type system designed to retain color and resist acid rain and most atmospheric chemicals found on the fire ground or emergency scene. The paint shall have a minimum thickness of 2.00 mils, followed by a clear top coat not to exceed 2.00 mils. The entire cab shall then be baked at 180 degrees for one (1) hour to speed the curing process of the coatings.

CAB PAINT MANUFACTURER

The cab shall be painted with PPG Industries paint.

CAB PAINT PRIMARY/LOWER COLOR

The primary/lower paint color shall be PPG FBCH 2185 White.

CAB PAINT WARRANTY

The cab and chassis shall be covered by a limited manufacturer paint warranty which shall be in effect for ten (10) years from the first owner's date of purchase or in service or the first 100,000 actual miles, whichever occurs first.

The warranty details can be found in the chassis warranty document.

CAB PAINT INTERIOR

The visible interior cab structure surfaces shall be painted with a multi-tone black-black texture finish.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB ENTRY DOORS

The cab shall include four (4) entry doors, two (2) front doors and two (2) crew doors designed for ease of entering and egress when outfitted with an SCBA. The doors shall be constructed of extruded aluminum with a nominal thickness of 0.13 inch. The exterior skins shall be constructed of 0.13 inch aluminum plate.

The doors shall include a double rolled style automotive rubber seal around the perimeter of each door frame and door edge which ensures a weather tight fit.

All door hinges shall be hidden within flush mounted cab doors for a pleasing smooth appearance and perfect fit along each side of the cab. Each door hinge shall be piano style with a 0.38 inch pin and shall be constructed of stainless steel.

CAB ENTRY DOOR TYPE

All cab entry doors shall be barrier clear design resulting in exposed lower cab steps. The doors shall provide approximately 32.00 inches of clearance from the ground to the bottom of the door so cab doors may be opened unhindered by most obstacles encountered, such as guard rails along interstate highways.

Entry doors shall include Pollak mechanical plunger style switches for electrical component activation.

CAB INSULATION

The cab ceiling and walls shall include 1.00 inch thick foam insulation. The insulation shall act as a barrier absorbing noise as well as assisting in sustaining the desired climate within the cab interior.

LH EXTERIOR REAR COMPARTMENT

The cab shall offer an exterior compartment on the left side of the cab behind the rear door. The compartment opening shall be 17.00 inches wide X 60.19 inches high. The compartment size shall be 17.34 inches wide X 60.19 inches high X 21.19 inches deep. The compartment shall have a 16.63 inch wide, 60.00 inch high and 1.50 inch thick hinged box pan style flush mount door with a bright aluminum tread plate inner panel and a bent D-ring slam latch. The door shall open towards the rear of the cab. There shall be a switch to activate a light inside the compartment and the open compartment warning light in the cab in the event the door is left ajar.

LEFT HAND EXTERIOR REAR COMPARTMENT LIGHTING

There shall be one (1) SoundOff Signal brand LED strip light installed to illuminate the exterior rear compartment on the left side of the cab. The strip light shall be 43.00 inches long and shall include twelve (12) bright white Gen3 LEDs.

LH EXTERIOR COMPARTMENT INTERIOR FINISH

The interior of the left hand exterior compartment shall have a multi-tone onyx black texture finish.

RH EXTERIOR REAR COMPARTMENT

The cab shall offer an exterior compartment on the right side of the cab behind the rear door. The compartment opening shall be 17.00 inches wide X 60.19 inches high. The compartment size shall be 17.34 inches wide X 60.19 inches high X 21.19 inches deep. The compartment shall have a 16.63 inch wide, 60.00 inch high and 1.50 inch thick hinged box pan style flush mount door with a bright aluminum tread plate inner panel and a bent D-ring slam latch. The door shall open towards the rear of the cab. There shall be a switch to activate a light inside the compartment and the open compartment warning light in the cab in the event the door is left ajar.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

RIGHT HAND EXTERIOR REAR COMPARTMENT LIGHTING

There shall be one (1) SoundOff Signal brand LED strip light installed to illuminate the exterior rear compartment on the right side of the cab. The strip light shall be 43.00 inches long and shall include twelve (12) bright white Gen3 LEDs.

RH EXTERIOR COMPARTMENT INTERIOR FINISH

The interior of the right hand exterior compartment shall have a multi-tone onyx black texture finish.

CAB STRUCTURAL WARRANTY

Summary of Warranty Terms:

THE FOLLOWING IS SUMMARY OF WARRANTY TERMS FOR INFORMATION ONLY. THE ACTUAL LIMITED WARRANTY DOCUMENT, CAN BE FOUND IN THE CHASSIS WARRANTY DOCUMENT, CONTAINS THE COMPLETE STATEMENT OF THE SPARTAN MOTORS USA LIMITED WARRANTY. SPARTAN'S RESPONSIBILITY IS TO BE ACCORDING TO THE TERMS OF THE COMPLETE LIMITED WARRANTY DOCUMENT.

The cab structure shall be warranted for a period of ten (10) years or one hundred thousand (100,000) miles which ever may occur first. The warranty period shall commence on the date the vehicle is delivered to the first end user.

CAB TEST INFORMATION

The cab shall have successfully completed the preload side impact, static roof load application and frontal impact without encroachment to the occupant survival space when tested in accordance with Section 4 of SAE J2420 COE Frontal Strength Evaluation Dynamic Loading Heavy Trucks, Section 5 of SAE J2422 Cab Roof Strength Evaluation Quasi –Static Loading Heavy Trucks and ECE R29 Uniform Provisions Concerning the Approval of Vehicles with regard to the Protection of the Occupants of the Cab of a Commercial Vehicles Annex 3 Paragraph 5.

The above tests have been witnessed by and attested to by an independent third party. The test results were recorded using cameras, high speed imagers, accelerometers and strain gauges. Documentation of the testing shall be provided upon request.

ELECTRICAL SYSTEM

The chassis shall include a single starting electrical system which shall include a 12 volt direct current multiplexing system, suppressed per SAE J551. The wiring shall be appropriate gauge cross link with 311 degree Fahrenheit insulation. All SAE wires in the chassis shall be color coded and shall include the circuit number and function where possible. The wiring shall be protected by 275 degree Fahrenheit minimum high temperature flame retardant loom. All nodes and sealed Deutsch connectors shall be waterproof.

MULTIPLEX DISPLAY

The multiplex electrical system shall include a Weldon Vista IV display which shall be located on the left side of the dash in the switch panel. The Vista IV shall feature a full color LCD display screen which includes a message bar displaying the time of day and important messages requiring acknowledgement by the user which shall all be displayed on the top of the screen in the order they are received. There shall be eight (8) push button virtual controls, four (4) on each side of the display for the on-board diagnostics. The display screen shall be video ready for back-up cameras, thermal cameras, and DVD.

The Vista IV display shall offer varying fonts and background colors. The display shall be fully programmable to the needs of the customer and shall offer virtually infinite flexibility for screen configuration options.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

LOAD MANAGEMENT SYSTEM

The apparatus load management shall be performed by the included multiplex system. The multiplex system shall also feature the priority of sequences and shall shed electrical loads based on the priority list specifically programmed.

DATA RECORDING SYSTEM

The chassis shall have a Weldon Vehicle Data Recorder (VDR) system installed. The system shall be designed to meet NFPA 1901 and shall be integrated with the Weldon Multiplex electrical system. The following information shall be recorded:

- Vehicle Speed
- Acceleration
- Deceleration
- Engine Speed
- Engine Throttle Position
- ABS Event
- Seat Occupied Status
- Seat Belt Status
- Master Optical Warning Device Switch Position
- Time
- Date

Each portion of the data shall be recorded at the specified intervals and stored for the specified length of time to meet NFPA 1901 guidelines and shall be retrievable by connecting a laptop computer to the VDR system.

ACCESSORY POWER

The electrical distribution panel shall include two (2) power studs. The studs shall be size #10 and each of the power studs shall be circuit protected with a fuse of the specified amperage. One (1) power stud shall be capable of carrying up to a 40 amp battery direct load. One (1) power stud shall be capable of carrying up to a 15 amp ignition switched load. The two (2) power studs shall share one (1) #10 ground stud. A 225 amp battery direct power and ground stud shall be provided and installed on the chassis near the left hand battery box for OEM body connections.

AUXILIARY ACCESSORY POWER

An auxiliary set of power and ground studs shall be provided and installed behind the driver seat with a 40 amp breaker. The studs shall be 0.38 inch diameter and capable of carrying up to a 40 amp battery direct load. An additional 4.00 feet of wire shall accompany the option.

EXTERIOR ELECTRICAL TERMINAL COATING

All terminals exposed to the elements will be sprayed with a high visibility protective rubberized coating to prevent corrosion.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ENGINE

The chassis engine shall be a Cummins L9 engine. The L9 engine shall be an in-line six (6) cylinder, four cycle diesel powered engine. The engine shall offer a rating of 450 horse power at 2100 RPM and shall be governed at 2200 RPM. The torque rating shall feature 1250 foot pounds of torque at 1400 RPM with 543 cubic inches (8.9 liters) of displacement.

The L9 engine shall feature a VGT™ Turbocharger, a high pressure common rail fuel system, fully integrated electronic controls with an electronic governor, and shall be EPA certified to meet the 2017 emissions standards using cooled exhaust gas recirculation and selective catalytic reduction technology.

The engine shall include an engine mounted combination full flow/by-pass oil filter with replaceable spin on cartridge for use with the engine lubrication system. The engine shall include Citgo brand Citgard 500, or equivalent 15W40 CK-4 low ash engine oil which shall be utilized for proper engine lubrication.

A wiring harness shall be supplied ending at the back of the cab. The harness shall include a connector which shall allow an optional harness for the pump panel. The included circuits shall be provided for a tachometer, oil pressure, engine temperature, hand throttle, high idle and a PSG system. A circuit for J1939 data link shall also be provided at the back of the cab.

CAB ENGINE TUNNEL

The cab interior shall include an integrated engine tunnel constructed of 5052-H32 Marine Grade 0.19 of an inch thick aluminum alloy plate. The side walls shall be tapered from the top of the seatbox to an angle of 22.00 degrees from vertical. The tapered tunnel will provide 3.00 inches of additional inboard hip room for both the driver and officer seating positions. The rear of the tunnel shall be shortened to provide 2.00 inches of additional crew space behind the tunnel.

DIESEL PARTICULATE FILTER CONTROLS

There shall be two (2) controls for the diesel particulate filter. One (1) control shall be for regeneration and one (1) control shall be for regeneration inhibit.

ENGINE PROGRAMMING HIGH IDLE SPEED

The engine high idle control shall maintain the engine idle at approximately 1250 RPM when engaged.

ENGINE HIGH IDLE CONTROL

The vehicle shall be equipped with a virtual Vista button and an automatic high-idle speed control. It shall be pre-set so when activated, it will operate the engine at the appropriate RPM to increase alternator output. This device shall operate only when the engine is running and the transmission is in neutral with the parking brake set. The device shall disengage when the operator depresses the brake pedal, or the transmission is placed in gear, and shall be available to manually or automatically re-engage when the brake is released, or when the transmission is placed in neutral. There shall be an indicator on the Vista display and control screen for the high idle speed control.

ENGINE PROGRAMMING ROAD SPEED GOVERNOR

The engine shall include programming which will govern the top speed of the vehicle.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AUXILIARY ENGINE BRAKE

A compression brake, for the six (6) cylinder engine shall be provided. A cutout relay shall be installed to disable the compression brake when in pump mode or when an ABS event occurs. The engine compression brake shall activate upon 0% accelerator when in operation mode and actuate the vehicle's brake lights.

The engine shall utilize a variable geometry turbo (VGT) as an integrated auxiliary engine brake to offer a variable rate of exhaust flow, which when activated in conjunction with the compression brake shall enhance the engine's compression braking capabilities.

AUXILIARY ENGINE BRAKE CONTROL

An engine compression brake control device shall be included. The electronic control device shall monitor various conditions and shall activate the engine brake only if all of the following conditions are simultaneously detected:

- A valid gear ratio is detected.
- The driver has requested or enabled engine compression brake operation.
- The throttle is at a minimum engine speed position.
- The electronic controller is not presently attempting to execute an electronically controlled final drive gear shift.

The compression brake shall be controlled through an on/off switch and a low/medium/high selector switch.

ELECTRONIC ENGINE OIL LEVEL INDICATOR

The engine oil shall be monitored electronically and shall send a signal to activate a warning in the instrument panel when levels fall below normal. The warning shall activate in a low oil situation upon turning on the master battery and ignition switches without the engine running.

FLUID FILLS

The front of the chassis shall accommodate fluid fill for the engine oil through the grille. This area shall also accommodate a check for the engine oil. The transmission, power steering, and coolant fluid fills and checks shall be under the cab. The windshield washer fill shall be accessible through the front left side mid step.

ENGINE DRAIN PLUG

The engine shall include an original equipment manufacturer installed oil drain plug.

ENGINE WARRANTY

The Cummins engine shall be warranted for a period of five (5) years or 100,000 miles, whichever occurs first.

REMOTE THROTTLE HARNESS

An apparatus interface wiring harness for the engine and transmission pump interlocks shall be supplied with the chassis. The harness shall include a connector for connection to a chassis pump panel harness supplied by the body builder and shall terminate in the left frame rail behind the cab for connection by the body builder. The harness shall include circuits deemed for a pump panel and shall contain circuits for a hand throttle, and a multiplexed gauge. Separate circuits shall also be included for a pump control switch, "Pump Engaged" and "OK to Pump" indicator lights, open compartment ground, start signal, park brake ground, ignition signal, master power, clean power, customer ignition, air horn solenoid switch, high idle switch and high idle indicator light. The harness shall contain interlocks that will prevent shifting to road or pump mode unless the transmission output speed translates to less than 1 mph and the transmission is in neutral. The shift to pump mode shall also require the park brake be set.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ENGINE PROGRAMMING REMOTE THROTTLE

The engine ECM discreet wire remote throttle circuit will be turned on for use with a discreet wire based pump controller.

ENGINE PROGRAMMING IDLE SPEED

The engine low idle speed will be programmed at 700 rpm.

ENGINE AIR INTAKE

The engine air intake system shall include an ember separator. This ember separator shall be designed to protect the downstream air filter from embers using a combination of unique flat and crimped metal screens packaged in a heavy duty galvanized steel frame. This multilayered screen shall trap embers and allow them to burn out before passing through the pack.

The engine air intake system shall also include an air cleaner mounted above the radiator. This air cleaner shall utilize a replaceable dry type filter element designed to prevent dust and debris from being ingested into the engine. A service cover shall be provided on the housing, reducing the chance of contaminating the air intake system during air filter service.

The air intake system shall include a restriction indicator light in the warning light cluster on the instrument panel, which shall activate when the air cleaner element requires replacement.

ENGINE FAN DRIVE

The engine cooling system fan shall incorporate a thermostatically controlled, Horton clutched type fan drive. The clutch fan shall override the thermostatic variable speed and function as full on automatically in pump mode.

When the clutched fan is disengaged it shall facilitate improved vehicle performance, cab heating in cold climates, and fuel economy. The fan clutch design shall be fail safe so that if the clutch drive fails the fan shall engage to prevent engine overheating due to the fan clutch failure. The fan speed shall be electronically programmed to vary through thermostatic control to run as efficiently and quietly as required to maintain temperature.

ENGINE COOLING SYSTEM

There shall be a heavy-duty aluminum cooling system designed to meet the demands of the emergency response industry. The cooling system shall have the capacity to keep the engine properly cooled under all conditions of road and pumping operations. The cooling system shall be designed and tested to meet or exceed the requirements specified by the engine and transmission manufacturer and all EPA requirements. The complete cooling system shall be mounted to isolate the entire system from vibration or stress. The individual cores of the cooling system shall be mounted in a manner to allow expansion and contraction at various rates without inducing stress into the adjoining cores.

The cooling system shall be comprised of a charge air cooler to radiator serial flow package that provides the maximum cooling capacity for the specified engine as well as serviceability. The main components shall include a surge tank, a charge air cooler bolted to the front of the radiator, recirculation shields, a shroud, a fan, and required tubing.

The radiator shall be a down-flow design constructed with aluminum cores, plastic end tanks, and a steel frame. The radiator shall be equipped with a drain cock to drain the coolant for serviceability.

The cooling system shall include a one piece injected molded polymer fan with a three (3) piece fiberglass fan shroud.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

The cooling system shall be equipped with a surge tank that is capable of removing entrained air from the system. The surge tank shall be equipped with a low coolant probe and rearward oriented sight glass to observe coolant in the system. A cold fill and observation line shall be included within the frame mounted translucent recovery bottle to monitor the level of the coolant. The surge tank shall have a dual seal cap that meets the engine manufacturer's pressure requirements and allows for expansion and recovery of coolant into a separate integral expansion chamber.

All radiator tubes shall be formed from aluminized steel tubing. Recirculation shields shall be installed where required to prevent heated air from reentering the cooling package and affecting performance.

The charge air cooler shall be a cross-flow design constructed completely of aluminum with cast tanks. All charge air cooler tubes shall be formed from aluminized steel tubing and installed with silicone hump hoses and stainless steel "constant torque" style clamps meeting the engine manufacturer's requirements.

The radiator and charge air cooler shall be removable through the bottom of the chassis.

ENGINE COOLING SYSTEM PROTECTION

The engine cooling system shall include a recirculation shield designed to act as a light duty skid plate below the radiator to provide additional protection for the engine cooling system from light impacts, stones, and road debris. The skid plate shall be painted to match the frame components.

ENGINE COOLANT

The cooling package shall include Extended Life Coolant (ELC). The use of ELC provides longer intervals between coolant changes over standard coolants providing improved performance. The coolant shall contain a 50/50 mix of ethylene glycol and de-ionized water to keep the coolant from freezing to a temperature of -34 degrees Fahrenheit.

Proposals offering supplemental coolant additives (SCA) shall not be considered, as this is part of the extended life coolant makeup.

ELECTRONIC COOLANT LEVEL INDICATOR

The instrument panel shall feature a low engine coolant indicator light which shall be located in the center of the instrument panel. An audible tone alarm shall also be provided to warn of a low coolant incident.

ENGINE PUMP HEAT EXCHANGER

A single bundle type coolant to water heat exchanger shall be installed between the engine and the radiator. The heat exchanger shall be designed to prohibit water from the pump from coming in contact with the engine coolant. This shall allow the use of water from the discharge side of the pump to assist in cooling the engine.

COOLANT HOSES

The engine cooling system hoses shall be Goodyear Hi-Miler Straight Radiator Hose where permitted, formed silicone adapters, and formed aluminized steel tubing. Charge air cooling system shall consist of reinforced silicone bellows or sleeve, and formed aluminized steel tubing.

Cab heating system shall be Goodyear Hi-Miler Blue Heater Hose.

All silicone hose and formed adapters shall be secured with stainless steel constant torque band clamps. All aluminized steel tubing connections shall be beaded.

Exhaust after treatment/DEF system plumbing shall be Spartan controlled.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ENGINE COOLANT OVERFLOW BOTTLE

A remote engine coolant overflow expansion bottle shall be provided in the case of over filling the coolant system. The overflow bottle shall capture the expansion fluid or overfill rather than allow the fluid to drain on the ground.

ENGINE EXHAUST SYSTEM

The exhaust system shall include an end-in end-out horizontally mounted single module after treatment device, downpipe from the charge air cooled turbo. The single module shall include four temperature sensors, diesel particulate filter (DPF), urea dosing module (UL2), and a selective catalytic reduction (SCR) catalyst to meet current EPA standards. The selective catalytic reduction catalyst utilizes a diesel exhaust fluid solution consisting of urea and purified water to convert NOx into nitrogen, water, and trace amounts of carbon dioxide. The solution shall be mixed and injected into the system through the between the DPF and SCR.

The system shall utilize 0.07 inch thick stainless steel exhaust tubing between the engine turbo and the DPF. Zero leak clamps seal all system joints between the turbo and DPF.

The single module after treatment through the end of the tailpipe shall be connected with zero leak clamps. The discharge shall terminate horizontally on the right side of the vehicle ahead of the rear tires.

The exhaust system after treatment module shall be mounted below the frame in the outboard position.

DIESEL EXHAUST FLUID TANK

The exhaust system shall include a molded cross linked polyethylene tank for Diesel Exhaust Fluid (DEF). The tank shall have a capacity of six (6) usable gallons and shall be mounted on the left hand side of the chassis frame behind the batteries below the frame.

The DEF tank shall be designed with capacity for expansion in case of fluid freezing. Engine coolant, which shall be thermostatically controlled, shall be run through lines in the tank to help prevent the DEF from freezing and to provide a means of thawing the fluid if it should become frozen.

The tank fill tube shall be routed under the rear of the cab with the fill neck and splash guard accessible in the top rear step.

ENGINE EXHAUST ACCESSORIES

An exhaust temperature mitigation device shall be shipped loose for installation by the body manufacturer on the vehicle. The temperature mitigation device shall lower the temperature of the exhaust by combining ambient air with the exhaust gasses at the exhaust outlet.

ENGINE EXHAUST WRAP

The exhaust tubing between the engine turbo and the diesel particulate filter (DPF) shall be wrapped with a thermal cover in order to retain the necessary heat for DPF regeneration. The exhaust wrap shall also help protect surrounding components from radiant heat which can be transferred from the exhaust.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TRANSMISSION

The drive train shall include an Allison model EVS 3000 torque converting, automatic transmission which shall include electronic controls. The transmission shall feature two (2) 10-bolt PTO pads located on the converter housing.

The transmission shall include two (2) internal oil filters and Castrol TranSynd™ synthetic TES 295 transmission fluid which shall be utilized in the lubrication of the EVS transmission. An electronic oil level sensor shall be included with the readout located in the shift selector.

The transmission gear ratios shall be:

1st	3.49:1
2nd	1.86:1
3rd	1.41:1
4th	1.00:1
5th	0.75:1
6th	0.65:1 (if applicable)
Rev	5.03:1

TRANSMISSION MODE PROGRAMMING

The transmission, upon start-up, will automatically select a four (4) speed operation. The fifth speed over drive shall be available with the activation of the mode button on the shifting pad.

TRANSMISSION FEATURE PROGRAMMING

The Allison Gen V-E transmission EVS group package number 127 shall contain the 198 vocational package in consideration of the duty of this apparatus as a pumper. This package shall incorporate an automatic neutral with selector override. This feature commands the transmission to neutral when the park brake is applied, regardless of drive range requested on the shift selector. This requires re-selecting drive range to shift out of neutral for the override.

This package shall be coupled with the use of a split shaft PTO and incorporate pumping circuits. These circuits shall be used allowing the vehicle to operate in the fourth range lockup while operating the pump mode due to the 1 to 1 ratio through the transmission, therefore the output speed of the engine is the input speed to the pump. The pump output can be easily calculated by using this input speed and the drive ratio of the pump itself to rate the gallons of water the pump can provide.

A transmission interface connector shall be provided in the cab. This package shall contain the following input/output circuits to the transmission control module. The Gen V-E transmission shall include prognostic diagnostic capabilities. These capabilities shall include the monitoring of the fluid life, filter change indication, and transmission clutch maintenance.

<u>Function ID</u>	<u>Description</u>	<u>Wire assignment</u>
Inputs		
C	PTO Request	142
J	Fire Truck Pump Mode (4th Lockup)	122 / 123
Outputs		
C	Range Indicator	145 (4th)
G	PTO Enable Output	130
	Signal Return	103

ELECTRONIC TRANSMISSION OIL LEVEL INDICATOR

The transmission fluid shall be monitored electronically and shall send a signal to activate a warning in the instrument panel when levels fall below normal.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TRANSMISSION SHIFT SELECTOR

An Allison pressure sensitive range selector touch pad shall be provided and located to the right of the driver within clear view and easy reach. The shift selector shall have a graphical Vacuum Florescent Display (VFD) capable of displaying two lines of text. The shift selector shall provide mode indication and a prognostic indicator (wrench symbol) on the digital display. The prognostics monitor various operating parameters and shall alert you when a specific maintenance function is required.

TRANSMISSION PRE-SELECT WITH AUXILIARY BRAKE

When the auxiliary brake is engaged, the transmission shall automatically shift to second gear to decrease the rate of speed assisting the secondary braking system and slowing the vehicle.

TRANSMISSION COOLING SYSTEM

The transmission shall include a water to oil cooler system located in the cooling loop between the radiator and the engine. The transmission cooling system shall meet all transmission manufacturer requirements. The transmission cooling system shall feature continuous flow of engine bypass water to maintain uninterrupted transmission cooling.

TRANSMISSION DRAIN PLUG

The transmission shall include an original equipment manufacturer installed magnetic transmission fluid drain plug.

TRANSMISSION WARRANTY

The Allison EVS series transmission shall be warranted for a period of five (5) years with unlimited mileage. Parts and labor shall be included in the warranty.

PTO LOCATION

The transmission shall have two (2) power take off (PTO) mounting locations, one (1) in the 8:00 o'clock position and one (1) in the 4:00 o'clock position.

DRIVELINE

All drivelines shall be heavy duty metal tube and equipped with MSI 1710 series universal joints. The shafts shall be dynamically balanced prior to installation to alleviate future vibration. In areas of the driveline where a slip shaft is required, the splined slip joint shall be coated with Glide Coat[®]. The drivelines shall include Meritor brand u-joints with thrust washers.

MIDSHIP PUMP / GEARBOX

A temporary jackshaft driveline shall be installed by the chassis manufacturer to accommodate the mid-ship split shaft pump as specified by the apparatus manufacturer.

MIDSHIP PUMP / GEARBOX MODEL

The midship pump/gearbox provisions shall be for a Waterous CSUC20 pump.

MIDSHIP PUMP GEARBOX DROP

The Waterous pump gearbox shall have a "C" (medium length) drop length.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

MIDSHIP PUMP RATIO

The ratio for the midship pump shall be 2.27:1.

MIDSHIP PUMP LOCATION C/L SUCTION TO C/L REAR AXLE

The midship pump shall be located so the dimension from the centerline of the suction to the centerline of the rear axle is 93.00 inches.

PUMP SHIFT CONTROLS

One (1) air pump shift control panel shall be located on the left hand side of the engine tunnel, integrated with the shifter pod. The following shall be provided on the panel: a three (3) position control lever; an engraved PUMP ENGAGED identification light; and an engraved OK TO PUMP identification light. The pump shift control panel shall be black with a yellow border outline and shall include pump instructions. An instruction plate describing the transmission shift selector position used for pumping shall be provided and located so it can be read from the driver's position per NFPA **16.10.1.3**. The road mode shall be selected when the control lever is in the forward position and pump mode shall be selected when the control lever is in the rearward position.

The control lever center position shall exhaust air from both pump and road sides of the pump gear box shift cylinder.

PUMP SHIFT CONTROL PLUMBING

Air connections shall be provided from the air supply tank to the pump shift control valve and from the pump shift control valve to the frame mounted bracket. The frame mounted bracket shall include labeling identifying the pump and road connection points with threaded 0.25 inch NPT fittings on the solenoid for attaching the customer installed pump. The air supply shall be pressure protected from service brake system.

FUEL FILTER/WATER SEPARATOR

The fuel system shall have a Fleetguard FS1098 fuel filter/water separator as a primary filter. The fuel filter shall have a drain valve.

A water in fuel sensor shall be provided and wired to an instrument panel lamp and audible alarm to indicate when water is present in the fuel/water separator.

A secondary fuel filter shall be included as approved by the engine manufacturer.

FUEL LINES

The fuel system supply and return lines installed from the fuel tank to the engine shall be reinforced nylon tubing rated for diesel fuel. The fuel lines shall be brown in color and connected with brass fittings.

FUEL SHUTOFF VALVE

A fuel shutoff valve shall be installed in the fuel draw line at the primary fuel filter to allow the fuel filter to be changed without loss of fuel to the fuel pump.

A second fuel shutoff valve shall be installed in the fuel draw line, near the fuel tank to allow maintenance to be performed with minimal loss of fuel.

ELECTRIC FUEL PRIMER

Integral to the engine assembly is an electric lift pump that serves the purpose of pre-filter fuel priming.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FUEL TANK

The fuel tank shall have a capacity of sixty-five (65) gallons and shall measure 35.00 inches in width X 18.50 inches in height X 24.00 inches in length.

The baffled tank shall have a vent port to facilitate venting to the top of the fill neck for rapid filling without "blow-back" and a roll over ball check vent for temperature related fuel expansion and draw.

The tank is designed with dual draw tubes and sender flanges. The tank shall have 2.00 inch NPT fill ports for right or left hand fill. A 0.50 inch NPT drain plug shall be centered in the bottom of the tank.

The fuel tank shall be mounted below the frame, behind the rear axle. Two (2) three-piece strap hanger assemblies with "U" straps bolted midway on the fuel tank front and rear shall be utilized to allow the tank to be easily lowered and removed for service purposes. Rubber isolating pads shall be provided between the tank and the upper tank mounting brackets. Strap mounting studs through the rail, hidden behind the body shall not be acceptable.

FUEL TANK MATERIAL AND FINISH

The fuel tank shall be constructed of 12 gauge aluminized steel. The exterior of the tank shall be powder coated black and then painted to match the frame components.

All powder coatings, primers and paint shall be compatible with all metals, pretreatments and primers used. The cross hatch adhesion test per ASTM D3359 Method B, results to be 5B minimum. The pencil hardness test per ASTM D3363 shall have a final post-cured pencil hardness of H-2H. The direct impact resistance test per ASTM D2794, results to be 5B minimum.

Any proposals offering painted fuel tanks with variations from the above process shall not be accepted. The film thickness of vendor supplied parts shall also be sufficient to meet the performance standards as stated above.

FUEL TANK STRAP MATERIAL

The fuel tank straps shall be constructed of ASTM A-36 steel. The fuel tank straps shall be powder coated black and then painted to match the frame components if possible.

FUEL TANK FILL PORT

The fuel tank fill ports shall be even with the left and right fill port located in the middle position of the fuel tank.

FUEL TANK SERVICEABILITY PROVISIONS

The chassis fuel lines shall have additional length provided so the tank can be easily lowered and removed for service purposes. The additional 8.00 feet of length shall be located above the fuel tank and shall be coiled and secured. The fuel line fittings shall be pointed towards the right side (curbside) of the chassis.

FUEL TANK DRAIN PLUG

A 0.5 inch NPT magnetic drain plug shall be centered in the bottom of the fuel tank.

FRONT AXLE

The front axle shall be a Meritor Easy Steer Non drive front axle, model number MFS-20. The axle shall include a 3.74 inch drop and a 71.00 inch king pin intersection (KPI). The axle shall include a conventional style hub with a standard knuckle.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FRONT AXLE WARRANTY

The front axle shall be warranted by Meritor for five (5) years with unlimited miles under the general service application. Details of the Meritor warranty are provided on the PDF document attached to this option.

FRONT WHEEL BEARING LUBRICATION

The front axle wheel bearings shall be lubricated with oil. The oil level can be visually checked via clear inspection windows in the front axle hubs.

FRONT SHOCK ABSORBERS

Two (2) Bilstein inert, nitrogen gas filled shock absorbers shall be provided and installed as part of the front suspension system. The shocks shall be a monotubular design and fabricated using a special extrusion method, utilizing a single blank of steel without a welded seam, achieving an extremely tight peak-to-valley tolerance and maintains consistent wall thickness. The monotubular design shall provide superior strength while maximizing heat dissipation and shock life.

The ride afforded through the use of a gas shock is more consistent and shall not deteriorate with heat, the same way a conventional oil filled hydraulic shock would.

The Bilstein front shocks shall include a digressive working piston assembly allowing independent tuning of the compression and rebound damping forces to provide optimum ride and comfort without compromise. The working piston design shall feature fewer parts than most conventional twin tube and "road sensing" shock designs and shall contribute to the durability and long life of the Bilstein shock absorbers.

Proposals offering the use of conventional twin tube or "road sensing" designed shocks shall not be considered.

FRONT SUSPENSION

The front suspension shall include a ten (10) leaf spring pack in which the longest leaf measures 54.00 inch long and 4.00 inches wide and shall include a military double wrapped front eye. Both spring eyes shall have a case hardened threaded bushing installed with lubrication counter bore and lubrication land off cross bore with grease fitting. The spring capacity shall be rated at 21,500 pounds.

STEERING COLUMN/ WHEEL

The cab shall include a Douglas Autotech steering column which shall include a seven (7) position tilt, a 2.25 inch telescopic adjustment, and an 18.00 inch, four (4) spoke steering wheel located at the driver's position. The steering wheel shall be covered with black polyurethane foam padding.

The steering column shall contain a horn button, self-canceling turn signal switch, four-way hazard switch and headlamp dimmer switch.

ELECTRONIC POWER STEERING FLUID LEVEL INDICATOR

The power steering fluid shall be monitored electronically and shall send a signal to activate an audible alarm and visual warning in the instrument panel when fluid level falls below normal.

POWER STEERING PUMP

The hydraulic power steering pump shall be a TRW PS and shall be gear driven from the engine. The pump shall be a balanced, positive displacement, sliding vane type. The power steering system shall include an oil to air passive cooler.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FRONT AXLE CRAMP ANGLE

The chassis shall have a front axle cramp angle of 48-degrees to the left and 44-degrees to the right.

POWER STEERING GEAR

The power steering gear shall be a TRW model TAS 85 with an assist cylinder.

CHASSIS ALIGNMENT

The chassis frame rails shall be measured to insure the length is correct and cross checked to make sure they run parallel and are square to each other. The front and rear axles shall be laser aligned. The front tires and wheels shall be aligned and toe-in set on the front tires by the chassis manufacturer.

REAR AXLE

The rear axle shall be a Meritor model RS-24-160 single drive axle. The axle shall include precision forged, single reduction differential gearing, and shall have a rated capacity of 24,000 pounds.

The axle shall be built of superior construction and quality components to provide the rugged dependability needed to stand up to the fire industry's demands. The axle shall include rectangular shaped, hot-formed housing with a standard wall thickness of 0.50 of an inch for extra strength and rigidity and a rigid differential case for high axle strength and reduced maintenance.

The axle shall have heavy-duty Hypoid gearing for longer life, greater strength and quieter operation. Industry-standard wheel ends for compatibility with both disc and drum brakes, and unitized oil seal technology to keep lubricant in and help prevent contaminant damage will be used.

REAR AXLE DIFFERENTIAL LUBRICATION

The rear axle differential shall be lubricated with synthetic oil.

REAR AXLE WARRANTY

The rear axle shall be warranted by Meritor for five (5) years with unlimited miles under the general service application. Details of the Meritor warranty are provided on the PDF document attached to this option.

WHEEL HUB PAINT

Each of the wheel hubs shall be coated with gloss black paint.

REAR WHEEL BEARING LUBRICATION

The rear axle wheel bearings shall be lubricated with synthetic oil.

VEHICLE TOP SPEED

The top speed of the vehicle shall be approximately 75 MPH +/-2 MPH at governed engine RPM.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

REAR SUSPENSION

The single rear axle suspension shall feature a Neway ADZ-124 air suspension. The suspension shall include optimized air springs mounted to cast structural trailing arms, transverse cross beams for increased roll stability and four heavy duty shock absorbers. Dual air height control valves shall be installed to ensure equal frame height on both sides of the vehicle regardless of the load. Axle alignment is maintained using EZ-ALIGN® pivot connections for fast and easy axle alignment.

The rear suspension capacity shall be rated at 21,000 to 24,000 pounds.

REAR SHOCK ABSORBERS

Shock absorbers shall be supplied by the suspension manufacturer and installed on the rear axle suspension.

TIRE INTERMITTENT SERVICE RATING

The chassis shall be rated using Intermittent Service ratings provided to the emergency vehicle market by the tire manufacturers as the basis for determining the maximum vehicle load and speed.

FRONT TIRE

The front tires shall be Goodyear 425/65R-22.5 20PR "L" tubeless radial G296 MSA mixed service tread.

The front tire stamped load capacity shall be 22,800 pounds per axle with a nominal speed rating of 68 miles per hour when properly inflated to 120 pounds per square inch.

The Goodyear Intermittent Service Rating maximum load capacity shall be 24,400 pounds per axle with a speed rating of 68 miles per hour when properly inflated to 120 pounds per square inch.

The Goodyear Intermittent Service Rating maximum speed capacity shall be 22,800 pounds per axle with a speed rating of 75 miles per hour when properly inflated to 120 pounds per square inch.

The Goodyear Intermittent Service Rating limits the operation of the emergency vehicle to no more than fifty (50) miles of continuous operation under maximum recommended payload, or without stopping for at least twenty (20) minutes. The emergency vehicle must reduce its speed to no more than 50 MPH after the first fifty (50) miles of travel.

REAR TIRE

The rear tires shall be Goodyear 12R-22.5 16PR "H" tubeless radial G751 MSA mixed service tread.

The rear tire stamped load capacity shall be 27,120 pounds per axle with a speed rating of 68 miles per hour when properly inflated to 120 pounds per square inch.

The Goodyear Intermittent Service Rating maximum load capacity shall match the stamped rating.

The Goodyear Intermittent Service Rating maximum speed capacity shall be 27,120 pounds per axle with a speed rating of 75 miles per hour when properly inflated to 120 pounds per square inch.

The Goodyear Intermittent Service Rating limits the operation of the emergency vehicle to no more than fifty (50) miles of continuous operation under maximum recommended payload, or without stopping for at least twenty (20) minutes. The emergency vehicle must reduce its speed to no more than 50 MPH after the first fifty (50) miles of travel.

REAR AXLE RATIO

The rear axle ratio shall be 4.56:1.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TIRE PRESSURE INDICATOR

There shall be electronic chrome LED valve caps shipped loose for installation by the OEM which shall illuminate with a red LED when tire pressure drops 8psi provided. The valve caps are self-calibrating and set to the pressure of the tire upon installation.

FRONT WHEEL

The front wheels shall be Alcoa hub piloted, 22.50 inch X 12.25 inch LVL One™ polished aluminum wheels. The hub piloted mounting system shall provide easy installation and shall include two-piece flange nuts. The wheels shall feature one-piece forged strength and shall include Alcoa's Dura-Bright® finish with XBR technology as an integral part of the wheel surface. Alcoa Dura-Bright® wheels keep their shine without polishing. Brake dust, grime and road debris are easily removed by simply cleaning the wheels with soap and water.

REAR WHEEL

The rear wheels shall be Alcoa hub piloted, 22.50 inch X 8.25 inch LVL One™ aluminum wheels with a polished outer surface and Alcoa Dura-Bright® wheel treatment with XBR® technology as an integral part of the wheel. The hub piloted mounting system shall provide easy installation and shall include two-piece flange nuts.

TIRE CHAINS

Onspot brand six (6) strand automatic ice chains shall be installed on the rear axle of the chassis to provide instant traction while traveling on ice and snow at speeds below 35 MPH.

TIRE CHAINS ACTIVATION

The tire chain system shall be activated by a locking switch on the dash to deter accidental activation. The light on the switch shall illuminate when the tire chains are engaged. The tire chains shall be interlocked with the transmission and shall engage only if the vehicle is traveling 30 MPH or less. After traveling over 30 MPH, the vehicle must be reduced to a speed below 5 MPH for the tire chains to be engaged or re-engaged.

BRAKE SYSTEM

A rapid build-up air brake system shall be provided. The air brakes shall include, at a minimum, a two (2) air tank, three (3) reservoir system with a total of 4152 cubic inch of air capacity. A floor mounted treadle valve shall be mounted inside the cab for graduated control of applying and releasing the brakes. An inversion valve shall be installed to provide a service brake application in the unlikely event of primary air supply loss. All air reservoirs provided on the chassis shall be labeled for identification.

The rear axle spring brakes shall automatically apply in any situation when the air pressure falls below 25 PSI and shall include a mechanical means for releasing the spring brakes when necessary. An audible alarm shall designate when the system air pressure is below 60 PSI.

A four (4) sensor, four (4) modulator Anti-lock Braking System (ABS) shall be installed on the front and rear axles in order to prevent the brakes from locking or skidding while braking during hard stops or on icy or wet surfaces. This in turn shall allow the driver to maintain steering control under heavy braking and in most instances, shorten the braking distance. The electronic monitoring system shall incorporate diagonal circuitry which shall monitor wheel speed during braking through a sensor and tone ring on each wheel. A dash mounted ABS lamp shall be provided to notify the driver of a system malfunction. The ABS system shall automatically disengage the auxiliary braking system device when required. The speedometer screen shall be capable of reporting all active defaults using PID/SID and FMI standards.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Additional safety shall be accommodated through Automatic Traction Control (ATC) which shall be installed on the single rear axle. The ATC system shall apply the ABS when the drive wheels lose traction. The system shall scale the electronic engine throttle back to prevent wheel spin while accelerating on ice or wet surfaces.

A virtual style switch shall be provided and properly labeled "mud/snow". When the switch is pressed once, the system shall allow a momentary wheel slip to obtain traction under extreme mud and snow conditions. During this condition the ATC light shall blink continuously notifying the driver of activation. Pressing the switch again shall deactivate the mud/snow feature.

The Electronic Stability Control (ESC) unit is a functional extension of the electronic braking system. It is able to detect any skidding of the vehicle about its vertical axis as well as any rollover tendency. The control unit comprises an angular-speed sensor that measures the vehicle's motion about the vertical axis, caused, for instance, by cornering or by skidding on a slippery road surface. An acceleration sensor measures the vehicle's lateral acceleration. The Controller Area Network (CAN) bus provides information on the steering angle. On the basis of lateral acceleration and steering angle, an integrated microcontroller calculates a theoretical angular speed for the stable vehicle condition.

FRONT BRAKES

The front brakes shall be Meritor EX225 Disc Plus disc brakes with 17.00 inch vented rotors.

REAR BRAKES

The rear brakes shall be Meritor EX225 Disc Plus disc brakes with 17.00 inch vented rotors.

PARK BRAKE

Upon application of the push-pull valve in the cab, the rear brakes will engage via mechanical spring force. This is accomplished by dual chamber rear brakes, satisfying the FMVSS parking brake requirements.

PARK BRAKE CONTROL

A Meritor-Wabco manual hand control push-pull style valve shall operate the parking brake.

The parking brake actuation valve shall be mounted to the left side of the engine tunnel integrated into the transmission shift pod console within easy access of the driver.

AIR DRYER

The brake system shall include a Wabco System Saver 1200 air dryer with an integral heater with a Metri-Pack sealed connector. The air dryer incorporates an internal turbo cutoff valve that closes the path between the air compressor and air dryer purge valve during the compressor "unload" cycle. The turbo cutoff valve allows purging of moisture and contaminants without the loss of turbo boost pressure. The air dryer shall be mounted behind the battery box on the left hand side.

FRONT BRAKE CHAMBERS

The front brakes shall be provided with MGM type 24 long stroke brake chambers.

REAR BRAKE CHAMBERS

The rear axle shall include TSE 24/30 H.O.T. (High Output Technology) brake chambers shall convert the energy of compressed air into mechanical force and motion. This shall actuate the brake camshaft, which in turn shall operate the foundational brake mechanism forcing the brake pads against the brake rotor.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AIR COMPRESSOR

The air compressor provided for the engine shall be a Wabco® SS318 single cylinder pass-through drive type compressor which shall be capable of producing 18.7 CFM at 1200 engine RPMs. The air compressor shall feature a higher delivery efficiency translating to more air delivery per horsepower absorbed. The compressor shall include an aluminum cylinder head which shall improve cooling, reduce weight and decrease carbon formation. Superior piston and bore finishing technology shall reduce oil consumption and significantly increasing the system component life.

AIR GOVERNOR

An air governor shall be provided to control the cut-in and cut-out pressures of the engine mounted air compressor. The governor shall be calibrated to meet FMVSS requirements. The air governor shall be located on the air dryer bracket on the left frame rail behind the battery box.

AUXILIARY AIR RESERVOIR

One (1) auxiliary air reservoir with a 1200 cubic inch capacity shall be installed on the chassis to act as an additional reserve supply to the air system for air horn, air tool, or other non-service brake use. The reservoir shall be isolated with a 90 PSI pressure protection valve on the reservoir supply side to prevent depletion of the air to the air brake system.

MOISTURE EJECTORS

Manual cable actuated drain valves shall be installed on all reservoirs of the air supply system. The actuation pull cables shall be coiled and tied at each drain valve. The supplied cables when extended shall be sufficient in length to allow each drain to be activated from the side of the apparatus.

AIR SUPPLY LINES

The air system on the chassis shall be plumbed with color coded reinforced nylon tubing air lines. The primary (rear) brake line shall be green, the secondary (front) brake line red, the parking brake line orange and the auxiliary (outlet) will be blue.

Brass compression type fittings shall be used on the nylon tubing. All drop hoses shall include fiber reinforced neoprene covered hoses.

AIR INLET CONNECTION

An air connection for the shoreline air inlet shall be supplied.

AIR INLET LOCATION

The air inlet shall be installed in the left hand side lower front step in the forward position.

AIR OUTLET CONNECTION

A quick release air outlet female connector shall be installed in the mid-section of the left lower cab step towards the front of the cab for the use of auxiliary air tools. The air outlet connector shall be compatible with a Milton 787, Parker Hannifin B13 or Meyers 54-410 connector.

PLUMBING AIR OUTLET CONNECTION

The cab mounted air outlet connection shall be plumbed to the chassis auxiliary air system reservoir.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AIR INLET/ OUTLET FITTING TYPE

The air connector supplied shall be a 0.25 inch size Tru-Flate Interchange style manual connection which is compatible with Milton 'T' style, Myers 0.25 inch Automotive style and Parker 0.25 inch 10 Series connectors.

WHEELBASE

The chassis wheelbase shall be 190.00 inches.

REAR OVERHANG

The chassis rear overhang shall be 60.00 inches.

FRAME

The frame shall consist of double rails running parallel to each other with cross members forming a ladder style frame. The frame rails shall be formed in the shape of a "C" channel, with the outer rail measuring 10.25 inches high X 3.50 inches deep upper and lower flanges X 0.38 inches thick with an inner channel of 9.44 inches high X 3.13 inches deep and 0.38 inches thick. Each rail shall be constructed of 110,000 psi minimum yield high strength low alloy steel. Each double rail section shall be rated by a Resistance Bending Moment (RBM) minimum of 3,213,100 inch pounds and have a minimum section modulus of 29.21 cubic inches. The frame shall measure 35.00 inches in width.

Proposals calculating the frame strength using the "box method" shall not be considered.

Proposals including heat treated rails shall not be considered. Heat treating frame rails produces rails that are not uniform in their mechanical properties throughout the length of the rail. Rails made of high strength, low alloy steel are already at the required yield strength prior to forming the rail.

A minimum of seven (7) fully gusseted 0.25 inch thick cross members shall be installed. The inclusion of the body mounting, or bumper mounting shall not be considered as a cross member. The cross members shall be attached using zinc coated grade 8 fasteners. The bolt heads shall be flanged type, held in place by distorted thread flanged lock nuts. Each cross member shall be mounted to the frame rails utilizing a minimum of 0.25 inch thick gusset reinforcement plates at all corners balancing the area of force throughout the entire frame.

Any proposals not including additional reinforcement for each cross member shall not be considered.

All relief areas shall be cut in with a minimum 2.00 inch radius at intersection points with the edges ground to a smooth finish to prevent a stress concentration point.

The frame and cross members shall carry a lifetime warranty to the original purchaser. A copy of the frame warranty shall be made available upon request.

Proposals offering warranties for frames not including cross members shall not be considered.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FRAME WARRANTY

Summary of Warranty Terms:

THE FOLLOWING IS SUMMARY OF WARRANTY TERMS FOR INFORMATION ONLY. THE ACTUAL LIMITED WARRANTY DOCUMENT, CAN BE FOUND IN THE CHASSIS WARRANTY DOCUMENT, CONTAINS THE COMPLETE STATEMENT OF THE SPARTAN MOTORS USA LIMITED WARRANTY. SPARTAN'S RESPONSIBILITY IS TO BE ACCORDING TO THE TERMS OF THE COMPLETE LIMITED WARRANTY DOCUMENT.

The frame and cross members shall carry a limited lifetime warranty to the original purchaser. The warranty period shall commence on the date the vehicle is delivered to the first end user.

FRAME CLEAR AREA

The chassis frame shall be left clear of chassis mounted components inside and outside the frame rails within the first 48.00 inches behind the cab to allow space for OEM installed components. Cross members may be installed in the clear area if required for proper frame or driveline configuration.

FRAME PAINT

The frame rails shall be hot dip galvanized prior to assembly and attachment of any components. The components that shall be galvanized shall include:

- Main frame "C" channel or channels

The frame parts which are not galvanized shall be powder coated prior to any attachment of components. Parts which shall be powder coated shall include but are not limited to:

- Steering gear bracket
- Front splayed rails and fish plates
- Bumper extensions
- Cross members
- Cross member gussets
- Fuel tank mounting brackets
- Fuel tank straps (unless material/finish is specified in 3130 subcat)
- Air tanks (unless color coded tanks are specified in 3205 subcat)
- Air tank mounting brackets
- Exhaust mounting brackets
- Air cleaner skid plate
- Radiator skid plate
- Battery supports, battery trays and battery covers

Other non-galvanized under carriage components which are received from the suppliers with coatings already applied shall include but are not limited to:

- Suspension components
- Front and rear axles

All powder coatings, primers and paint used on the non-galvanized components shall be compatible with all metals, pretreatments and primers used. The cross hatch adhesion test per ASTM D3359 shall not have a fail of more than ten (10) squares. The pencil hardness test per ASTM D3363 shall have a final post-cured pencil hardness of H-2H. The direct impact resistance test per ASTM D2794 shall have an impact resistance of 120.00 inches per pound at 2 mils.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FRONT BUMPER

A one piece, two (2) rib wrap-around style, polished stainless steel front bumper shall be provided. The material shall be 10 gauge 304 stainless steel, 12" high and 104.50 inches wide.

FRONT BUMPER EXTENSION LENGTH

The front bumper shall be extended approximately 6.00 inches ahead of the cab.

FRONT BUMPER DISCHARGE

The chassis shall include frame mounted 2.00 inch diameter plumbed pipe intended for use as a discharge trash line. The discharge pipe shall be routed from the right hand front splay rail area behind the bumper to the area rear of the front axle, ahead of the battery box.

The discharge shall pipe shall be a, 2.00 inch stainless steel schedule 10 tube. The discharge shall include a Victaulic groove for connecting to the pump and discharge hose plumbing on each end of the tube.

The apparatus manufacturer shall plumb the discharge pipe to the pump and shall provide all valves as required.

MECHANICAL SIREN

A Federal Q2B™ siren shall be provided and installed by the customer.

AIR HORN

The chassis shall include plumbing for two (2) air horns that shall be provided and installed by the body manufacturer.

AIR HORN RESERVOIR

One (1) air reservoir, with a 1200 cubic inch capacity, shall be installed on the chassis to act as a supply tank for operating air horns. The reservoir shall be isolated with a 90 PSI pressure protection valve on the reservoir supply side to prevent depletion of the air to the air brake system.

FIRE BELL

A chromed cast formed fireman's bell shall be installed on the front bumper. The bell shall include an eagle perched at the top and feature a polished chrome finish. The bell shall measure approximately 17.50 inches in height from the top of the eagle to the base of the bell.

FIRE BELL LOCATION

The fire bell shall be pedestal mounted on the right side cab corner on a polished stainless steel bracket.

FRONT BUMPER TOW HOOKS

Two (2) heavy duty tow hooks, painted to match the frame components, shall be installed behind the front bumper in the forward position, bolted directly to the side of each chassis frame rail with grade 8 bolts.

FRONT BUMPER TOW EYES

The chassis shall include two (2) chrome plated tow eyes which are designed for mounting through the front bumper in the ship loose items. The tow eyes shall be fabricated from 0.75 inch thick #1020 ASTM-36 hot rolled steel. The inside diameter of the tow eye shall be 2.00 inch and have inside/outside chamfered edges.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB TILT SYSTEM

The entire cab shall be capable of tilting approximately 45-degrees to allow for easy maintenance of the engine and transmission. The cab tilt pump assembly shall be located on the right side of the chassis above the battery box.

The electric-over-hydraulic lift system shall include an ignition interlock and red cab lock down indicator lamp on the tilt control which shall illuminate when holding the "Down" button to indicate safe road operation.

It shall be necessary to activate the master battery switch and set the parking brake in order to tilt the cab. As a third precaution the ignition switch must be turned off to complete the cab tilt interlock safety circuit.

Two (2) spring-loaded hydraulic hold down hooks located outboard of the frame shall be installed to hold the cab securely to the frame. Once the hold-down hooks are set in place, it shall take the application of pressure from the hydraulic cab tilt lift pump to release the hooks.

Two (2) cab tilt cylinders shall be provided with velocity fuses in each cylinder port. The cab tilt pivots shall be 1.90 inch ball and be anchored to frame brackets with 1.25 inch diameter studs.

A steel safety channel assembly, painted safety yellow shall be installed on the right side cab lift cylinder to prevent accidental cab lowering. The safety channel assembly shall fall over the lift cylinder when the cab is in the fully tilted position. A cable release system shall also be provided to retract the safety channel assembly from the lift cylinder to allow the lowering of the cab.

CAB TILT AUXILIARY PUMP

A manual cab tilt pump module shall be attached to the cab tilt pump housing.

CAB TILT LIMIT SWITCH

A cab tilt limit switch shall be installed. The switch will effectively limit the travel of the cab when being tilted. The limit adjustment of the switch shall be preset by the chassis manufacturer to prevent damage to the cab or any bumper mounted option mounted in the cab tilt arc. Further adjustment to the limit by the apparatus manufacturer shall be available to accommodate additional equipment.

CAB TILT CONTROL RECEPTACLE

The cab tilt control cable shall include a receptacle which shall be temporarily located on the right hand chassis rail rear of the cab to provide a place to plug in the cab tilt remote control pendant. The tilt pump shall include 8.00 feet of cable with a six (6) pin Deutsch receptacle with a cap.

The remote control pendant shall include 20.00 feet of cable with a mating Deutsch connector. The remote control pendant shall be shipped loose with the chassis.

CAB TILT LOCK DOWN INDICATOR

The cab dash shall include a message located within the dual air pressure gauge which shall alert the driver when the cab is unlocked and ajar. The alert message shall cease to be displayed when the cab is in the fully lowered position and the hold down hooks are secured and locked to the cab mounts.

In addition to the alert message an audible alarm shall sound when the cab is unlocked and ajar and the parking brake is released.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB WINDSHIELD

The cab windshield shall have a surface area of 2969.88 square inches and be of a two (2) piece wraparound design for maximum visibility.

The glass utilized for the windshield shall include standard automotive tint. The left and right windshield shall be fully interchangeable thereby minimizing stocking and replacement costs.

Each windshield shall be installed using black self locking window rubber.

GLASS FRONT DOOR

The front cab doors shall include a window which is 27.00 inches in width X 26.00 inches in height. These windows shall have the capability to roll down completely into the door housing. This shall be accomplished manually utilizing a crank style handle on the inside of the door. A reinforced window regulator assembly shall be provided for severe duty use.

There shall be an irregular shaped fixed window which shall measure 2.50 inches wide at the top, 8.00 inches wide at the bottom X 26.00 inches in height, more commonly known as "cozy glass" ahead of the front door roll down windows.

The windows shall be mounted within the frame of the front doors trimmed with a black anodized ring on the exterior.

GLASS TINT FRONT DOOR

The windows located in the left and right front doors shall include a dark gray automotive tint which shall allow forty-five percent (45%) light transmittance. The dark tint shall aid in cab cooling and help protect passengers from radiant solar energy.

GLASS REAR DOOR RH

The rear right hand side door shall include a window which is 27.00 inches in width X 26.00 inches in height. This window shall roll up and down manually utilizing a crank style handle on the inside of the door. A reinforced window regulator assembly shall be provided for severe duty use.

GLASS TINT REAR DOOR RIGHT HAND

The window located in the right hand side rear window shall include a dark gray automotive tint which shall allow forty-five percent (45%) light transmittance. The dark tint shall aid in cab cooling and help protect passengers from radiant solar energy.

GLASS REAR DOOR LH

The rear left hand side door shall include a window which is 27.00 inches in width X 26.00 inches in height. This window shall roll up and down manually utilizing a crank style handle on the inside of the door. A reinforced window regulator assembly shall be provided for severe duty use.

GLASS TINT REAR DOOR LEFT HAND

The window located in the left hand side rear door shall include a dark gray automotive tint which shall allow forty-five percent (45%) light transmittance. The dark tint shall aid in cab cooling and help protect passengers from radiant solar energy.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

GLASS SIDE MID RH

The cab shall include a window on the right side behind the front and ahead of the crew door which shall measure 16.00 inches wide X 26.00 inches high. This window shall be fixed within this space and shall be rectangular in shape. The window shall be mounted using self locking window rubber. The glass utilized for this window shall include a green automotive tint unless otherwise noted.

GLASS TINT SIDE MID RIGHT HAND

The window located on the right hand side of the cab between the front and rear doors shall include a dark gray automotive tint which shall allow forty-five percent (45%) light transmittance. The dark tint shall aid in cab cooling and help protect passengers from radiant solar energy.

GLASS SIDE MID LH

The cab shall include a window on the left side behind the front door and ahead of the crew door and above the wheel well which shall measure 16.00 inches wide X 26.00 inches high. This window shall be fixed within this space and shall be rectangular in shape. The window shall be mounted using self locking window rubber. The glass utilized for this window shall include a green automotive tint unless otherwise noted.

GLASS TINT SIDE MID LEFT HAND

The window located on the left hand side of the cab between the front and rear doors shall include a dark gray automotive tint which shall allow forty-five percent (45%) light transmittance. The dark tint shall aid in cab cooling and help protect passengers from radiant solar energy.

CLIMATE CONTROL

A ceiling mounted combination defroster and cabin heating and air conditioning system shall be located above the engine tunnel area. The system covers and plenums shall be of severe duty design made of aluminum which shall be coated with a customer specified interior paint. The design of the system's covers shall provide quick access to washable air intake filters as well as easy access to other serviceable items.

The air delivery plenums provide targeted airflow directly to the vehicle occupants. Six (6) adjustable louvers will provide comfort for the front seat occupants and ten (10) adjustable louvers will provide comfort for the rear crew occupants.

The system shall be capable of producing up to 12 FPM of air velocity at all occupant seating positions. Separate front and rear blower motors shall be of brushless design and shall be controlled independently. It shall be capable of reducing the interior cabin air temperature from 122° F (+/- 3° F) to 80° F in thirty minutes with 50% relative humidity and full solar load as described in SAE J2646.

The system shall also provide heater pull up performance which meets or exceeds the performance requirements of SAE J1612 as well as defrost performance that meets or exceeds the performance requirements of SAE J381.

A gravity drain system shall be provided that is capable of evacuating condensate from the vehicle while on a slope of up to a 13% grade in any direction.

The air conditioning system plumbing shall be a mixture of custom bent zinc coated steel fittings and Aeroquip flexible hose with Aeroquip EZ-Clip fittings.

The overhead heater/defroster plumbing shall include an electronic flow control valve that re-directs hot coolant away from the evaporator, via a bypass loop, as the temperature control is moved toward the cold position.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Any component which needs to be accessed to perform system troubleshooting shall be accessible by one person using basic hand tools. Regularly serviced items shall be replaceable by one person using basic hand tools.

*****Spartan Motors Inc. recommends that the overall climate system performance be based off third-party testing in accordance to Society of Automotive Engineering standards as a complete system.***

Individual component level BTU ratings is not an accurate indicator of the performance capability of the completed system. System individual component BTU ratings:

- Air conditioning evaporator total BTU/HR: 82,000
- Air conditioning condenser total BTU/HR: 59,000
- Heater coil total BTU/HR: 98,000

Performance data specified is based on testing performed by an independent third-party test facility using a medium four-door 10" Raised roof Gladiator chassis equipped with an ISL engine.

CLIMATE CONTROL DRAIN

The climate control system shall include a gravity drain for water management. The gravity drain shall remove condensation from the air conditioning system without additional mechanical assistance.

CLIMATE CONTROL ACTIVATION

The heating, defrosting and air conditioning controls shall be in the center dash center switch panel, in a position which is easily accessible to the driver. The climate control shall be activated by a rotary switch.

HVAC OVERHEAD COVER PAINT

The overhead HVAC cover shall be painted with a multi-tone black-black texture finish.

A/C CONDENSER LOCATION

A roof mounted A/C condenser shall be installed centered on the cab forward of the raised roof against the slope rise.

A/C COMPRESSOR

The air-conditioning compressor shall be a belt driven, engine mounted compressor. The compressor shall be compatible with R134-a refrigerant.

*****Spartan Motors Inc. recommends that the overall climate system performance be based off third-party testing in accordance to Society of Automotive Engineering standards as a complete system.***

Individual component level ratings are not an accurate indicator of the performance capability of the completed system.

Refrigerant Compressor displacement: 19.1 cubic inches per revolution.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

UNDER CAB INSULATION

The underside of the cab tunnel surrounding the engine shall be lined with multi-layer insulation, engineered for application inside diesel engine compartments.

The insulation shall act as a noise barrier, absorbing noise thus keeping the decibel level in the cab well within NFPA recommendations. As an additional benefit, the insulation shall assist in sustaining the desired temperature within the cab interior.

The engine tunnel insulation shall measure approximately 0.30 inch thick including a multi-layer foil faced glass cloth and polyester fiber layer. The foil surface acts as protection against heat, moisture and other contaminants. The insulation shall meet or exceed FMVSS 302 flammability test.

The insulation shall be cut precisely to fit each section and sealed for additional heat and sound deflection. The insulation shall be held in place by acrylic pressure sensitive adhesive.

INTERIOR TRIM FLOOR

The floor of the cab shall be covered with a multi-layer mat consisting of 0.25 inch thick sound absorbing closed cell foam with a 0.06 inch thick non-slip vinyl surface with a pebble grain finish. The covering shall be held in place by a pressure sensitive adhesive and aluminum trim molding. All exposed seams shall be sealed with silicone caulk matching the color of the floor mat to reduce the chance of moisture and debris retention.

INTERIOR TRIM

The cab interior shall include trim on the front ceiling, rear crew ceiling, and the cab walls. It shall be easily removable to assist in maintenance. The trim shall be constructed of insulated vinyl over a hard board backing.

REAR WALL INTERIOR TRIM

The rear wall of the cab shall be trimmed with vinyl.

HEADER TRIM

The cab interior shall feature header trim over the driver and officer dash constructed of 5052-H32 Marine Grade, 0.13 inch thick aluminum.

TRIM CENTER DASH

The main center dash area shall be constructed of 5052-H32 Marine Grade, 0.13 inch thick aluminum plate. There shall be four (4) holes located on the top of the dash near each outer edge of the electrical access cover for ventilation. The center dash electrical access cover shall include a gas cylinder stay which shall hold the cover open during maintenance.

TRIM LH DASH

The left hand dash shall be constructed of 5052-H32 Marine Grade, 0.13 inch thick aluminum plate for a perfect fit around the instrument panel. For increased occupant protection the extreme duty left hand dash utilizes patent pending break away technology to reduce rigidity in the event of a frontal crash. The left hand dash shall offer lower vertical surface area to the left and right of the steering column to accommodate control panels.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TRIM RH DASH

The right hand dash shall be constructed of 5052-H32 Marine Grade, 0.13 of an inch thick aluminum plate and shall include a glove compartment with a hinged door and a Mobile Data Terminal (MDT) provision. The glove compartment size will measure 14.00 inches wide X 6.38 inches high X 5.88 inches deep. The MDT provision shall be provided above the glove compartment.

ENGINE TUNNEL TRIM

The cab engine tunnel shall be covered with a multi-layer mat consisting of 0.25 inch thick sound absorbing closed cell foam with a 0.06 inch thick non-slip vinyl surface with a pebble grain finish. The covering shall be held in place by a pressure sensitive adhesive.

The cab engine tunnel shall have an overlay of 5052-H32 aluminum plate which shall feature a Spar-Liner spray on bedliner coating, colored to match the cab paint interior finish color scheme. The aluminum plate shall be held down with screws. All exposed seams shall be sealed with silicone caulk matching the color of the floor mat to reduce the chance of moisture and debris retention.

POWER POINT DASH MOUNT

The cab shall include one (1) 12 volt cigarette lighter type receptacles in the switch panel to provide a power source for 12 volt electrical equipment. The cab shall also include two (2) Blue Sea dual universal serial bus (USB) charging receptacles in the cab dash to provide a power source for USB chargeable electrical equipment. The USB ports shall be capable of a 5 Volt-2.1 amp total output. The receptacles shall be wired battery direct.

STEP TRIM

Each cab entry door shall include a three step entry. The first step closest to the ground shall be constructed of polished 5032 H32 aluminum Grip Strut® grating with angled outer corners. The step shall feature a splash guard to reduce water and debris from splashing in to the step. The splash guard shall have an opening on the outer edge to allow debris and water to flow through rather than becoming trapped within the stepping surface. The lower step shall be mounted to a frame which is integral with the construction of the cab for rigidity and strength. The middle step shall be integral with the cab construction and shall be trimmed with a Flex-Tred® adhesive grit surface material.

UNDER CAB ACCESS DOOR

The cab shall include an aluminum access door in the left crew step riser painted to match the cab interior paint with a push and turn latch. The under cab access door shall provide access to the diesel exhaust fluid fill.

INTERIOR DOOR TRIM

The interior trim on the doors of the cab shall consist of an aluminum panel constructed of Marine Grade 5052-H32 0.13 of an inch thick aluminum plate. The door panels shall include a painted finish.

DOOR TRIM KICKPLATE

The inner door panels shall include a DA sanded kick plate which shall be fastened to the lower portion of the door panels.

DOOR TRIM SCUFF PLATE

The trim along the door shall include a stainless steel scuff plate along the door jamb to prevent the chipping of paint should the seat belt buckle come in contact with the door jamb.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

DOOR TRIM CUSTOMER NAMEPLATE

The interior door trim on the front doors shall include a customer nameplate which states the vehicle was custom built for their Department.

CAB DOOR TRIM REFLECTIVE

The interior of each door shall include high visibility reflective tape. A white reflective tape shall be provided vertically along the outer rear edge of the door. The lowest portion of each door skin shall include a reflective tape chevron with red and white stripes. The chevron tape shall measure 6.00 inches in height.

INTERIOR GRAB HANDLE "A" PILLAR

There shall be two (2) rubber covered 11.00 inch grab handles installed inside the cab, one on each "A" post at the left and right door openings. The left handle shall be located 7.88 inches above the bottom of the door window opening and the right handle shall be located 2.88 inches above the bottom of the door window opening. The handles shall assist personnel in entering and exiting the cab.

INTERIOR GRAB HANDLE FRONT DOOR

Each front door shall include one (1) ergonomically contoured 9.00 inch cast aluminum handle mounted horizontally on the interior door panels. The handles shall feature a textured red finish to assist personnel entering and exiting the cab.

INTERIOR GRAB HANDLE REAR DOOR

A cast aluminum assist handle shall be provided on the inside of each rear crew door. A 30.00 inch long handle shall extend horizontally the width of the window just above the window sill. The handle shall include a textured red finish and assist personnel in exiting and entering the cab.

INTERIOR REAR WALL COMPARTMENT

The cab shall include an interior clear area provision for the side curtain crew airbag mounting to account for a compartment located on the right side at the rear wall to be installed by the body builder. The clear area shall extend from behind the standard rear door location to the rear wall. The provision allows appropriate airbag selection for clear airbag deployment and adequate protection and ejection mitigation.

INTERIOR SOFT TRIM COLOR

The cab interior soft trim surfaces shall be black in color.

INTERIOR TRIM SUNVISOR

The header shall include two (2) sun visors, one each side forward of the driver and officer seating positions above the windshield. Each sun visor shall be constructed of Masonite and covered with padded vinyl trim.

INTERIOR FLOOR MAT COLOR

The cab interior floor mat shall be black in color.

CAB PAINT INTERIOR DOOR TRIM

The inner door panel surfaces shall be painted with multi-tone black/black texture finish.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

HEADER TRIM INTERIOR PAINT

The metal surfaces in the header area shall be coated with multi-tone black-black texture finish.

TRIM CENTER DASH INTERIOR PAINT

The entire center dash shall be coated with multi-tone black-black texture finish. Any accessory pods attached to the dash shall also be painted this color.

TRIM LH DASH INTERIOR PAINT

The left hand dash shall be painted with a multi-tone black-black texture finish.

TRIM RIGHT HAND DASH INTERIOR PAINT

The right hand dash shall be painted with multi-tone black-black texture finish.

DASH PANEL GROUP

The main center dash area shall include three (3) removable panels located one (1) to the right of the driver position, one (1) in the center of the dash and one (1) to the left of the officer position. The center panel shall be within comfortable reach of both the driver and officer.

SWITCHES CENTER PANEL

The center dash panel shall include six (6) switch positions in the upper left portion of the panel.

A rocker switch with a blank legend installed directly above shall be provided for any position without a switch and legend designated by a specific option. The non-specified switches shall be two-position, black switches with a green indicator light. Each blank switch legend can be custom engraved by the body manufacturer. All switch legends shall have backlighting provided.

SWITCHES LEFT PANEL

The left dash panel shall include five (5) switches in a three (3) over two (2) staggered switch configuration. Two (2) rocker switches, one (1) headlight switch, one (1) windshield wiper/washer control switch and one (1) instrument lamp dimmer switch shall be provided.

A rocker switch with a blank legend installed directly above shall be provided for any position not designated by a specific option. The non-designated switches shall be two-position, black switches with a green indicator light. Each blank switch legend can be custom engraved by the body manufacturer. All switch legends shall have backlighting provided.

SWITCHES RIGHT PANEL

The right dash panel shall include no rocker switches or legends.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SEAT BELT WARNING

A Weldon seat belt warning system, integrated with the Vehicle Data Recorder system, shall be installed for each seat within the cab. The system shall provide a visual warning indicator in the Vista display and control screen(s), an indicator light in the instrument panel, and an audible alarm.

The warning system shall activate when any seat is occupied with a minimum of 60 pounds, the corresponding seat belt remains unfastened, and the park brake is released. The warning system shall also activate when any seat is occupied, the corresponding seat belt was fastened in an incorrect sequence, and the park brake is released. Once activated, the visual indicators and audible alarm shall remain active until all occupied seats have the seat belts fastened.

SEAT MATERIAL

The Bostrom Firefighter seats shall include a covering of extra high strength, wear resistant fabric made of durable Durawear Plus™ ballistic polyester. A PVC coating shall be bonded to the back side of the material to help protect the seats from UV rays and from being saturated or contaminated by fluids. Durawear Plus™ meets or exceeds specification of the common trade name Imperial 1800. The material meets FMVSS 302 flammability requirements.

If applicable, Theatre style seats located in the cab shall be high strength, wear resistant fabric made of durable ballistic polyester. A PVC coating shall be bonded to the back side of the material to help protect the seats from UV rays and from being saturated or contaminated by fluids. Common trade names for this material are Imperial 1200 and Durawear.

SEAT COLOR

All seats supplied with the chassis shall be black in color. All seats shall include red seat belts.

SEAT BACK LOGO

The seat backs shall include the logo for the OEM body manufacturer. The logo shall be centered on the standard headrest of the seat back and on the left side of a split headrest.

SEAT DRIVER

The driver's seat shall be an H.O. Bostrom 500 Series Firefighter Sierra model seat. The seat shall feature eight-way electric positioning. The eight positions shall include up and down, fore and aft with 8.00 inches of travel, back angle adjustment and seat rake adjustment. The seat shall feature integral springs to isolate shock.

The seat shall feature an all belts to seat (ABTS) style of safety restraint. The ABTS feature shall include a three-point shoulder harness with the lap belt, automatic retractor and buckle as an integral part of the seat assembly. The ABTS feature shall also include the RiteHite™ shoulder adjustment feature to provide enhanced comfort and safety by allowing customized seat belt fit.

The minimum vertical dimension from the seat H-point to the ceiling for this belted seating position shall be 35.00 inches measured with the seat height adjusted to the lowest position of travel.

This model of seat shall have successfully completed the static load tests set forth by FMVSS 207, 209, and 210 in effect at the time of manufacture. This testing shall include a simultaneous forward load of 3000 pounds each on the lap and shoulder belts and twenty (20) times the weight through the center of gravity.

The materials used in construction of the seat shall also have successfully completed testing with regard to the flammability of materials used in the occupant compartments of motor vehicles as outlined in FMVSS 302, of which dictates the allowable burning rate of materials in the occupant compartments of motor vehicles.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SEAT BACK DRIVER

The driver's seat shall include a standard seat back incorporating the all belts to seat feature (ABTS). The seat back shall feature a contoured head rest.

SEAT MOUNTING DRIVER

The driver's seat shall be installed in an ergonomic position in relation to the cab dash.

OCCUPANT PROTECTION DRIVER

The driver's position shall be equipped with the Advanced Protection System™ (APS). The APS shall selectively deploy integrated systems to protect against injuries in qualifying frontal impact, side impact, and rollover events. The increase in survivable space and security of the APS shall also provide ejection mitigation protection.

The driver's seating area APS shall include:

- Advanced seat belt system - retractor pre-tensioner tightens the seat belt around the driver, securing the occupant in the seat and the load limiter plays out some of the seat belt webbing to reduce seat belt to chest and torso force upon impact as well as mitigate head and neck injuries.
- Large side curtain airbag - protects the driver's head, neck, and upper body from dangerous cab side surfaces and contact points with intrusive surfaces as a result of a collision as well as provides ejection mitigation protection to the driver in a qualifying event by covering the window and the upper portion of the door.
- Dual knee airbags (patent pending) with energy management mounting (patent pending) - protects the driver's lower body from dangerous surface contact injuries, acceleration injuries, and from intrusion as well as locks the lower body in place so the upper body shall be slowed by the load limiting seat belt.

Steering wheel airbag - protects the driver's head, neck, and upper torso from contact injuries, acceleration injuries, and contact points with intrusive surfaces as a result of a collision.

SEAT OFFICER

The officer's seat shall be an H.O. Bostrom 500 Series Sierra model seat. The seat shall feature eight-way electric positioning. The eight positions shall include up and down, fore and aft with 8.00 inches of travel, back angle adjustment and seat rake adjustment. The seat shall feature integral springs to isolate shock.

The seat shall feature an all belts to seat (ABTS) style of safety restraint. The ABTS feature shall include a three-point shoulder harness with the lap belt, automatic retractor and buckle as an integral part of the seat assembly. The ABTS feature shall also include the RiteHite™ shoulder adjustment feature to provide enhanced comfort and safety by allowing customized seat belt fit.

The minimum vertical dimension from the seat H-point to the ceiling for this belted seating position shall be 35.00 inches measured with the seat height adjusted to the lowest position of travel.

This model of seat shall have successfully completed the static load tests set forth by FMVSS 207, 209, and 210 in effect at the time of manufacture. This testing shall include a simultaneous forward load of 3000 pounds each on the lap and shoulder belts and twenty (20) times the weight through the center of gravity.

The materials used in construction of the seat shall also have successfully completed testing with regard to the flammability of materials used in the occupant compartments of motor vehicles as outlined in FMVSS 302, of which dictates the allowable burning rate of materials in the occupant compartments of motor vehicles.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SEAT BACK OFFICER

The officer's seat shall include a standard seat back incorporating the all belts to seat feature (ABTS). The seat back shall feature a contoured head rest.

SEAT MOUNTING OFFICER

The officer's seat shall be installed in an ergonomic position in relation to the cab dash.

OCCUPANT PROTECTION OFFICER

The officer's position shall be equipped with the Advanced Protection System™ (APS). The APS shall selectively deploy integrated systems to protect against injuries in qualifying frontal impact, side impact, and rollover events. The increase in survivable space and security of the APS shall also provide ejection mitigation protection.

The officer's seating area APS shall include:

- Advanced seat belt system - retractor pre-tensioner tightens the seat belt around the officer, securing the occupant in the seat and the load limiter plays out some of the seat belt webbing to reduce seat belt to chest and torso force upon impact as well as mitigate head and neck injuries.
- Large side curtain airbag - protects the officer's head, neck, and upper body from dangerous cab side surfaces and contact points with intrusive surfaces as a result of a collision as well as provides ejection mitigation protection to the officer in a qualifying event by covering the window and the upper portion of the door.

Knee airbags - protects the officer's lower body from dangerous surface contact injuries, acceleration injuries, and from contact points with intrusive surfaces as a result of a collision as well as locks the lower body in place so the upper body shall be slowed by the load limiting seat belt.

POWER SEAT WIRING

The power seat or seats installed in the cab shall be wired directly to battery power.

SEAT BELT ORIENTATION CREW

The crew position seat belts shall follow the standard orientation which extends from the outboard shoulder extending to the inboard hip.

SEAT REAR FACING OUTER LOCATION

The crew area shall include two (2) rear facing crew seats, which include one (1) located directly behind the left side front seat and one (1) located directly behind the right side front seat.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SEAT CREW REAR FACING OUTER

The crew area shall include a seat in the rear facing outboard position which shall be a H.O. Bostrom 500 Series Firefighter model seat. The seat shall feature a tapered and padded seat, and cushion. The seat shall be mounted in a fixed position.

The seat shall feature an all belts to seat (ABTS) style of safety restraint. The ABTS feature shall include a three-point shoulder harness with the lap belt and automatic retractor as an integral part of the seat assembly. The buckle portion of the seat belt shall extend from the seat base towards the driver position within easy reach of the occupant. The ABTS feature shall also include the RiteHite™ shoulder adjustment feature to provide enhanced comfort and safety by allowing customized seat belt fit.

The minimum vertical dimension from the seat H-point to the ceiling for this belted seating position shall be 35.00 inches.

This model of seat shall have successfully completed the static load tests by FMVSS 207/210. This testing shall include a simultaneous forward load of 3000 pounds each on the lap and shoulder belts and twenty (20) times the weight through the center of gravity. This model of seat installed in the cab model, as specified, shall have successfully completed the dynamic sled testing using FMVSS 208 as a guide with the following accommodations. In order to reflect the larger size outfitted firefighters, the test dummy used shall be a 95th percentile hybrid III male weighing 225 pounds rather than the 50th percentile male dummy weighing 165 pounds as referenced in FMVSS 208. The model of seats shall also have successfully completed the flammability of materials used in the occupant compartments of motor vehicles as outlined in FMVSS 302, of which decides the burning rate of materials in the occupant compartments of motor vehicles.

SEAT BACK REAR FACING OUTER

The rear facing outboard seat shall feature a Bostrom SecureAll™ self contained breathing apparatus (SCBA) locking system which shall store most U.S. and International SCBA brands and bottle sizes while in transit or for storage within the seat back. The bracket shall be easily adjustable for all SCBA brands and cylinder diameters. All adjustment points shall utilize similar hardware and adjustments shall be made with one tool.

The bracket shall be adjustable to compensate for different cylinder lengths without the use of tools. The adjustment shall be made by raising a lever and moving the top clamp vertically.

The bracket system shall be free of straps that may interfere with auxiliary equipment on SCBA units. The center guide fork shall keep the SCBA tank in place for a safe and comfortable fit in the seat back cavity. The SCBA unit simply needs to be pushed against the pivot arm to engage the patented auto-locking system. Once the lock is engaged, the top clamp shall surround the top of the SCBA tank for a secure fit in all directions.

The SecureAll™ shall include a release handle which shall be integrated into the center of the bottom seat cushion for easy access and to eliminate hooking the release handle with clothing or other equipment.

The seat back shall include a removable padded cover which shall be provided over the SCBA cavity.

SEAT MOUNTING REAR FACING OUTER

The rear facing outer seats shall offer special mounting positions which shall be 2.00 inches towards the rear wall offering additional space between the front seats and the outer rear facing seats.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

OCCUPANT PROTECTION RFO

The rear facing outer seat position(s) shall be equipped with the Advanced Protection System™ (APS). The APS shall selectively deploy integrated systems to protect against injuries in qualifying frontal impact, side impact, and rollover events. The increase in survivable space and security of the APS shall also provide ejection mitigation protection.

Each rear facing outer seating position APS shall include:

- APS advanced seat belt system - retractor pre-tensioners tighten the seat belts around each occupant, securing the occupants in seats and load limiters play out some of the seat belt webbing to reduce seat belt to chest and torso force upon impact as well as mitigate head and neck injuries.

Side curtain airbag - protects each occupant's head, neck, and upper body from dangerous cab side surfaces and contact points with intrusive surfaces as a result of a collision as well as provides ejection mitigation protection to each occupant in a qualifying event by covering the windows and walls adjacent to each seating position with an airbag custom designed for each cab configuration.

SEAT REAR FACING CENTER LOCATION

The crew area shall include one (1) rear facing crew seat located directly behind the engine tunnel in the center of the cab.

SEAT CREW REAR FACING CENTER

The crew area shall include a seat in the rear facing center position which shall be a H.O. Bostrom 500 Series Firefighter model seat. The seat shall feature a tapered and padded seat, and cushion. The seat and cushion shall be spring load hinged and compact in design for additional room. The seat shall include a "Fold and Hold" feature so that the cushion shall remain in the seated position and simply touched to flip up.

The seat shall feature an all belts to seat (ABTS) style of safety restraint. The ABTS feature shall include a three-point shoulder harness with the lap belt and automatic retractor as an integral part of the seat assembly. The buckle portion of the seat belt shall extend from the seat base towards the driver position within easy reach of the occupant. The ABTS feature shall also include the RiteHite™ shoulder adjustment feature to provide enhanced comfort and safety by allowing customized seat belt fit.

The minimum vertical dimension from the seat H-point to the ceiling for each belted seating position shall be 35.00 inches.

This model of seat shall have successfully completed the static load tests by FMVSS 207/210. This testing shall include a simultaneous forward load of 3000 pounds each on the lap and shoulder belts and twenty (20) times the weight through the center of gravity. This model of seat installed in the cab model, as specified, shall have successfully completed the dynamic sled testing using FMVSS 208 as a guide with the following accommodations. In order to reflect the larger size outfitted firefighters, the test dummy used shall be a 95th percentile hybrid III male weighing 225 pounds rather than the 50th percentile male dummy weighing 165 pounds as referenced in FMVSS 208. The model of seats shall also have successfully completed the flammability of materials used in the occupant compartments of motor vehicles as outlined in FMVSS 302, of which decides the burning rate of materials in the occupant compartments of motor vehicles.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SEAT BACK REAR FACING CENTER

The rear facing center seat shall feature a SecureAll™ self contained breathing apparatus (SCBA) locking system which shall be one bracket model and store most U.S. and International SCBA brands and sizes while in transit or for storage within the seat back. The bracket shall be easily adjustable for all SCBA brands and cylinder diameters. All adjustment points shall utilize similar hardware and adjustments shall be made with one tool.

The bracket shall be adjustable to compensate for different cylinder lengths without the use of tools. The adjustment shall be made by raising a lever and moving the top clamp vertically.

The bracket system shall be free of straps and clamps that may interfere with auxiliary equipment on SCBA units. The center guide fork shall keep the SCBA tank in place for a safe and comfortable fit in the seat back cavity. The SCBA unit simply needs to be pushed against the pivot arm to engage the patented auto- locking system. Once the lock is engaged, the top clamp shall surround the top of the SCBA tank for a secure fit in all directions.

The SecureAll™ shall include a release handle which shall be integrated into the seat cushion for quick and easy release. This shall eliminate the need for straps or pull cords to interfere with other SCBA equipment.

The seat back shall include a removable padded cover which shall be provided over the SCBA cavity.

SEAT MOUNTING REAR FACING CENTER

The rear facing center seat shall be mounted facing the rear of the cab.

OCCUPANT PROTECTION RFC

The rear facing center seat position(s) shall be equipped with the Advanced Protection System™ (APS). The APS shall selectively deploy integrated systems to protect against injuries in qualifying frontal impact, side impact, and rollover events. The increase in survivable space and security of the APS shall also provide ejection mitigation protection.

Each rear facing center seating position APS shall include:

- APS advanced seat belt system - retractor pre-tensioners tighten the seat belts around each occupant, securing the occupants in seats and load limiters play out some of the seat belt webbing to reduce seat belt to chest and torso force upon impact as well as mitigate head and neck injuries.

Side curtain airbag - provides ejection mitigation protection to each occupant in a qualifying event by covering the windows and walls adjacent to crew seating with an airbag custom designed for each cab configuration.

SEAT FRAME REAR FACING CENTER

The rear facing center seating shall include a seat frame which is located and installed behind the engine tunnel. The seat frame shall measure 46.15 inches wide X 12.00 inches high X 15.88 inches deep. The seat frame shall be constructed of 0.19 inch thick Marine Grade 5052-H32 smooth aluminum plate. The seat box shall be painted with the same color as the remaining interior.

SEAT FRAME REAR FACING CENTER STORAGE ACCESS

The rear facing center seat frame shall include a storage access opening which shall measure 32.00 inches wide X 8.75 inches high to allow access within the seat frame for storage. A solid access door which shall measure 34.00 inches wide X 11.12 inches high shall be provided at the opening.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB FRONT UNDERSEAT STORAGE ACCESS

The left and right under seat storage areas shall have a solid aluminum hinged door with non-locking latch.

SEAT COMPARTMENT DOOR FINISH

All underseat storage compartment access doors shall have a multi-tone black-black texture finish.

WINDSHIELD WIPER SYSTEM

The cab shall include a triple arm linkage wiper system which shall clear the windshield of water, ice and debris. There shall be two (2) windshield wipers; each shall be affixed to a radial arm. The wiper motor shall be activated by an intermittent wiper control located within easy reach of the driver's position.

ELECTRONIC WINDSHIELD FLUID LEVEL INDICATOR

The windshield washer fluid level shall be monitored electronically. When the washer fluid level becomes low the yellow "Check Message Center" indicator light on the instrument panel shall illuminate and the message center in the dual air pressure gauge shall display a "Check Washer Fluid Level" message.

CAB DOOR HARDWARE

The cab entry doors shall be equipped with exterior pull handles, suitable for use while wearing firefighter gloves. The handles shall be made of aluminum with a chrome plated finish.

The interior exit door handles shall be flush paddle type with a black finish, which are incorporated into the upper door panel.

All cab entry doors shall include locks which are keyed alike. The door locks shall be designed to prevent accidental lockout.

The exterior pull handles shall include a scuff plate behind the handle constructed of polished stainless steel to help protect the cab finish.

DOOR LOCKS

Each cab entry door shall include a manually operated door lock. Each door lock may be actuated from the inside of the cab by means of a red knob located on the paddle handle of the respective door or by using a TriMark key from the exterior. The door locks are designed to prevent accidental lock out.

DOOR LOCK LH REAR CAB COMPARTMENT

The left hand side rear compartment shall feature a manual door lock.

DOOR LOCK RH REAR CAB COMPARTMENT

The right hand side rear compartment shall feature a manual door lock.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

GRAB HANDLES

The cab shall include one (1) 18.00 inch three-piece knurled aluminum anti-slip exterior grab handle behind each cab door. The Hansen Lit Anti-Slip Rails shall be mounted in bright anodized aluminum 4000 Series II stanchions, complete with weep holes to prevent the buildup of moisture.

The grab rails shall include a 12 volt, 17.00 inch long red LED light to provide an increased margin of safety for night time cab entry and egress. The lights shall only be activated when the parking brake is set, and the ignition is on.

AUXILIARY GRAB HANDLE

There shall be a 7.00 inch molded grab handle with a black finish attached to the front fascia of the cab above the right side headlight.

REARVIEW MIRRORS

Ramco model CRM-310-1350-PCHR bus style mirrors shall be provided. The mirror heads shall be injection molded chrome plated ABS plastic and shall measure 9.75 inches wide X 13.50 inches high. The mirrors shall be mounted one (1) on each the driver and officer doors of the cab with polished die-cast aluminum arms.

The mirrors shall feature an upper heated remote controlled flat glass and a lower heated remote controlled convex glass. The mirror control switches shall be located within easy reach of the driver. The mirrors shall be manufactured using the finest quality non-glare glass and shall feature a rigid mounting thereby reducing vibration. The mirrors shall be corrosion free under all weather conditions.

REARVIEW MIRROR HEAT SWITCH

The heat for the rearview mirrors shall be controlled through a virtual button on the Vista display and control screen.

CAB FENDER

Full width wheel well liners shall be installed on the extruded cab to limit road splash and enable easier cleaning. Each two-piece liner shall consist of an inner liner 16.00 inches wide made of vacuum formed ABS composite and an outer fenderette 3.50 inches wide made of SAE 304 polished stainless steel.

MUD FLAPS FRONT

The front wheel wells shall have mud flaps installed on them. The mud flaps shall extend from the outer edge of the wheel well to the inner edge of the wheel well to provide additional protection from road spray.

CAB EXTERIOR FRONT & SIDE EMBLEMS

The cab shall include three (3) Spartan emblems. There shall be one (1) installed on the front air intake grille and two (2) for the exterior sides of the cab shipped loose with the chassis for installation by the body manufacturer. The cab shall also include one (1) Advanced Protection System shield emblem on each front door.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

IGNITION

A master battery system with a keyless start ignition system shall be provided. Each system shall be controlled by a one-quarter turn Cole Hersee switch, both of which shall be mounted to the left of the steering wheel on the dash. A chrome push type starter button shall be provided adjacent to the master battery and ignition switches.

Each switch shall illuminate a green LED indicator light on the dash when the respective switch is placed in the "ON" position.

The starter button shall only operate when both the master battery and ignition switches are in the "ON" position.

BATTERY

The single start electrical system shall include six (6) Harris BCI 31 925 CCA batteries with a 210 minute reserve capacity and 4/0 welding type dual path starter cables per SAE J541.

BATTERY TRAY

The batteries shall be installed within two (2) steel battery trays located on the left side and right side of the chassis, securely bolted to the frame rails. The battery trays shall be coated with the same material as the frame.

The battery trays shall include drain holes in the bottom for sufficient drainage of water. A durable, non-conducting, interlocking mat made by Dri-Dek shall be installed in the bottom of the trays to allow for air flow and help prevent moisture build up. The batteries shall be held in place by non-conducting phenolic resin hold down boards.

BATTERY BOX COVER

Each battery box shall include a steel cover which protects the top of the batteries. Each cover shall be coated the same as the frame and shall include flush latches which shall keep the cover secure as well as a black powder coated handle for convenience when opening.

BATTERY CABLE

The starting system shall include cables which shall be protected by 275 degree F. minimum high temperature flame retardant loom, sealed at the ends with heat shrink and sealant.

BATTERY JUMPER STUD

The starting system shall include battery jumper studs. These studs shall be located in the forward most portion of the driver's side lower step, 8.00 inches apart. The studs shall allow the vehicle to be jump started, charged, or the cab to be raised in an emergency in the event of battery failure.

ALTERNATOR

The charging system shall include a 300 amp Delco Remy 40SI 12 volt alternator. The alternator shall include a self-exciting integral regulator.

STARTER MOTOR

The single start electrical system shall include a Delco brand starter motor.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

BATTERY CONDITIONER

A Kussmaul Auto Charge 40 LPC battery conditioner shall be supplied. The battery conditioner shall provide a 40 amp output for the chassis batteries and a 15 amp output circuit for accessory loads. The battery conditioner shall be shipped loose with the cab. The battery conditioner shall include an additional 12.00 feet of coiled wire for relocation by the body manufacturer. This additional wire shall be routed behind the driver's seat.

BATTERY CONDITIONER DISPLAY

A Kussmaul battery conditioner with bar graph display shall be integrated into the electrical inlet.

ELECTRICAL INLET LOCATION

An electrical inlet shall be shipped loose for the OEM to install on the body.

ELECTRICAL INLET

A Kussmaul 20 amp super auto-eject electrical receptacle shall be supplied. It shall automatically eject the plug when the starter button is depressed.

A single item or an addition of multiple items must not exceed the rating of the electric inlet that it's connected to.

ELECTRICAL INLET CONNECTION

The electrical inlet eject feature shall be pre-wired. The prewire shall include a 35.00 foot coil of wire in the area behind the cab on the driver side frame rail for use by an OEM installed electrical inlet.

ELECTRICAL INLET COLOR

The electrical inlet connection shall include a red cover.

HEADLIGHTS

The cab front shall include four (4) rectangular halogen headlamps with separate high and low beams mounted in bright chrome bezels.

FRONT TURN SIGNALS

The front fascia shall include two (2) Whelen model M6 4.00 inch X 6.00 inch amber LED turn signals which shall be installed in a chrome housing above and outboard of the front warning and head lamps.

HEADLIGHT LOCATION

The headlights shall be located on the front fascia of the cab directly below the front warning lights.

SIDE TURN/MARKER LIGHTS

The sides of the cab shall include two (2) Whelen OS LED side marker lights which shall be provided just behind the front cab radius corners.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

MARKER AND ICC LIGHTS

In accordance with FMVSS, there shall be five (5) Whelen Series OS LED cab marker lamps designating identification, center and clearance provided. These lights shall be installed on the face of the cab within full view of other vehicles from ground level.

HEADLIGHT AND MARKER LIGHT ACTIVATION

The headlights and marker lights shall be controlled through a rocker switch within easy reach of the driver. There shall be a dimmer switch within easy reach of the driver to adjust the brightness of the dash lights. The headlamps shall be equipped with the "Daytime Running" light feature, which shall illuminate the headlights to 80% brilliance when the battery master switch is in the "On" position and the parking brake is released.

GROUND LIGHTS

Each door shall include a Tecniq T44 LED ground light mounted to the underside of the cab step below each door. The lights shall include a polycarbonate lens, a housing which is vibration welded and LEDs which shall be shock mounted for extended life. The ground lighting shall be activated by the opening of the door on the respective cab side as well as through a virtual button on the Vista display and control screen.

LOWER CAB STEP LIGHTS

The middle step located at each door shall include a 4.00 inch round Whelen LED recess mounted light which shall activate with the opening of the respective door.

INTERMEDIATE STEP LIGHTS

The intermediate step well area at each door shall include an LED light within a chrome housing. The Egress step lights shall provide visibility to the step well area for the first step exiting the vehicle. The Egress step lights shall activate with Entry step lighting.

LIGHTBAR PROVISION

There shall be one (1) light bar installed on the cab roof. The light bar shall be provided and installed by Spartan Chassis. The light bar installation shall include a lowered mounting that shall place the light bar just above the junction box and wiring to a control switch on the cab dash.

CAB FRONT LIGHTBAR

The lightbar provisions shall be for one (1) Whelen brand Freedom IV LED lightbar mounted centered on the front of the cab roof. The lightbar shall be 60.00 inches in length. The lightbar shall feature twelve (12) red LED light modules and two (2) clear LED light modules. The entire lightbar shall feature a clear lens. The clear lights shall be disabled with park brake engaged. The cable shall exit the lightbar on the right side of the cab.

LIGHTBAR SWITCH

The light bar shall be controlled by a virtual button on the Vista display and control screen. This button shall be clearly labeled for identification.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SIDE SCENE LIGHTS

The cab shall include two (2) Whelen M9 LED scene lights, one (1) each side which shall be surface mounted. The Whelen lights shall provide directional lighting from twenty four (24) Super-LEDs and a clear gradient lens. The scene light shall have specialized TIR optics for ideal scene illumination.

SIDE SCENE LIGHT LOCATION

The scene lighting located on the left and right sides of the cab shall be mounted rearward of the cab "B" pillar in the 10.00 inch raised roof portion of the cab between the front and rear crew doors.

SIDE SCENE ACTIVATION

The scene lights shall be activated by two (2) virtual buttons on the Vista display and control screen(s), one (1) for each light, and by opening the respective side cab doors.

INTERIOR OVERHEAD LIGHTS

The cab shall include a two-section, red and clear Weldon LED dome lamp located over each door. The dome lamps shall be rectangular in shape and shall measure approximately 7.00 inches in length X 3.00 inches in width with a black colored bezel. The clear portion of each lamp shall be activated by opening the respective door and via the multiplex display and both the red and clear portion can be activated by individual push lenses on each lamp.

An additional incandescent three (3) light module with dual map lights shall be located over the engine tunnel which can be activated by individual switches on the lamp.

MAP LIGHTS

A Hella HE-87141 series 19" gooseneck style map light shall be provided. The light shall have a clear bulb and a control switch on the light head. The light shall be located on the right hand side cab "A" pillar above the grab handle in a location that does not interfere with entering or exiting the cab.

ENGINE COMPARTMENT LIGHT

There shall be a LED NFPA compliant light mounted under the engine tunnel for area work lighting on the engine. The light shall include a polycarbonate lens, a housing which is vibration welded and a bulb which shall be shock mounted for extended life. The light shall activate automatically when the cab is tilted.

DO NOT MOVE APPARATUS LIGHT

The front headliner of the cab shall include a flashing red Whelen Ion LED light clearly labeled "Do Not Move Apparatus". In addition to the flashing red light, an audible alarm shall be included which shall sound while the light is activated.

The flashing red light shall be located centered left to right for greatest visibility.

The light and alarm shall be interlocked for activation when either a cab door is not firmly closed or an apparatus compartment door is not closed, and the parking brake is released.

MASTER WARNING SWITCH

A master switch shall be included, as a virtual button on the Vista display and control screen which shall be labeled "E Master" for identification. The button shall feature control over all devices wired through it. Any warning device switches left in the "ON" position when the master switch is activated shall automatically power up.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

HEADLIGHT FLASHER

An alternating high beam headlight flashing system shall be installed into the high beam headlight circuit which shall allow the high beams to flash alternately from left to right.

Deliberate operator selection of high beams will override the flashing function until low beams are again selected. Per NFPA, these clear flashing lights will also be disabled "On Scene" when the park brake is applied.

HEADLIGHT FLASHER SWITCH

The flashing headlights shall be activated through a virtual button on the Vista display and control screen.

INBOARD FRONT WARNING LIGHTS

The cab front fascia shall include two (2) Whelen M6 Super LED front warning lights in the left and right inboard positions. The lights shall feature multiple flash patterns including steady burn for solid colors and multiple flash patterns for split colors. The lights shall be mounted to the front fascia of the cab within a chrome bezel

INBOARD FRONT WARNING LIGHTS COLOR

The warning lights mounted on the cab front fascia in the inboard positions shall be blue on the left and red on the right side.

OUTBOARD FRONT WARNING LIGHTS

The cab front fascia shall include two (2) Whelen M6 Super LED front warning lights in the left and right outboard positions. The lights shall feature multiple flash patterns including steady burn for solid colors and multiple flash patterns for split colors. The lights shall be mounted to the front fascia of the cab within a chrome bezel.

OUTBOARD FRONT WARNING LIGHTS COLOR

The warning lights mounted on the cab front fascia in the outboard position shall be blue on the left side and red light on the right side of the cab.

FRONT WARNING SWITCH

The front warning lights shall be controlled through a virtual control on the Vista display and control screen. This switch shall be clearly labeled for identification.

INTERSECTION WARNING LIGHTS

The chassis shall be prewired for the installation of Weldon LED intersection warning lights. The lights shall be provided and installed by the apparatus manufacturer.

INTERSECTION WARNING LIGHTS COLOR

The intersection lights shall be red.

SIDE AND INTERSECTION WARNING SWITCH

The side warning lights shall be controlled through a virtual button on the Vista display and control screen. This button shall be clearly labeled for identification.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TANK LEVEL LIGHTS

There shall be two (2) Whelen Strip-Light Plus XL tank lights surface mounted within a chrome bezel.

The light strips shall feature four (4) colors of LED lights to indicate the fluid level of a tank. The lights shall change in color to indicate the water level of the tank in ¼ tank increments, the colors shall change from green indicating a full tank to blue, amber, and red as the tank level drops.

TANK LEVEL LIGHTS ACTIVATION

An FRC remote large light driver shall be installed under the dash with the signal wire for the primary display routed to the rear of cab on the chassis.

The light activation shall be active with the park brake set and ignition on.

TANK LEVEL LIGHTS LOCATION

There shall be water level lights mounted on each side of the cab, behind the rear cab doors.

SIREN CONTROL HEAD

A Whelen 295HFS2 electronic siren control head with remote amplifier shall be provided and flush mounted in the switch panel with a location specific to the customer's needs. The siren shall feature 200-watt output, hands free mode and shall be in "standby" mode awaiting instruction. The siren shall offer radio broadcast, public address, wail, yelp, or piercer tones and hands free operation which shall allow the operator to turn the siren on and off from the horn ring if a horn/siren selector switch option is also selected.

HORN BUTTON SELECTOR SWITCH

A rocker switch shall be installed in the switch panel between the driver and officer to allow control of either the electric horn or the air horn from the steering wheel horn button. The electric horn shall sound by default when the selector switch is in either position to meet FMCSA requirements.

AIR HORN ACTIVATION

The air horn activation shall be accomplished by the steering wheel horn button for the driver and a black momentary push button on the switch panel. An air horn activation circuit shall be provided to the chassis harness pump panel harness connector.

MECHANICAL SIREN ACTIVATION

The mechanical siren shall be actuated by two (2) Linemaster model SP491-S81 foot switches mounted in the front section of the cab for use by the driver and officer. A red momentary siren brake rocker switch shall be provided in the switch panel on the dash.

The siren shall only be active when master warning switch is on to prevent accidental engagement.

BACK-UP ALARM

An ECCO model 575 backup alarm shall be installed at the rear of the chassis with an output level of 107 dB. The alarm shall automatically activate when the transmission is placed in reverse.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FIRE BELL ACTIVATION

There shall be a black push button located on the switch panel which shall actuate the fire bell. The button shall be clearly labeled for identification.

INSTRUMENTATION

An ergonomically designed instrument panel shall be provided. Each gauge shall be backlit with LED lamps. Stepper motor movements shall drive all gauges. The instrumentation system shall be multiplexed and shall receive ABS, engine, and transmission information over the J1939 data bus to reduce redundant sensors and wiring.

A twenty eight (28) icon lightbar message center with integral LCD odometer/trip odometer shall be included. The odometer shall display up to 999,999.9 miles. The trip odometer shall display 9,999.9 miles. The LCD message center screen shall be capable of custom configuration by the users for displaying certain vehicle status and diagnostic functions.

The instrument panel shall contain the following gauges:

One (1) three-movement gauge displaying vehicle speed, fuel level, and Diesel Exhaust Fluid (DEF) level. The primary scale on the speedometer shall read from 0 to 100 MPH, and the secondary scale on the speedometer shall read from 0 to 160 KM/H. The scale on the fuel and DEF level gauges shall read from empty to full as a fraction of full tank capacity. Red indicator lights in the gauge and an audible alarm shall indicate low fuel or low DEF at 1/8th tank level.

One (1) three-movement gauge displaying engine RPM, and primary and secondary air system pressures shall be included. The scale on the tachometer shall read from 0 to 3000 RPM. The scale on the air pressure gauges shall read from 0 to 150 pounds per square inch (PSI) with a red line zone indicating critical levels of air pressure. Red indicator lights in the gauge and an audible alarm shall indicate low air pressure.

One (1) four-movement gauge displaying engine oil pressure, coolant temperature, voltmeter, and transmission temperature shall be included. The scale on the engine oil pressure gauge shall read from 0 to 100 pounds PSI with a red line zone indicating critical levels of oil pressure. A red indicator light in the gauge and audible alarm shall indicate low engine oil pressure. The scale on the coolant temperature gauge shall read from 100 to 250 degrees Fahrenheit (°F) with a red line zone indicating critical coolant temperatures. A red indicator light in the gauge and audible alarm shall indicate high coolant temperature. The scale on the voltmeter shall read from 9 to 18 volts with a red line zone indicating critical levels of battery voltage. A red indicator light in the gauge and an audible alarm shall indicate high or low system voltage. The low voltage alarm shall indicate when the system voltage has dropped below 11.8 volts for more than 120 seconds in accordance with the requirements of NFPA 1901. The scale on the transmission temperature gauge shall read from 100 to 300 degrees °F with a red line zone indicating critical temperatures. A red indicator light in the gauge and an audible alarm shall indicate a high transmission temperature.

The light bar portion of the message center shall include twenty-eight (28) LED backlit indicators. The lightbar shall be split with fourteen (14) indicators on each side of the LCD message screen. The lightbar shall contain the following indicators and produce the following audible alarms when supplied in conjunction with applicable configurations:

RED INDICATORS

Stop Engine - indicates critical engine fault

Air Filter Restricted - indicates excessive engine air intake restriction

Park Brake - indicates parking brake is set

Seat Belt - indicates a seat is occupied and corresponding seat belt remains unfastened

Low Coolant - indicates critically low engine coolant

Cab Tilt Lock - indicates the cab tilt system locks are not engaged.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AMBER INDICATORS

Malfunction Indicator Lamp (MIL) - indicates an engine emission control system fault

Check Engine - indicates engine fault

Check Transmission - indicates transmission fault

Anti-Lock Brake System (ABS) - indicates anti-lock brake system fault

High exhaust system temperature – indicates elevated exhaust temperatures

Water in Fuel - indicates presence of water in fuel filter

Wait to Start - indicates active engine air preheat cycle

Windshield Washer Fluid – indicates washer fluid is low

DPF restriction - indicates a restriction of the diesel particulate filter

Regen Inhibit-indicates regeneration of the DPF has been inhibited by the operator

Range Inhibit - indicates a transmission operation is prevented and requested shift request may not occur.

SRS - indicates a problem in the supplemental restraint system

Check Message - indicates a vehicle status or diagnostic message on the LCD display requiring attention.

GREEN INDICATORS

Left and Right turn signal indicators

ATC - indicates low wheel traction for automatic traction control equipped vehicles, also indicates mud/snow mode is active for ATC system

High Idle - indicates engine high idle is active.

Cruise Control - indicates cruise control is enabled

OK to Pump - indicates the pump is engaged and conditions have been met for pump operations

Pump Engaged - indicates the pump transmission is currently in pump gear

Auxiliary Brake - indicates secondary braking device is active

BLUE INDICATORS

High Beam indicator

AUDIBLE ALARMS

Air Filter Restriction

Cab Tilt Lock

Check Engine

Check Transmission

Open Door/Compartment

High Coolant Temperature

High or Low System Voltage

High Transmission Temperature

Low Air Pressure

Low Coolant Level

Low DEF Level

Low Engine Oil Pressure

Low Fuel

Seatbelt Indicator

Stop Engine

Water in Fuel

Extended Left/Right Turn Signal On

ABS System Fault

BACKLIGHTING COLOR

The instrumentation gauges and the switch panel legends shall be backlit using red LED backlighting.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAMERA RIGHT HAND

One (1) Audiovox Voyager heavy duty rearview teardrop shaped chrome plated housing camera shall be mounted on the officer side of the cab below the windshield ahead of the front door at approximately the same level as the cab door handles. The camera display shall activate when the right side turn signal is activated.

CAMERA REAR

One (1) Audiovox Voyager heavy duty box shaped HD camera shall be shipped loose for OEM installation in the body to afford the driver a clear view to the rear of the vehicle.

The camera system shall include a one-way communication device that shall be an integral part of the rear camera for the use of voice commands directly to the driver. The rear camera display shall activate when the vehicle's transmission is placed in reverse.

CAMERA DISPLAY

The camera system shall be wired to a single Weldon Vista display located on the driver's side dash. The camera system display can be activated through the Vista display panel.

CAMERA SPEAKER

A speaker wired to the rear camera shall be provided in the cab and shall audible to the driver and officer. There shall be a virtual button provided on the Vista display and control panel to deactivate the speaker.

CAB EXTERIOR PROTECTION

The cab face shall have a removable plastic film installed over the painted surfaces to protect the paint finish during transport to the body manufacturer.

FIRE EXTINGUISHER

A 2.50 pound D.O.T approved fire extinguisher with BC rating shall be shipped loose with the cab.

ROAD SAFETY KIT

The cab and chassis shall include one (1) emergency road safety triangle kit.

DOOR KEYS

The cab and chassis shall include a total of four (4) door keys for the manual door locks.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

DIAGNOSTIC SOFTWARE OCCUPANT PROTECTION

Diagnostic software for the Spartan Advanced Protection System shall be available for free download from the Spartan Chassis website to Spartan authorized OEMs, dealers and service centers, as well as the vehicle owner.

The software has been validated to be compatible with the following RP1210 interface adapters:

- Dearborn Group DPA4 Plus
- Noregon Systems JPRO® DLA+
- Cummins INLINE5
- Cummins INLINE6
- NexIQ™ USB-Link™

The software and adapter utilize the SAE J1939-13 heavy duty nine (9) pin connector which is located below the driver's side dash to the left of the steering column.

WARRANTY

Summary of Warranty Terms:

THE FOLLOWING IS SUMMARY OF WARRANTY TERMS FOR INFORMATION ONLY. THE ACTUAL LIMITED WARRANTY DOCUMENT, WHICH IS ATTACHED TO THIS OPTION, CONTAINS THE COMPLETE STATEMENT OF THE SPARTAN MOTORS USA LIMITED WARRANTY. SPARTAN'S RESPONSIBILITY IS TO BE ACCORDING TO THE TERMS OF THE COMPLETE LIMITED WARRANTY DOCUMENT.

The chassis manufacturer shall provide a limited parts and labor warranty to the original purchaser of the custom built cab and chassis for a period of twenty-four (24) months, or the first 36,000 miles, whichever occurs first. The warranty period shall commence on the date the vehicle is delivered to the first end user.

CHASSIS OPERATION MANUAL

There shall be two (2) digital copies of the chassis operation manual provided with the chassis. The digital data shall include a parts list specific to the chassis model.

ENGINE AND TRANSMISSION OPERATION MANUALS

The following manuals specific to the engine and transmission models ordered will be included with the chassis in the ship loose items:

- (1) Hard copy of the Engine Operation and Maintenance manual with digital copy
- (1) Digital copy of the Transmission Operator's manual
- (1) Digital copy of the Engine Owner's manual

CAB/CHASSIS AS BUILT WIRING DIAGRAMS

The cab and chassis shall include two (2) digital copies of wiring schematics and option wiring diagrams.

PAINT CONFIRMATION

There shall be a paint confirmation letter sent to the body manufacturer with paint spray outs to confirm the cab primary paint color or primary and secondary paint color as specified by the paint options.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SALES TERMS

The sale of the Spartan Chassis shall be governed by the terms contained on the Sales Terms – Acceptance of Purchase Order document, a copy of which is attached to this option.

DRIVELINE LAYOUT CONFIRMATION

During the design phase of the chassis the Spartan Chassis driveline engineer shall submit the driveline layout to an OEM engineer to review the chassis design for any potential problems integrating the OEM body to the chassis. The OEM engineer shall provide approval to the driveline engineer prior to driveline bills of materials being released.

CAB TO AXLE DIMENSION

Cab to axle will be 120".

CAB/CHASSIS PREPAYMENT

The specified cab/chassis shall be prepaid by Boulder Rural Fire Protection District within 30 days of invoice. Boulder Rural Fire Protection District understands that if payment is made after 30 days, additional interest charges may apply.

CHASSIS MODIFICATIONS

LUBRICATION AND TIRE DATA PLATE

A permanent label in the driving compartment shall specify the quantity and type of the following fluids used in the vehicle and tire information:

- Engine oil
- Engine coolant
- Chassis transmission fluid
- Pump transmission lubrication fluid . . (if applicable)
- Pump priming system fluid, if applicable . . (if applicable)
- Drive axle(s) lubrication fluid
- Air conditioning refrigerant . . (if applicable)
- Air conditioning lubrication oil . . (if applicable)
- Power steering fluid
- Cab tilt mechanism fluid . . (if applicable)
- Transfer case fluid . . (if applicable)
- Equipment rack fluid (if applicable)
- CAFS air compressor system lubricant . . (if applicable)
- Generator system lubricant . . (if applicable)
- Front tire cold pressure
- Rear tire cold pressure
- Maximum tire speed ratings

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

VEHICLE DATA PLATE

A permanent label in the driving compartment which indicates the following:

- Filter part numbers for the;
 - Engine
 - Transmission
 - Air
 - Fuel
- Serial numbers for the;
 - Engine
 - Transmission
- Delivered Weights of the Front and Rear Axles
- Paint Brand and Code(s)
- Sales Order Number

OVERALL HEIGHT, LENGTH DATA PLATE (US)

The fire apparatus manufacturer shall permanently affix a high-visibility label in a location visible to the driver while seated.

The label shall show the height of the completed unequipped vehicle in feet and inches (meters), the length of the completed vehicle in feet and inches (meters to nearest 1/10th), and the GVWR in tons (metric tons).

Wording on the label shall indicate that; "The information shown was current when the apparatus was manufactured. If the overall height changes while the vehicle is in service, the fire department must revise that dimension on the plate".

PERSONNEL CAPACITY

A label that states the number of personnel the vehicle is designed to carry shall be located in an area visible to the driver.

SEAT BELT WARNING - FAMA06/07

A safety sign FAMA06 shall be visible from each seat that is not equipped with occupant restraint and therefore not intended to be occupied while the vehicle is in motion.

A safety sign FAMA07, which warns of the importance of seat belt use, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

EQUIPMENT MOUNTING FAMA10

A safety sign FAMA10, which warns of the need to secure items in the cab, shall be visible inside the cab.

FIRE SERVICE TIRES - FAMA12

A safety sign FAMA12, which warns of the special requirements for fire service-rated tires, shall be visible to the driver entering the cab of any apparatus so equipped.

HELMET WARNING - FAMA15

A safety sign FAMA15, which warns not to wear helmets while the vehicle is in motion, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CLIMBING METHOD - FAMA23

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

REAR STEP CROSSWALK WARNING - FAMA24

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

FINAL STAGE MANUFACTURER VEHICLE CERTIFICATION

A final stage manufacturer vehicle certification label shall be provided and installed in the driver cab door jamb area.

OEM FRONT BUMPER REPLACEMENT

The standard OEM bumper shall be removed and replaced with a custom bumper design. A 2" x 2" x 1/4" welded steel tubing framework shall be bolted to the OEM bumper mount location extending bumper 28". The framework is designed as an under slung "L" shape to allow for a deeper compartment storage above.

An SVI Edge contoured one-piece, fully welded steel construction front bumper shall be bolted in place of the OEM bumper. The front bumper {will/shall} be fabricated and from formed 7 gauge steel and welded to create contoured edges for an aesthetically pleasing design and improved front approach angle. Two (2) 3/4" steel tow eyes shall be provided on front with 2" opening. Bumper painted finish shall match lower cab paint color.

The top of the 28" extension shall be enclosed with 3/16" NFPA compliant aluminum treadplate. A large compartment shall be recessed into extension, 75" wide x 18" front-back, x 10" deep formed from 3/16" smooth aluminum. Additional options added ie: winch, air horns, recessed siren or speakers, make take away from compartment dimensions.

A 5" high single lid shall cover compartment fabricated from 1/8" aluminum tread plate with stainless steel hinges, chrome lift handle, two (2) butterfly type latches, and two (2) gas shock type hold open devices, one (1) at each end. A "Not a Step" label shall be provide on outer lid surface.

Bumper compartment shall have two (2) OnScene 36" Access LED lights mounted to light inside the compartment area to provide a minimum of 2 fc (20 lx) at any location on the floor of the compartment without any equipment in the compartment. Light shall be automatically activated when door is opened. A flashing warning light signal shall be provided indicating when parking brake is released that a compartment door is not in a closed position as required by NFPA 1901.

Bumper: Compartment Components, Electric

- Mount(s) shall be provided and installed for one (1) Boulder Rural Fire Protection District supplied ram(s).

SHOP NOTE: Make: Hurst Model: R421E2

- Mounts will be supplied and installed for one (1) Boulder Rural Fire Protection District supplied cutter(s).

SHOP NOTE: Make: Hurst Model: S788E2

- Mounts will be supplied and installed for one (1) Boulder Rural Fire Protection District supplied spreader(s).

SHOP NOTE: Make: Hurst Model: SP555E2

AIR HORNS

Two (2) Grover 24" Stuttertone chrome plated air horns shall be recess mounted in the front bumper, one (1) on each side outboard of the frame rails. An emergency air shut off valve shall be provided in the cab.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AIR HORN ACTIVATION

The air horn(s) activation shall be supplied by the cab/chassis manufacturer.

MOTOR DRIVEN SIREN

There shall be a Federal model Q2BP motor driven streamlined rotary siren with chrome plated grill and housing, pedestal mounted on extended front bumper. The siren shall be wired through the master warning light switch, and properly wired with heavy copper cable for minimum voltage drop.

The siren shall be located on the streetside of the front bumper.

There shall be a siren brake installed in the rocker switch control panel to activate the siren brake.

SIREN ACTIVATION

The siren activation shall be provided by cab/chassis manufacturer.

GROUND LIGHTS

There shall be two (2) OnScene 8" Access white LED lights installed below bumper capable of providing illumination at a minimum level of 2 fc (20 lx) on ground areas within 30 in. (800 mm) of the edge of the vehicle in areas designed for personnel to climb onto or descend from the vehicle to the ground level.

Lighting shall be switchable but activated automatically when the vehicle park brake is set.

FRONT BUMPER

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with a black hammertone powder coat paint finish located at the front bumper for use with removable rope anchor point and/or a portable electric winch (if specified).
 - There shall be one (1) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
 - The receiver(s) shall have one (1) rubber cover(s) provided.

FRONT BUMPER RECIEVER, SIDES

There shall be two (2) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located, one (1) on streetside, and one (1) on curbside of front bumper extension for use with removable rope anchor and/or a portable electric winch (when specified).

- There shall be two (2) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
- Two (2) 12" x 2" M x 2" F winch mounting adapter(s) shall be provided. Winch adapter will extend the specified portable winch 6" from receiver. An aluminum mounting bracket shall be provided to store winch adapter(s) inside a body compartment as close to receiver location as possible.
- The receiver(s) shall have two (2) rubber cover(s) provided.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SIREN SPEAKER

One (1) Whelen model SA314A 100 watt aluminum, 6.4" x 6.1" x 3.1" deep siren speaker shall be provided and located behind grill or front bumper with natural aluminum finish. The solid state siren speaker shall be vibration resistant. The SA314A shall comply with California Title XIII, Class A, and SAE J1849 requirements and with OSHA 1910.95 Guidelines regarding "Permissible Noise Exposure". All mounting hardware shall be stainless steel and covered by a two year factory warranty.

The siren speaker shall be located on the curbside of front bumper.

FRONT TOW EYES

There shall be two (2) heavy duty tow eyes securely mounted to the chassis frame below the front bumper.

AIR INTAKE SYSTEM

An air filter shall be provided in the engine's air intake system by the customer cab/chassis manufacturer.

Air inlet restrictions shall not exceed the engine manufacturer's recommendations.

The air inlet shall be equipped with a means of separating water and burning embers from the air intake system.

This requirement shall be permitted to be achieved by either of the following methods:

1. Provision of a device such that burning particulate matter larger than 0.039 in. (1.0 mm) in diameter cannot reach the air filter element.
2. Provision of a multi screen ember separator capable of meeting the test requirements defined in the Parker Hannafin, Racor Division, publication LF 1093-90, *Ember Separation Test Procedure*, or an equivalent test.

EXHAUST

The exhaust system shall be as provided by cab/chassis manufacturer. The tailpipe may require some modifications for proper ground clearances and fit with body.

The exhaust piping and discharge outlet shall be located or shielded so as not to expose any portion of the vehicle or equipment to excessive heating.

Exhaust pipe discharge shall be directed away from any operator's position or entry doors on body.

Where parts of the exhaust system are exposed so that they are likely to cause injury to operating personnel, protective guards shall be provided.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

RADIO/ANTENNA INSTALLATION

There shall be three (3) Boulder Rural Fire Protection District supplied radio(s) with antenna installed in the cab within easy reach of driver. The location of radio shall be determined by the Boulder Rural Fire Protection District at the pre-construction meeting. All required radio programming shall be responsibility of Boulder Rural Fire Protection District. Radio(s) may not be fully tested if no radio program is provided with radio and will be responsibility of Boulder Rural Fire Protection District after delivery.

There shall be:

- 2- Boulder Rural supplied radios and antennas
- 1- Boulder Rural supplied Cradle point and antenna

Radio shall be installed per Manufacturer's requirements and wired for proper 12 volt power and ground.

12 VDC USB, DUAL CHARGING PORT

There shall be three (3) Blue Sea switch mount style, dual USB 4.8 amp, 12 VDC charging port(s) provided and installed in cab area, wired battery direct. Charging port shall have over temp protection, dust cover and be located per required usage and protected from damage. The USB's shall be located one (1) in each forward face rear wall compartment.

SEAT BELT COLOR

Section 14.1.3.3 of the NFPA 1901 Standards, requires all seat belt webbing in cab to be bright red or bright orange in color, and the buckle portion of the seat belt shall be mounted on a rigid or semi rigid stalk such that the buckle remains positioned in an accessible location.

SEAT BELT WEB LENGTH - CUSTOM CAB

Sections 14.1.3.2 and 14.1.3.3 of the NFPA 1901 standards, require the effective seat belt web length for a Type 1 lap belt for pelvic restraint to be a minimum of 60", and a Type 2 pelvic and upper torso restraint-style seat belt assembly to be a minimum of 110".

The chassis seat belt web length as supplied by the custom chassis manufacturer shall be compliant to NFPA Standards 14.1.3.2 and 14.1.3.3.

SEAT BELT / VDR SYSTEM - CUSTOM CAB

The seat belt warning and vehicle data recorder systems shall be provided by the cab/chassis manufacturer.

STORAGE MODULE

A storage module shall be provided in the cab. The module shall be as large as possible and fabricated of 1/8" smooth aluminum. A textured powder coat paint finish shall be provided for durability and finished appearance. The paint shall match the interior cab color.

The final design and location of console shall be determined by the Boulder Rural Fire Protection District at the pre-construction meeting.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CUSTOMER SUPPLIED COMPONENTS

Boulder Rural Fire Protection District supplied Knox Box Key Secure shall be installed in cab. Location shall be determined after cab cabinet installation.

Boulder Rural Fire Protection District supplied thermal camera shall be installed on the engine tunnel. Location shall be determined after cab cabinet installation.

Boulder Rural Fire Protection District supplied Knox Narcs vault shall be installed in cab. Location shall be determined after cab cabinet installation.

SIX (6) – LED TIRE PRESSURE VISUAL INDICATORS

Each tire valve stem shall be equipped with an LED Tire Alert (or equal), heavy duty valve cap LED indicator that indicates proper tire pressure. The LED Tire Alert valve cap is self-calibrating. When the cap is mounted on the valve stem the first time, it will memorize that tire pressure, and can be set to recognize a drop in pressure as little as 6 psi. It can be checked for functionality and battery condition by simply unscrewing the cap. If it is in working condition, it will immediately start blinking.

HELMET STORAGE

No helmet storage is required in the cab driving area. A safety sign FAMA15, which warns not to wear helmets while the vehicle is in motion, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

HELMET STORAGE, CREW AREA

Four (4) OnScene Solutions Talon model helmet storage bracket(s) shall be provided and installed in the rear crew area. The helmet mounting will comply with the 9G NFPA requirements. If cab is specified with air bags, the helmet bracket(s) will be mounted clear of the deployment area.

- Four (4) helmet bracket(s) shall be mounted on the rear wall area adjacent to seating. Mounting shall not interfere with air bag systems, if specified.

Final location to be verified with customer after chassis arrival.

GEAR HOOK

Three (3) coat hooks shall be provided and installed in the cab. PAC Trac single face model 7000 aluminum extrusion with the tracks in a horizontal orientation shall be attached to the cab walls which will be the anchor point for the coat hooks.

The hooks shall be on the back wall of the cab between specified rear wall cabinets. Final location to be verified by customer after chassis arrival.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB CRASH TEST CERTIFICATION

A cab crash test certification from the fire apparatus manufacturer shall be provided with the equipment. A copy of this certification shall be included with the bid.

NOTE: There shall be no exception to any portion of the cab integrity certification requirements. Nonconformance shall lead to immediate rejection of bid.

The certification shall state that the cab does meet or exceed the requirements below:

- 1) European Occupant Protection Standard ECE Regulation No. 29.
- 2) SAE J2422 Cab Roof Strength Evaluation - Quasi-Static Loading Heavy Trucks.

HUB AND NUT COVERS

Front and rear wheels shall be provided with stainless steel hub caps and wheel nut covers.

MUDFLAPS

There shall be 1/4" rubber mudflaps with logo provided and installed behind each set of tires to prevent throwing road debris and lower road spray.

CHASSIS AIR TANK DRAIN CABLES

The cab/chassis air brake system tank drains cables shall be extended to panel(s) located on forward streetside lower body or as per tank locations. Each air tank drain cable shall be extended/routed to the panel(s) through eyelets so as to prevent cables hanging or being exposed below the body.

Each pull ring/handle shall be properly labeled to identify each tank and include a black colored label bezel.

ROAD EMERGENCY SAFETY KIT

The DOT required reflective triangles, warning flares, and fire extinguisher shall be provided by cab and chassis supplier.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB INTERIOR CABINET - CURBSIDE REAR WALL

If cab is specified with air bags, the interior cabinet(s) will be mounted clear of the deployment area.

There shall be one (1) full height cabinet located in rear cab area. The cabinet shall be fabricated from 1/8" smooth aluminum, and shall have a cargo net covering with automotive latches.

The cabinet shall be finished with a dark gray hammer tone powder coat paint for a hard and durable finish. The cabinet shall be approximately 23" wide x cab interior height (less 3") x 21" deep. If cab is specified with air bags, the interior cabinet(s) will be mounted clear of the deployment area.

- There shall be one (1) OnScene Solutions 54" Night Axe LED light(s) mounted inside the cabinet.
- Cabinet(s) shall be provided with vertically mounted shallow aluminum Shelf-Trac for specified component installation.
- There shall be three (3) adjustable shelf/shelves in the above cabinet(s). Each shelf shall have a 1.25" vertical lip at front to contain items while vehicle is in motion.
- There shall be one (1) 120 VAC outlet(s) located inside cabinet against the back wall.

Outlet to be QUAD style located upper cabinet area.

- There shall be one (1) approximate 2' long 120 VAC outlet strip(s) with straight blade household type outlets provided.
 - The outlet receptacle(s) shall be 20 amp, straight-blade (NEMA 5-20R).
 - Outlet(s) shall be powered through the on-board shore power system.

CAB INTERIOR CABINET - CENTER REAR WALL

There shall be one (1) full height cabinet located in rear cab area. The cabinet shall be fabricated from 1/8" smooth aluminum, and shall have a cargo net covering with automotive latches.

The cabinet shall be finished with a dark gray hammer tone powder coat paint for a hard and durable finish. The cabinet shall be approximately 23" wide x cab interior height (less 3") x 21" deep. If cab is specified with air bags, the interior cabinet(s) will be mounted clear of the deployment area.

- There shall be one (1) OnScene Solutions 54" Night Axe LED light(s) mounted inside the cabinet.
- Cabinet(s) shall be provided with vertically mounted shallow aluminum Shelf-Trac for specified component installation.
- There shall be three (3) adjustable shelf/shelves in the above cabinet(s). Each shelf shall have a 1.25" vertical lip at front to contain items while vehicle is in motion.
- There shall be two (2) Zico ULLH walkaway type SCBA air pack bracket(s) with "V" type clip and strap assembly to hold SCBA in place.

SCBA brackets located in lower cabinet on side walls.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CAB INTERIOR CABINET - STREETSIDE REAR WALL

If cab is specified with air bags, the interior cabinet(s) will be mounted clear of the deployment area.

There shall be one (1) full height cabinet located in rear cab area. The cabinet shall be fabricated from 1/8" smooth aluminum, and shall have a cargo net covering with automotive latches.

The cabinet shall be finished with a dark gray hammer tone powder coat paint for a hard and durable finish. The cabinet shall be approximately 23" wide x cab interior height (less 3") x 21" deep. If cab is specified with air bags, the interior cabinet(s) will be mounted clear of the deployment area.

- There shall be one (1) OnScene Solutions 54" Night Axe LED light(s) mounted inside the cabinet.
- Cabinet(s) shall be provided with vertically mounted shallow aluminum Shelf-Trac for specified component installation.
- There shall be three (3) adjustable shelf/shelves in the above cabinet(s). Each shelf shall have a 1.25" vertical lip at front to contain items while vehicle is in motion.
- There shall be one (1) 120 VAC outlet(s) located inside cabinet against the back wall.

Outlet to be QUAD style located upper cabinet area.

- There shall be one (1) approximate 2' long 120 VAC outlet strip(s) with straight blade household type outlets provided.
 - The outlet receptacle(s) shall be 20 amp, straight-blade (NEMA 5-20R).
 - Outlet(s) shall be powered through the on-board shore power system.

CAB MISCELLANEOUS EQUIPMENT

The following items shall be provided in cab as follows;

FUEL FILL

There shall be one (1) fuel fill door located in the streetside exterior wheel well panel, behind the rear axle. The fill door shall be fabricated from brushed stainless steel. There shall be a permanent label with the text "DIESEL FUEL ONLY" located adjacent to the fuel fill access.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

BODY DESIGN

The importance of public safety associated with emergency vehicles requires that the construction of this vehicle meet the following specifications. These specifications are written to establish the minimum level of quality and design. All Bidders shall be required to meet these minimum requirements.

It is the intent of these specifications to fully describe the requirements for a custom built emergency type vehicle. In order to extend the expected service life of this vehicle, the body module shall be removable from the chassis frame and be capable of being installed on a new chassis.

The sheet metal material requirements, including alloy and material thickness, throughout the specifications are considered to be a minimum. Since such materials are available to all Manufacturers, the material specifications shall be strictly adhered to.

The fabrication of the body shall be formed sheet metal. Formed components shall allow the Boulder Rural Fire Protection District to have the body repaired locally in the case where any object has struck the body and caused damage. The use of proprietary extrusions will prevent the Boulder Rural Fire Protection District from such repair and shall NOT be used. All fabricated body components to be cut by a laser or water-jet for superior cut edge quality.

Following construction of the subframe, which supports the apparatus body, the sheet metal portion of the body shall be built directly on the subframe. The joining of the subframe and body shall be of a welded integral construction.

The sheet metal fabrication of the body shall be performed using inert gas continuous feed welders only. The entire body shall be welded construction. The use of pop rivets in any portion of structural construction may allow premature failure of the body structure. Therefore, pop rivets shall NOT be used in the construction of the structural portions of the body. This includes side body sheets, inner panels of compartment doors, and any other structural portions of the body.

EXTERIOR ALUMINUM BODY

The fabrication of the body shall be constructed from aluminum 3003H-14 alloy smooth plate. This shall include compartment front panel, vertical side sheets, side upper rollover panels, rear panels and compartment door frames.

The body compartment floors and exterior panels shall be constructed with not less than 3/16" (.187) aluminum 3003H-14 smooth plate. Interior compartment dividing walls shall be constructed with not less than 1/8" (.125) aluminum 3003H-14 smooth plate. Lighter gauge sheet metal will not be acceptable in these areas, No Exceptions.

The front and rear corners of body shall be formed as part of the front or rear body panels. This provides a stronger body corner and finished appearance. The use of extruded corners, or caps will not be acceptable, No Exceptions.

The door side frame openings shall be formed "C" channel design. An electrical wiring conduit raceway running the full length of exterior compartments shall be provided. This raceway shall contain all 12 volt wiring running to the rear of the apparatus, permitting easy accessibility to wiring.

Individual compartment modules, with dead air space voids between compartments, will not be an acceptable method of compartment construction.

The compartments shall be an integral part of the body construction. Compartment floors from front of body to ahead of rear axle, also from rear axle to rear of body shall be single one-piece sections. Compartment floors shall be preformed, then positioned in body and welded into final position.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Compartment floors shall have a "sweep-out" design with door opening threshold positioned lower than compartment floor, permitting easy cleaning of compartments. Angles, lips, or door moldings are not acceptable in the base of compartment door opening. One-way rubber drain valves shall be provided in compartment floors so that a water hose may be used to flush-out compartment area.

All exterior seams in sheet metal below frame, and around the rear wheel well area shall be welded and caulked to prevent moisture from entering the compartments. All other interior seams and corners shall be sealed with silicone based caulk prior to painting.

Only stainless steel bolts, nuts, and sheet metal screws shall be used in mounting exterior trim, hardware and equipment.

DRIP RAILS

The body shall have drip rails over the side full height compartments. The drip rails shall be formed into the upper body panels providing a ridged lower panel and a flat upper body panel surface. The use of mechanically fastened, taped or glued on drip rails will not be acceptable, No Exceptions.

ROOF CONSTRUCTION

The roof structure shall be integral with the body sheet metal construction and shall be an all welded assembly. The body roof structure shall be overlaid with not less than 3/16" aluminum 3003H-14 alloy tread plate and welded to roof structure and body sheet metal. All seams in roof material shall be fully and continuously welded to prevent entry of moisture.

There shall be a total of four (4) 2" x 2" x 1/4" 6061-T6 alloy aluminum "C" channels running the length of body, two (2) on each outboard side. These "C" channels shall be used for roof support and in addition shall be used for mounting of any specified reels. This open "C" channel design along with special reel mounting clips allows for a universal location of any specified reels within each compartment.

In between the two (2) center "C" channels running the length of body shall be 2" x 2" x 1/4" 6061-T6 alloy aluminum tubing running in between and welded in place on approximate 16" centers to support roof and/or walkway structure if specified.

A 2" formed radius shall be provided along the body sides and utilized as a wiring trough. The use of aluminum extrusions in this area shall not be acceptable, .

BODY SUBFRAME

The chassis frame rails shall be fitted with 1/4" custom extruded UHMW polyethylene rail cap to isolate the body frame members from direct contact with chassis frame rails.

The body subframe shall be constructed from 6061T6 aluminum alloy tubing. Subframe shall consist of two (2) 2" x 4" x 1/4" aluminum tubes minimum, the same width as the chassis frame rails. Welded to this tubing shall be cross members of 2" x 4" x 1/4" aluminum. Smaller dimension, lighter gauge tubing or angle material subframe shall not be accepted.

These cross members shall extend the full width of the body to support the compartments. Cross members shall be located at front and rear of the body, below compartment divider walls, and in front and rear of wheel well opening. Additional aluminum cross members shall be located on 16" centers, or as necessary to support walkway or heavy equipment.

To form the frame, the tubing shall be beveled and welded at each joint using 5356 aluminum alloy welding wire.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

BODY MOUNTING

The body subframe shall be fastened to the chassis frame with a minimum of four (4) spring loaded body mounts. Each mount shall be configured using a two-piece encapsulated slide bracket. The two (2) brackets shall be fabricated of heavy duty 1/4" thick steel and shall have a powder coat finish to prevent any corrosion. Each mounting assembly shall utilize two (2) 3/4" diameter x 6" long grade 8 bolts and two (2) heavy duty springs. The assembly design shall allow the body and subframe to act as one (1) component, separate from the chassis. As the chassis frame twists under driving conditions, the spring mounting system shall eliminate any stress from being transferred into the body. The spring loaded body mounts shall also prevent frame side rail or body damage caused by unevenly distributed stress and strains due to load and chassis movement.

Body mountings that do not allow relief from chassis movement will not be acceptable.

18" REAR STEP BUMPER

The full width rear bumper shall be constructed from 2" x 2" x 1/4" aluminum tubing frame and covered with 3/16" NFPA compliant aluminum tread plate. The bumper shall extend from the rear vertical body panel 14" and provide a rear step with a minimum of 1/2" space at body for water drainage.

REAR TOW EYES

There shall be two (2) heavy duty rear mounted tow eyes securely attached to the body subframe, below body. The tow eyes shall be fabricated from 3/4" thick steel plate with a 3" diameter opening. Tow eyes shall have a black powder coat finish.

GROUND LIGHTS

There shall be two (2) OnScene 8" Access white LED lights installed below bumper capable of providing illumination at a minimum level of 2 fc (20 lx) on ground areas within 30 in. (800 mm) of the edge of the vehicle in areas designed for personnel to climb onto or descend from the vehicle to the ground level.

Lighting shall be switchable but activated automatically when the vehicle park brake is set.

WHEEL WELL EXTERIOR PANEL

The exterior panel of the body wheel well enclosure shall be constructed from 3/16" smooth aluminum and will be bolted on for easy removal and replacement.

STAINLESS STEEL BODY FENDERS

The body wheel well openings shall be provided with round radius, polished stainless steel fenderettes. The fenderettes shall be bolted and easily replaceable if damaged. The fenderettes shall be installed using a rubber gasket to reduce buildup of moisture and/or debris.

WHEEL WELL LINERS

The wheel wells shall be provided with an easily removable polymer, circular inner fender liner. The inner liner shall be bolted to the wheel well with stainless steel bolts and spaced away from the wheel well so the liner will not accumulate dirt or water.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SCBA CYLINDER COMPARTMENTS

There shall be three (3) SCBA cylinder storage compartments located, two (2) on the curbside, and one (1) on the streetside of rear wheel well area. Each compartment shall be capable of storing two (2) SCBA (60 min.) cylinders. Each compartment shall have a vertical hinged stainless steel aluminum door with a positive catch latch and painted primary lower body color. Each compartment shall allow the storage of an SCBA cylinder or a fire extinguisher up to 7-3/4" in diameter x 24" deep. The door shall activate the "Hazard Warning Light" in the cab when not in the closed position.

BODY PAINT SPECIFICATIONS

BODY PAINT PREPARATION

After the body and components have been fabricated they shall be disassembled so when vehicle is complete there shall be finish paint beneath the removable components. The body shall be removed from chassis during the paint process to insure proper paint coverage. The body and components shall be metal finished as follows to provide a superior substrate for painting.

The exterior (and interior, if painted) body shall undergo a thorough cleaning process starting with a biodegradable phosphoric acid solution to begin the etching process followed by a complete clear water rinse. The next step shall consist of a chemical conversion coating applied to seal the metal substrate and become part of the metal surface for greater film adhesion.

All bright metal fittings, if unavailable in stainless steel or polished aluminum, shall be chrome plated. Iron fittings shall be copper under plated prior to chrome plating.

PAINT PROCESS

The paint process shall follow the strict standards set forth by PPG Industries guidelines. Painters applying PPG products will be PPG Certified Commercial Technicians, and re-certified every two (2) years. The body shall go through the following paint process;

- 1) Clean bare metal with a wax and grease remover using low lint rags.
- 2) Inspect, straighten, and hammer high points, grind all seams, sharp edges, and welds. DA sand entire paintable surfaces using 24-180 grit dry paper. Plastic fill all low spots and DA sand fill areas using 36-180 grit dry paper. Apply pinhole filler and DA sand areas using 80-180 grit dry paper.
- 3) Re-clean bare metal using a wax and grease remover and low lint rags.
- 4) Within 24 hours, a PPG Delfleet® epoxy color primer with proper hardener for corrosion resistance using a pressure pot spray gun and applying 2-5 full wet coats or 1.5-8.0 dry mils max. achieving full hiding and allow to air dry 60 minutes @ 70°F or bake for 45 minutes @ 140°F degree.
- 5) Inspect, putty fill, and dry guild coat entire body surface and DA sand using 180-400 grit dry paper.
- 6) Re-clean bare metal using a wax and grease remover using low lint rags.
- 7) A PPG Delfleet® primer sealer with proper hardener and thinner shall be sprayed using a pressure pot spray gun and applying 1 full wet coat or 1.0-2.0 dry mils achieving full hiding and allow to flash off in spray booth for minimum of 60 minutes @ 70°F.
- 8) A PPG Delfleet® FBCH basecoat (color) with proper hardener and dry additive shall then be sprayed using a pressure pot set @ 45-60 PSI and achieving full hiding or 1.5-2.0 wet mils and allow to flash off in spray booth 45-60 minutes before applying clearcoat.
- 9) A PPG Delfleet® clearcoat with proper hardener and thinner shall be sprayed using a pressure pot spray gun and applying 2-3 full wet coats or 5.0 wet mils for a uniform gloss and allow to flash off in spray booth 10 minutes and bake for 120-140 minutes @ 125°F (surface temp.).
- 10) After cooling, DA sand heavy orange peel or runs using 1000 grit dry sand paper and final DA sand using 1500-2000 grit dry sand paper. Wipe off all surfaces to remove dust and debris. Buff unit as needed using 3M rubbing compound and a white wool pad and inspect until all sand scratches are removed.
- 11) Polish as needed using 3M Perfect-It-Polish and a black foam pad, repeat as necessary and inspect until all sand scratches are removed.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

PAINT - ENVIRONMENTAL IMPACT

The contractor shall meet or exceed all current State (his) regulations concerning paint operations. Pollution control shall include measures to protect the atmosphere, water and soil. PPG Delfleet® Evolution paint shall be free of all heavy metal (lead & chromate) components. Paint emissions from sanding and painting shall be filtered and collected. All paint wastes shall be disposed of in an environmentally safe manner. Solvents used in cleanup operations shall be collected, sent off-site for distillation and returned for reuse.

FASTENERS

Prior to the assembly and reinstallation of exterior components; i.e. warning and DOT lights, handrails, steps, door hardware, and miscellaneous items, a Mylar isolation tape, or gasket shall be used to prevent damage to the finish painted surface. These components shall be fastened to body using either a plastic insert into body metal with stainless steel screws or zinc coated nut-surts into body surface using stainless steel bolts to prevent corrosion from dissimilar metals.

ELECTROLYSIS CORROSION CONTROL

The vehicle shall be assembled using ECK brand or similar corrosion control compound on all high corrosion potential areas.

ECK protects aluminum and stainless steel against electrolytic reaction, isolates dissimilar metals and gives bedding protection for hardware and fasteners. ECK contains anti-seizing lubricant for threads. ECK is dielectric and perfect for use with electrical connectors.

PAINT FINISH - SINGLE COLOR

The body shall be painted with a single color of PPG Delfleet® Evolution per Boulder Rural Fire Protection District approved paint spray out provided.

A small touch-up bottle of paint shall be provided with completed vehicle.

BODY UNDERCOATING

The entire underside of body shall be sprayed with black automotive undercoating. Undercoating shall cover all areas underside of body and wheel well area to help prevent corrosion under the vehicle.

UNDERCOAT WARRANTY

The body undercoating shall have a warranty provided by the manufacturer for the lifetime of the vehicle or twenty (20) years, whichever occurs first. The warranty shall be transferable between vehicle owners. Should the undercoating material applied to the underside of the body and wheel wells of the vehicle ever flake off, peel, chip or crack due to drying out, the damaged area shall be re-sprayed without charge to the vehicle owner.

PAINT WARRANTY

The vehicle shall be provided with a ten (10) year non-prorated warranty to the original owner. Warranty is provided by PPG Inc. A warranty sheet with all conditions and maintenance procedures shall be provided with the delivered vehicle. **Pro-rated warranties will not be acceptable.**

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

COMPARTMENT INTERIOR FINISH

The compartment interior paintable surfaces shall be prepared and DA sanded using 80-120 grit dry paper and cleaned with a wax and grease remover. A PPG Delfleet® primer topcoat of either a solids epoxy primer or an etch primer shall be applied.

A PPG Delfleet® color primer with proper hardener and thinner mix shall then be sprayed using a pressure pot spray gun and applying 2 wet coats achieving full hiding on entire compartment surface and allow to air dry for 30 minutes @ 70°F before applying texture coat.

A PPG Delfleet® F3985 White/F3986 Gray top coat/texture coat with proper hardener and dry additive shall then be sprayed using a pressure pot and reducing the atomizing air pressure and turn fan pattern all the way in on the gun. Apply the first color texture coat as needed and allow to air dry @ 70°F over night before assembly and 7 days before putting into full service.

REFLECTIVE STRIPE REQUIREMENTS

Material

All retroreflective materials shall conform to the requirements of ASTM D4956, *Standard Specification for Retroreflective Sheeting for Traffic Control*, Section 6.1.1 for Type I Sheeting.

All retroreflective materials used that are colors not listed in ASTM D4956, Section 6.1.1, shall have a minimum coefficient of retro-reflection of 10 with observation angle of 0.2 degrees and entrance angle of -4 degrees.

Any printed or processed retroreflective film construction used shall conform to the standards required of an integral colored film as specified in ASTM D4956, Section 6.1.1.

Minimum Requirements

A retroreflective stripe(s) shall be affixed to at least 50 percent of the cab and body length on each side, excluding the pump panel areas, and at least 25 percent of the width of the front of the vehicle, not including mirrors or other protrusions.

The stripe or combination of stripes shall be a minimum of 4 in. (100 mm) in total width.

The 4 in. (100 mm) wide stripe or combination of stripes shall be permitted to be interrupted by objects (i.e., receptacles, cracks between slats in roll up doors) provided the full stripe is seen as conspicuous when approaching the apparatus.

A graphic design shall be permitted to replace all or part of the required striping material if the design or combination thereof covers at least the same perimeter length(s).

GRAPHICS PROOF

A color graphics proof of the reflective striping layout shall be provided for approval by Boulder Rural Fire Protection District prior to installation. The graphics proof shall be submitted to Boulder Rural Fire Protection District on 8.5" x 11" sheets with front, sides, rear and plan views, each on one (1) sheet. In addition if there is any special art work an additional sheet shall be provided showing all details.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

REFLECTIVE STRIPE - CAB SIDE

The reflective stripe material shall be 6" wide, 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

There shall be a 1" Scotchlite reflective stripe located 1" above and a second 1" Scotchlite reflective stripe located 1" below the main stripe.

- This reflective stripe shall be gold in color.

REFLECTIVE STRIPE - CAB FRONT

The reflective stripe material shall be 6" wide, 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

There shall be a 1" Scotchlite reflective stripe located 1" above and a second 1" Scotchlite reflective stripe located 1" below the main stripe.

- This reflective stripe shall be gold in color.

CHEVRON STRIPE - CAB BUMPER

A reflective stripe shall be affixed to the front of cab. The stripe or combination of stripes shall be a minimum of 4 in. (100 mm) in total width.

The approximate 10" wide Chevron retroreflective stripe shall be affixed to at least 25 percent of the width of the front of the apparatus with retroreflective striping in a chevron pattern sloping downward and away from the centerline of the vehicle at an angle of 45 degrees. Each stripe shall be 6" width. Chevron panels shall have a 3M UV over laminate to protect from UV rays, scene damage, and everyday use. Chevron panels shall have a minimum 10 year warranty for material failure, and colorfastness.

- The stripe material shall be 3M Scotchlite 680 series graphic film.

All retroreflective materials required shall conform to the requirements of ASTM D 4956, *Standard Specification for Retroreflective Sheeting for Traffic Control*, Section 6.1.1 for Type I Sheeting.

This reflective chevron stripe shall alternate red and yellow in color.

REFLECTIVE STRIPE - BODY SIDES

The reflective stripe material shall be 6" wide, 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

There shall be a 1" Scotchlite reflective stripe located 1" above and a second 1" Scotchlite reflective stripe located 1" below the main stripe.

- This reflective stripe shall be gold in color.

The stripe shall extend from the front of cab in a straight line, then just ahead of the rear wheels the stripe shall angle up and extend straight back to the rear of the body.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CHEVRON REFLECTIVE STRIPE - REAR SIDES PANELS

At least 50 percent of the rear-facing vertical surfaces, visible from the rear of the apparatus, excluding any pump panel areas not covered by a door, shall be equipped with retroreflective striping in a chevron pattern sloping downward and away from the centerline of the vehicle at an angle of 45 degrees. Each stripe shall be 6" width.

The rear side panels of the body on each side of a rear stairway or compartment shall have a chevron style reflective stripe, extending from bumper to full body height. Each chevron panel shall be a full sheet and shall have a 3M UV over laminate to protect from UV rays, scene damage, and everyday use. Chevron panel shall have a minimum 10 year warranty for material failure, and colorfastness.

The stripe material shall be 3M Diamond Grade.

This reflective chevron stripe shall alternate red and fluorescent yellow-green in color.

LETTERING

GRAPHICS PROOF

A color graphics proof of the lettering layout shall be provided for approval by Boulder Rural Fire Protection District prior to installation. The graphics proof shall be submitted to Boulder Rural Fire Protection District on 8.5" x 11" sheets with front, sides, rear and plan views, each on one (1) sheet. In addition if there is any special art work an additional sheet shall be provided showing all details.

The following lettering shall be provided and installed on the completed unit as follows;

SIDE CAB DOOR LETTERING

There shall be one hundred eighteen (118) 4" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be white in color.

There shall be eight (8) 8" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be white in color.

UPPER BODY SIDE LETTERING

There shall be thirty (30) 10" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be white in color.

There shall be twenty two (22) 6" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be white in color.

CAB ROOF LETTERING

There shall be four (4) 21" high reflective letters furnished and installed on the vehicle.

Cab Roof: "CO_BLRX"

- This reflective lettering shall be red in color.

SHOP NOTE; Red painted roof??

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CUSTOM DECAL LOGO - 12" -18"

One (1) custom designed 12" - 18" 3M Scotchlite type retroreflective logo shall be provided and located on the completed vehicle. The exact design and/or artwork shall be provided by the Boulder Rural Fire Protection District prior to construction.

One (1) copy of the above custom logo shall be provided and located on the completed vehicle as directed by Boulder Rural Fire Protection District.

EXTERIOR COMPARTMENT DOORS

FLUSH FITTING HINGED DOOR CONSTRUCTION

The exterior compartment doors shall be a flush style, custom manufactured and built for each compartment. The compartment doors must be able to withstand years of rugged service and wear. For this reason, the compartment door design, metal thickness, and attachments must be strictly adhered to.

The compartment doors shall be all aluminum 3003H-14 alloy construction. The exterior panel shall be of 1/8" thickness smooth plate aluminum and the interior panel shall be of 1/8" thickness smooth plate aluminum. Lighter gauge material will NOT BE ACCEPTABLE in these areas. The double panel doors shall be 1-3/4" thick to completely enclose the door latching assembly. Doors shall have drain hole openings for drainage and ventilation.

The doors shall be flush mounted so that the outer surface is in line with the side body surface. Lap or bevel type constructed doors, doors framed with extrusions, or doors requiring rubber bumpers to prevent unnecessary contact are NOT ACCEPTABLE.

Compartment door openings shall be sealed with closed cell automotive type rubber molding to provide a weather resistant seal around door. In addition, rubber molding shall be provided along hinge to prevent moisture entry. Open cell foam type rubber moldings are NOT ACCEPTABLE.

Hinged compartment doors shall have 14 gauge stainless steel hinge, with 1/4" stainless steel pin. The hinge shall be bolted to the door and body with stainless steel machine screws. A polyester barrier film gasket shall be placed between stainless steel hinge and any dissimilar metals as necessary.

Drip rails shall be installed above all compartment door openings. Drip rails shall be completely removable for easy replacement if necessary.

Each door shall be capable of being opened or closed without unlatching. Door checks shall be bolted to the upper compartment door header and the box pan of the door. Door checks that require unlatching by hand will NOT BE ACCEPTABLE.

Vertically hinged door openings up to 32" wide shall be single door construction. Door openings over 32" shall be double door construction with the forward first opening door overlapping the second opening door.

HINGED DOOR REFLECTIVE STRIPING

1-1/2" x 12" lengths of 3M™ Diamond Grade™ conspicuity striping shall be provided on door edges facing outward on all vertical and horizontal hinged door(s), and 2" x 12" on interior door panels facing inward on vertically hinged door(s). The striping shall be red/white in color.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ROLL-UP DOOR CONSTRUCTION - ROBINSON (ROM)

The vehicle shall be equipped with R•O•M Series IV roll-up exterior compartment doors. The R•O•M roll-up doors shall be complete with the following features;

Each shutter slat, track, bottom rail, and drip rail shall be constructed from anodized 6063 T6 aluminum. Shutter slats shall feature a double wall extrusion 0.315" thick with a concave interior surface to minimize loose equipment jamming the shutter door closed. Shutter slats shall feature an interlocking end shoe to prevent side to side binding of the shutter door during operation. Slat must have interlocking joints with an inverted locking flange. Slat inner seal shall be a one piece PVC extrusion; seal design will be such to prevent metal to metal contact while minimizing dirt and water from entering the compartment.

Shutter door track shall be one piece design with integral overlapping flange to provide a clean finished look without the need of caulk. Door track shall feature an extruded Santoprene rubber double lip low profile side seal with a silicone co-extruded back to reduce friction during shutter operation.

Shutter bottom rail shall be a one piece double wall extrusion with integrated finger pull. Finger pull shall be curved upward with a linear striated surface to improve operator grip while operating the shutter door. Bottom rail shall have a smooth contoured interior surface to prevent loose equipment from jamming the shutter door. Bottom rail seal shall be made from Santoprene; it will be a double "V" seal to prevent water and debris from entering compartment. Bottom rail lift bar shall be a one piece "D" shaped aluminum extrusion with linear striations to improve operator grip during operation. Lift bar shall have a wall thickness of 0.125". Lift bar shall be supported by no less than two pivot blocks; pivot blocks shall be constructed from Type 66 Glass filled reinforced nylon for superior strength. Bottom rail end blocks shall have incorporated drain holes which will allow any moisture that collects inside the extrusion to drain out.

Shutter door shall have an enclosed counter balance system. Counter balance system shall be 4" in diameter and held in place by two (2) heavy duty 18 gauge zinc plated plates. Counter balance system shall have two (2) over-molded rubber guide wheels to provide a smooth transition from vertical track to counter balance system; no foam material of any kind shall be permitted or used in this area.

The R•O•M Series IV roll-up compartment doors shall be free of manufacturing defects for a period of up to 7 years from date of purchase provided doors are used under conditions of normal use, regular periodic maintenance and service is performed, and doors were installed in accordance with R•O•M's instructions.

ROM DOOR BOTTOM RAIL

All exterior compartment doors shall have the standard 3.0" tall bottom rail extrusion for easy one (1) hand opening and closing.

The specified retroreflective stripe material shall be applied on the roll-up compartment doors. The stripe shall be precision machine cut for each door slat of the roll-up doors. Under no circumstance will the stripe material be cut on roll-up door surface.

BODY WIDTH DIMENSIONS

The pumper body shall be 100.0" wide, and 102.0" wide at drip rails. Interior compartment depth dimensions shall be approximately:

<u>Area Description</u>	<u>Dimension</u>
Transverse above subframe	95.0" (If specified.)
Compartment depth above subframe	13.0" or 24.5" (Depending on water tank and/or ladder configuration.)
Compartment depth below subframe	24.5"

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

STREETSIDE COMPARTMENT - FRONT (S1)


The interior useable compartment width (not including side ladder rack space required) shall be approximately 41.0" wide.

The compartment door opening shall be approximately 34.0" wide.

- This compartment shall have flush fitting vertically hinged compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be two (2) adjustable shelf/shelves approximately 12" deep. Each shelf shall be fabricated from 3/16" 3003 aluminum sheet with a 2" vertical flange along the front and rear edges. The shelves shall be located at 31" and 50" above the compartment floor.
 - The above component(s) shall have a smooth un-painted finish.
- Restraining straps shall be provided at base of compartment for Boulder Rural Fire Protection District barrel strainer, hose donut and hand tools.
- Lower shelf shall be provided for Boulder Rural Fire Protection District fittings & nozzles.
- Upper shelf shall be provided with low edged removable trays for miscellaneous supplies.



Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- The controls for the specified light tower(s).
- One (1) OnScene Solutions Rough-Service 9" white LED light(s) shall be provided below the body. Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment. Light(s) shall be switchable but activated automatically when the park brake is set.
- The 12 volt electrical distribution panel shall be located in the front upper compartment.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

STREETSIDE COMPARTMENT - ABOVE REAR WHEELS (S2)

The interior useable compartment width shall be approximately 59.5" wide.

The compartment door opening shall be approximately 52.2" wide.

- This compartment shall have a flush fitting horizontally hinged, lift-up style compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be a 3/16" (.188) 3003H-14 alloy smooth aluminum bolt-in vertical panel at compartment back wall for equipment mounting.
 - The above component(s) shall have a smooth un-painted finish.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

STREETSIDE COMPARTMENT - REAR (S3)

The interior useable compartment width shall be approximately 45.0" wide.

The compartment door opening shall be approximately 38.0" wide.

- This compartment shall have flush fitting vertically hinged compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- The floor of the compartment above the frame rails shall be extended to the interior edge of the door. The floor shall have a 2" vertical lip and a 1" return to increase strength.
- There shall be one (1) storage module(s) for air bags. The module shall be fabricated from 1/8" (.125) 3003H-14 aluminum alloy sheet. Circular notches shall be provided along the front edge to ease the access to the air bags. Each bay shall be sized to hold the air bag and a matching piece of 1/2" plywood (plywood not provided).

Module shall be designed to store the following air bags;

- One (1) 24" x 21" w/ 5/8" plywood
- One (1) _____
- There shall be one (1) OnScene Solutions Velcro cargo straps provided to secure the stored equipment.
- Bolted panels shall be installed on upper compartment area side and back walls for mounting necessary brackets, hooks and clamps for Boulder Rural Fire Protection District rescue struts.
 - Paratech Highway Vehicle Kit - VSK
 - Hi-Lift Rescue Jack
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- One (1) OnScene Solutions Rough-Service 9" white LED light(s) shall be provided below the body. Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment. Light(s) shall be switchable but activated automatically when the park brake is set.
- Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CURBSIDE COMPARTMENT - FRONT (C1)

The interior useable compartment width (not including side ladder rack space required) shall be approximately 41.0" wide.

The compartment door opening shall be approximately 34.0" wide.

- This compartment shall have flush fitting vertically hinged compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be two (2) adjustable shelf/shelves approximately 12" deep. Each shelf shall be fabricated from 3/16" 3003 aluminum sheet with a 2" vertical flange along the front and rear edges.
The shelves shall be located at 33.5" and 52.5" from the floor.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) adjustable shelf/shelves approximately 24" deep. Each shelf shall be fabricated from 3/16" 3003 aluminum sheet with a 2" vertical flange along the front and rear edge.
The shelf shall be located at 17.5" from the compartment floor.
 - The above component(s) shall have a smooth un-painted finish.
- One (1) Lista drawer cabinet, model ST-0450-NL-LILO-LG shall be provided in compartment. The Lista cabinet shall be x 28-3/4" wide x 21 5/6" high x 22-1/2" deep. Cabinet shall have three (3) individual locking drawers as follows; one (1) 2", one (1) 3", and one (1) 10". The cabinet shall be Light Gray in color.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

- One (1) OnScene Solutions Rough-Service 9" white LED light(s) shall be provided below the body. Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment. Light(s) shall be switchable but activated automatically when the park brake is set.
- Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CURBSIDE COMPARTMENT - ABOVE REAR WHEEL (C2)

The interior useable compartment width (not including side ladder rack space required) shall be approximately 41.0" wide.

The compartment door opening shall be approximately 34.0" wide.

- This compartment shall have flush fitting vertically hinged compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) adjustable shelf/shelves approximately 12" deep. Each shelf shall be fabricated from 3/16" 3003 aluminum sheet with a 2" vertical flange along the front and rear edges. The shelf shall be located at 20" from the compartment floor.
 - The above component(s) shall have a smooth un-painted finish.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CURBSIDE COMPARTMENT - REAR (C3)

The interior useable compartment width shall be approximately 45.0" wide.

The compartment door opening shall be approximately 38.0" wide.

- This compartment shall have flush fitting vertically hinged compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be two (2) adjustable shelf/shelves approximately 12" deep. Each shelf shall be fabricated from 3/16" 3003 aluminum sheet with a 2" vertical flange along the front and rear edges. The shelves shall be located at 29.75" and 46.5" from the compartment floor.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) 400 lbs. slide-out tray(s) approximately 24" deep and as wide as the compartment layout or door opening permits. The tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length. The tray assembly shall utilize a pneumatic cylinder mounted on underside to hold the tray in both the extended and closed positions.
 - The above component(s) shall have a smooth un-painted finish.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- One (1) OnScene Solutions Rough-Service 9" white LED light(s) shall be provided below the body. Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment. Light(s) shall be switchable but activated automatically when the park brake is set.
- Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

REAR COMPARTMENT - CENTER (RC1)

The rear center compartment shall be located behind the chassis frame rails and depth up to the specified water tank and below the frame rails as much as possible without affecting the angle of departure.

The interior useable compartment width shall be approximately 37.0" wide.

The compartment door opening shall be approximately 34.5" wide.

The compartment shall be open to L3 and R3 on the sides.

- This compartment shall have flush fitting vertically hinged compartment door. The door exterior shall be painted job color.
- The interior door panel shall have a smooth un-painted aluminum panel.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior lower door track to activate compartment lighting and door ajar signal in cab when door is opened.
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring non-locking handle. A gasket shall be placed between handle and door. Door latches shall be a two-point rotary slam, double-catch latch, recessed inside the double panel door with striker plate.
- The hinged door(s) shall have a pneumatic cylinder to hold door in the open and closed positions. Each door shall be capable of being closed without unlatching. Door checks shall be bolted to the compartment door header and the box pan of the door.
- A compartment threshold protection plate shall be installed on the bottom edge of the compartment door opening. The threshold protection shall be fabricated from an aluminum extrusion with an anodized exterior finish.

COMPARTMENT LAYOUT

- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ROPE ANCHOR OR PORTABLE WINCH RECEIVERS

The completed unit shall have an integrated receiver or anchor system for use with removable rope anchor point and/or a portable electric winch, when specified.

Receivers or anchors installed at any location on the apparatus for use as removable winch anchors shall be designed and affixed to provide at least a 2.0 to 1 straight line pull no-yield safety factor over the load rating of the removable winch.

Receivers or anchors installed at any location on the apparatus for use with rope operations shall be designed and affixed to the apparatus to provide at least a 9,000 lbf (40,000 N) no-yield condition with a straight line pull.

A safety sign FAMA28 shall be located on or near each receiver or anchor stating the maximum straight line pull rating.

Side receiver(s) (if specified) shall have the following load rating:

	<u>STRAIGHT PULL</u>	<u>SAFETY FACTOR</u>
Rope Tie Off:	600 Lbs.	15:1
Winch:	5,000 Lbs.	2:1

Front and/or rear receiver(s) (if specified) shall have the following load rating:

	<u>STRAIGHT PULL</u>	<u>SAFETY FACTOR</u>
Rope Tie Off:	600 Lbs.	15:1
Winch:	Winch Load Rating (9,000 Lbs. Max)	2:1

The following items shall be provided to accomplish rope rescue and/or portable winch operation;

ACCESSORIES

- Two (2) removable rope anchor(s) shall be provided for use with lower body specified receivers. Each rope anchor shall be fabricated from 3/4" steel, 2" high x 11.5" long with a 3" OD/2" ID eyelet. Eyelet end shall have radiused edge to prevent damage to rope or carabineer. Each rope anchor shall have a black powder coat paint finish.
- A steel 5/8" x 3" hitch pin shall lock the rope anchor into the receiver tube.
- An aluminum mounting bracket shall be provided to store rope anchor(s) inside a body compartment as close to receiver location as possible.

A portable winch shall be not be provided with completed unit.

REAR BUMPER

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located at the rear bumper for use with removable rope anchor point and/or a portable electric winch (when specified). They shall be located one (1) on each side of the apparatus.
 - The receiver(s) shall have one (1) rubber cover(s) provided.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

LADDER LIFT SYSTEM, CURBSIDE

A Ziamatic 12 VDC, 60 amp, HLAS (Horizontal Ladder Access System), model HLAS-975 shall be provided above the exterior side body compartments, on the curbside.

The lift system shall be electro-hydraulic with built-in electric safety latches and warning alarm when in operation. Access shall still be provided to compartments with system in lowered position. Flashing lights on ends shall produce a visual signal when the system is out of the stored position. A flashing warning light signal shall be provided indicating when a ladder rack is not in a stowed position as required by NFPA 1901. The outward ends of the equipment rack that protrude beyond the body of the apparatus shall have retroreflective material to indicate a hazard or an obstruction.

The ladder control panel shall be located on curbside pump panel. The ladder lift system shall be designed to store the specified ladders and equipment. The side of ladder storage area shall be enclosed with an aluminum panel and painted the same color as body.

LADDER LIFT INTERLOCK

An interlock circuit shall be included on the ladder lift system to prevent the lift from raising if a specified hose bed or compartment doors are in the open position.

Storage shall be provided for the following;

- One (1) 24' 2-section ladder(s). Manufacturer, model number of the ladder shall be provided in equipment section of specification, or at pre-construction meeting when provided by Boulder Rural Fire Protection District.
- One (1) 14' roof ladder(s). Manufacturer, model number of the ladder shall be provided in equipment section of specification, or at pre-construction meeting when provided by Boulder Rural Fire Protection District.
- One (1) 10' folding ladder(s). Manufacturer, model number of the ladder shall be provided in equipment section of specification, or at pre-construction meeting when provided by Boulder Rural Fire Protection District.
- Three (3) pike pole(s). Manufacturer, model number of the pike pole shall be provided in equipment section of specification, or at pre-construction meeting when provided by Boulder Rural Fire Protection District.

Specified:

One (1) 10' NY Hook, Fire Hooks Unlimited

One (1) 12' Rubbish Hook LeatherHead Dogbone

One (1) 8' Rubbish Hook LeatherHead Dogbone

- One (1) 10' length of hard suction hose. Hard suction hose(s) shall be supplied by contractor with completed unit. See equipment section.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

LOWER SIDE BODY PROTECTION - RUB RAIL

OnScene Solutions rub rails shall be provided below the compartment door openings on both the streetside and curbside.

The rub rail shall be fabricated from 6063 extruded aluminum, measuring approximately 2-3/4" high x 1-3/8" thick with tapered aluminum end caps. The rub rail shall be bolted to the body using stainless steel bolts and 1-1/2" diameter x 5/8" thick rubber mount isolators to prevent damage to the body.

The rails shall incorporate LED clearance marker lighting recessed into the rail fascia to avoid damage to the light in case of impact. The rub rail shall have an accessory mounting track integrated into the backside of the rail to allow mounting of accessories such as ground lighting.

3M™ Diamond Grade™ Conspicuity striping shall be provided in the rub rail. The striping shall be red/white in color.

FRONT PROTECTION PANELS

To protect areas subject to intensive wear, scuffing or abuse, protection panels shall be installed on the front vertical body panels and wrapped around to the front compartment door opening. The protection panels shall be fabricated from 20 gauge brushed stainless steel.

REAR BODY HANDRAILS

There shall be two (2) 24" vertical handrails on rear body. Handrails shall be NFPA compliant 1-1/4" knurled 304 stainless steel with welded end stanchions.

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

FOLDING STEPS

There shall be nine (9) Innovative Controls polished cast aluminum folding steps provided and installed on completed unit. Each step shall be heavy duty with stainless steel spring and textured step surface meeting NFPA standards. Each step shall include integrated LED lights. Steps shall be located as follows;

- Three (3) on front streetside of body adjacent to pump panel for access to upper pump module or dunnage area.
- Six (6) on rear of body (3 each side) for access to hose or ladder storage area.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

LOW VOLTAGE ELECTRICAL SYSTEM- 12 VDC

General

Any low voltage electrical systems or warning devices installed on the fire apparatus shall be appropriate for the mounting location and intended electrical load.

Where wire passes through sheet metal, grommets shall be used to protect wire and wire looms. Electrical connections shall be with double crimp water-tight heat shrink connectors.

All 12 VDC wiring running from front to back of vehicle body shall be run in full length electrical wiring raceway down each side of body.

Wiring

All electrical circuit feeder wiring supplied and installed by the fire apparatus manufacturer shall meet the requirements of NFPA Chapter 13.

The circuit feeder wire shall be stranded copper or copper alloy conductors of a gauge rated to carry 125% of the maximum current for which the circuit is protected. Voltage drops in all wiring from the power source to the using device shall not exceed 10%. The use of star washers for circuit ground connections shall not be permitted.

All circuits shall otherwise be wired in conformance with SAE J1292, *Automobile, Truck, Truck-Tractor, Trailer, and Motor Coach Wiring*.

Wiring and Wire Harness Construction

All insulated wire and cable shall conform to SAE J1127, *Low Voltage Battery Cable*, or SAE J1128, *Low Voltage Primary Cable*, type SXL, GXL, or TXL.

All conductors shall be constructed in accordance with SAE J1127 or SAE J1128, except where good engineering practice dictates special strand construction. Conductor materials and stranding, other than copper, shall be permitted if all applicable requirements for physical, electrical, and environmental conditions are met as dictated by the end application. Physical and dimensional values of conductor insulation shall be in conformance with the requirements of SAE J1127 or SAE J1128, except where good engineering practice dictates special conductor insulation. The overall covering of conductors shall be moisture-resistant loom or braid that has a minimum continuous rating of 194°F (90°C) except where good engineering practice dictates special consideration for loom installations exposed to higher temperatures. The overall covering of jacketed cables shall be moisture resistant and have a minimum continuous temperature rating of 194°F (90°C), except where good engineering practice dictates special consideration for cable installations exposed to higher temperatures.

All wiring connections and terminations shall use a method that provides a positive mechanical and electrical connection. The wiring connections and terminations shall be installed in accordance with the device manufacturer's instructions. All ungrounded electrical terminals shall have protective covers or be in enclosures. Wire nut, insulation displacement, and insulation piercing connections shall not be used.

Wiring shall be restrained to prevent damage caused by chafing or ice buildup and protected against heat, liquid contaminants, or other environmental factors.

Wiring shall be uniquely identified at least every 2 ft (0.6 m) by color coding or permanent marking with a circuit function code. The identification shall reference a wiring diagram.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Circuits shall be provided with properly rated low voltage over-current protective devices. Such devices shall be readily accessible and protected against heat in excess of the over-current device's design range, mechanical damage, and water spray. Circuit protection shall be accomplished by utilizing fuses, circuit breakers, fusible links, or solid state equivalent devices.

If a mechanical-type device is used, it shall conform to one of the following SAE standards:

- 1) SAE J156, *Fusible Links*
- 2) SAE J553, *Circuit Breakers*
- 3) SAE J554, *Electric Fuses (Cartridge Type)*
- 4) SAE J1888, *High Current Time Lag Electric Fuses*
- 5) SAE J2077, *Miniature Blade Type Electrical Fuses*

Switches, relays, terminals, and connectors shall have a direct current (dc) rating of 125% of maximum current for which the circuit is protected.

Power Supply

A 12 V or greater electrical alternator shall be provided. The alternator shall have a minimum output at idle to meet the minimum continuous electrical load of the vehicle, at 200°F (93°C) ambient temperature within the engine compartment, and shall be provided with full automatic regulation.

Minimum Continuous Electrical Load

The minimum continuous electrical load shall consist of the total amperage required to simultaneously operate the following in a stationary mode during emergency operations:

- 1) The propulsion engine and transmission
- 2) All legally required clearance and marker lights, headlights, and other electrical devices except windshield wipers and four-way hazard flashers
- 3) The radio(s) at a duty cycle of 10 percent transmit and 90% receive (for calculation and testing purposes, a default value of 5 A continuous)
- 4) The lighting necessary to produce 2 fc (20 lx) of illumination on all walking surfaces on the apparatus and on the ground at all egress points onto and off the apparatus, 5 fc (50 lx) of illumination on all control and instrument panels, and 50 percent of the total compartment lighting loads
- 5) The minimum optical warning system, where the apparatus is blocking the right-of way
- 6) The continuous electrical current required to simultaneously operate any fire pumps, aerial devices, and hydraulic pumps
- 7) Other warning devices and electrical loads defined by the purchaser as critical to the mission of the apparatus

If the apparatus is equipped to tow a trailer, an additional 45 A shall be added to the minimum continuous electrical load to provide electrical power for the federally required clearance and marker lighting and the optical warning devices mounted on the trailer.

The condition of the low voltage electrical system shall be monitored by a warning system that provides both an audible and a visual signal to persons on, in, or near the apparatus of an impending electrical system failure caused by the excessive discharge of the battery set.

The charge status of the battery shall be determined either by direct measurement of the battery charge or indirectly by monitoring the electrical system voltage.

If electrical system voltage is monitored, the alarm shall sound if the system voltage at the battery or at the master load disconnect switch drops below 11.8 V for 12 V nominal systems, 23.6 V for 24 V nominal systems, or 35.4 V for 42 V nominal systems for more than 120 seconds.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

A voltmeter shall be mounted on the driver's instrument panel to allow direct observation of the system voltage.

Electromagnetic Interference

Electromagnetic interference suppression shall be provided, as required, to satisfy the radiation limits specified in SAE J551/1, *Performance Levels and Methods of Measurement of Electromagnetic Compatibility of Vehicles, Boats (up to 15 m), and Machines (16.6 Hz to 18 GHz)*.

Wiring Diagram

A complete electrical wiring schematic of actual system shall be provided with finished apparatus. Similar or generic type electrical schematics shall NOT BE ACCEPTABLE.

Low Voltage Electrical System Performance Test

A low voltage electrical system test certification shall be provided with delivered apparatus.

12 VOLT MULTIPLEX CONTROL CENTER

The apparatus shall be equipped with a Weldon V-MUX multiplexed 12 volt electrical system that will provide complete diagnostic capability, No Exception. The system shall have the capability of delivering multiple signals via a CAN bus, utilizing specifications set forth by SAE J1939. The system shall be node based to maximize stability so that failure of one node does not affect the operation of the other nodes. The system shall use shielded twisted-pair wire for transmission of system function signals. The shielded wire shall provide protection against EMI and RFI noise interruptions.

The multiplex system shall be responsible for providing power management functions as well as load shedding. The warning light system shall be controlled by the multiplex system. The system shall be capable of displaying text and/or graphic messages on a display module. The system shall be based on solid-state technology and shall include self-contained diagnostic indicators.

WELDON CERTIFICATION

A letter shall be provided with bid submittal that the Contractor has successfully completed the Weldon training requirements for Level 1 of the V-MUX Certified Supplier Program and is authorized to design, build, and service V-MUX electrical systems.

The apparatus shall be equipped with a Weldon V-MUX multiplexed 12 volt electrical system that will provide complete diagnostic capability, No Exception. The system shall have the capability of delivering multiple signals via a CAN bus, utilizing specifications set forth by SAE J1939. The system shall be node based to maximize stability so that failure of one node does not affect the operation of the other nodes. The system shall use shielded twisted-pair wire for transmission of system function signals. The shielded wire shall provide protection against EMI and RFI noise interruptions.

The multiplex system shall be responsible for providing power management functions as well as load shedding. The warning light system shall be controlled by the multiplex system. The system shall be capable of displaying text and/or graphic messages on a display module. The system shall be based on solid-state technology and shall include self-contained diagnostic indicators.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

MULTIPLEX SYSTEM INTERFACE DISPLAY

The Weldon V-MUX Vista IV multiplex system interface display(s) shall be provided by the cab/chassis manufacturer. The full-color Vista interface display allows the user to control warning and scene lighting, HVAC controls (when specified), and view on-board diagnostics including service information. This display has a wide operating temperature range, automatic screen switching in response to current conditions, and a sleep mode option to eliminate night glare. The following features shall be included;

- 800 x 480 resolution
- Four video ports
- Flash updates with USB memory stick
- Display inside and outside temperature (when specified)
- Automatic climate control (when specified)
- 100% Configurable (OEM Level)
- Field re-programmable
- Peer to peer network
- On-board diagnostics / service information
- Colors change to indicate button status
- Video Ready for: Backup camera, Thermal camera, DVD, GPS...

BATTERY SYSTEM

The battery connectors shall be heavy duty type with cables terminating in heat shrink loom. Heavy duty battery cables shall provide maximum power to the electrical system. Where required, the cables shall be shielded from exhaust tubing and the muffler. Large rubber grommets shall be provided where cables enter the battery compartment.

Batteries shall be of the high-cycle type. With the engine off, the battery system shall be able to provide the minimum continuous electrical load for 10 minutes without discharging more than 50 percent of the reserve capacity and then to restart the engine. The battery system cold cranking amps (CCA) rating shall meet or exceed the minimum CCA recommendations of the engine manufacturer. The batteries shall be mounted to prevent movement during fire apparatus operation and shall be protected against accumulations of road spray, snow, and road debris. The batteries shall be readily accessible for examination, testing, and maintenance.

A means shall be provided for jump-starting the engine if the batteries are not accessible without lifting the cab of a tilt-cab apparatus.

Where an enclosed battery compartment is provided, it shall be ventilated to the exterior to prevent the buildup of heat and explosive fumes. The batteries shall be protected against vibration and temperatures that exceed the battery manufacturer's recommendation.

An onboard battery conditioner or charger or a polarized inlet shall be provided for charging all batteries. Where an onboard conditioner or charger is supplied, the associated line voltage electrical power system shall be installed in accordance with Chapter 22.

One of the following master disconnect switches shall be provided:

- 1) A master body disconnect switch that disconnects all electrical loads not provided by the chassis manufacturer
- 2) A master load disconnect switch that disconnects all electrical loads on the apparatus except the starter

Electronic control systems and similar devices shall be permitted to be otherwise connected if so specified by their manufacturer.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

The alternator shall be wired directly to the batteries through the ammeter shunt(s), if one is provided, and not through the master load disconnect switch.

A green "battery disconnect on" indicator light that is visible from the driver's position shall be provided.

Rechargeable hand lights, radios, and other similar devices shall be permitted to be connected to the electrical system ahead of the master disconnect switch.

A sequential switching device shall be permitted to energize the optical warning devices and other high current devices required in minimum continuous electrical load, provided the switching device shall first energize the electrical devices required in minimum continuous electrical load within 5 seconds.

BATTERY SWITCH

One (1) "battery disconnect on" switch in cab located within easy reach of Driver with green indicator light that is visible from the driver's position shall be provided. The switch and indicator light shall be supplied and installed by the cab/chassis manufacturer.

BATTERY SOLENOID

Battery switch shall consist of a minimum 200 ampere, constant duty solenoid to feed from positive side of battery.

BATTERY CONDITIONER

The battery conditioner shall be supplied and installed by the cab chassis manufacturer.

ENGINE COMPARTMENT LIGHT

Engine compartment light(s) shall be supplied and installed by the cab chassis manufacturer.

CAB HAZARD WARNING LIGHT

A red flashing or rotating light, located in the driving compartment. The light shall be furnished by the cab/chassis manufacturer. The light shall be illuminated automatically whenever the vehicles parking brake is not fully engaged and any of the following conditions exist:

- Any passenger or equipment compartment door is not closed.
- Any ladder or equipment rack is not in the stowed position.
- Stabilizer system is not in its stowed position.
- Powered light tower is not stowed.
- Any other device permanently attached to the apparatus is open, extended, or deployed in a manner that is likely to cause damage to the apparatus if the apparatus is moved.

Compartments and equipment meeting all of the following conditions shall be permitted to be exempt from being wired to the hazard light:

- The volume is less than or equal to 4 ft³ (0.1 m³).
- The compartment has an opening less than or equal to 144 in.² (92,900 mm²).
- The open door does not extend sideways beyond the mirrors or up above the top of the fire apparatus.
- All equipment in the compartment is restrained so that nothing can fall out if the door is open while the apparatus is moving.
- Manually raised pole lights with an extension of less than 5 ft (1.5 m).

The hazard light shall be labeled "DO NOT MOVE APPARATUS WHEN FLASHING".

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

BACK-UP ALARM

An electronic back-up alarm shall be supplied and installed by the cab/chassis manufacturer. The back-up alarm shall actuate automatically when the transmission gear selector is placed in reverse.

REAR VIEW CAMERA

The cab chassis provided rear view camera shall be installed on the rear of the body.

TAIL LIGHTS

Rear body tail lights shall be vertically mounted and located per Federal Motor Vehicle Safety Standards, FMVSS and Canadian Motor Vehicle Safety Standards CMVSS. The following lights shall be furnished;

- Position 1 shall be Two (2) Whelen specified lower Zone "C" warning lights
- Position 2 shall be Two (2) Whelen M6 Series M6BTT red LED stop/tail lights
- Position 3 shall be Two (2) Whelen M6 Series M6T amber LED turn signal lights
- Position 4 shall be Two (2) Whelen M6 Series M6BUW LED back-up lights with clear lens

Each of the lights above shall be mounted in an M6FCV4, 4-light chrome finish bezels.

MIDSHIP MARKER/TURN SIGNAL

Two (2) Whelen model T0A00MAR 2" round amber LED midship body clearance marker/turn signal lights shall be provided and installed, one (1) light on each side of the body, in forward wheel well of rear axle. Midship marker/turn lights shall be wired to the headlight circuit of the chassis.

MARKER LIGHTS

The body shall be equipped with all necessary side and rear clearance lights and reflectors in accordance with Federal Motor Vehicle Safety Standards (FMVSS) and Canadian Motor Vehicle Safety Standards (CMVSS). Clearance lights shall be Truck-Lite model 18 series, 3 diode LED, reflectorized type to reduce the need for maintenance and lower the amp draw. Clearance lights on body shall be connected to the clearance light circuit of the chassis.

CAB STEP LIGHTS / GROUND LIGHTS

The step lights and/or ground lights shall be supplied and installed by the cab/chassis manufacturer. Light(s) shall be capable of providing illumination at a minimum level of 2 fc (20 lx) on ground areas within 30 in. (800 mm) of the edge of the vehicle in areas designed for personnel to climb onto or descend from the vehicle to the ground level.

Lighting designed to provide illumination on areas under the driver and crew riding area exits shall be switchable but activated automatically when the exit doors are opened.

LICENSE PLATE LIGHT

One (1) Arrow #437 chrome plated LED license plate light shall be installed on the rear of the body. License plate light shall be wired to the headlight circuit of chassis. A fastener system shall be provided for license plate installation.

ELECTRONIC SIREN

The siren control head shall be supplied and installed by the cab/chassis manufacturer, if required by Boulder Rural Fire Protection District. Siren power shall be wired through the master warning light switch.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FRONT LED FLOODLIGHT

One (1) Rigid Industries E-Series model 130312, 30" combination spot/flood LED light(s) with white housing color and cradle mount brackets shall be provided on front of vehicle. The E-Series 30" LED light(s) shall have 13,800 lumen output each.

Each light shall be wired directly to the 12 VDC electrical system with stranded copper wire. The floodlights shall be protected with circuit breakers rated at the proper amperage and wire size.

The lights shall be controlled at the multiplex display(s) in the cab.

SIDE LED SCENE LIGHTS

There shall be four (4) Whelen M9 Series Model M9LZC , 9" x 7" surface mounted scene light(s) provided on the upper body. Light quantity shall be divided equally per side. The M9LZC configuration shall consist of 24 clear Super-LEDs and a clear gradient optic polycarbonate lens with chrome flange. The M9LZC series light shall have 6,500 useable lumens each. The scene light is covered by a five year factory warranty.

Two (2) switches shall be provided, one (1) for the streetside scene lights, and one (1) for the curbside scene lights.

The lights shall be controlled at the multiplex display(s) in the cab.

LIGHT TOWER

One (1) Command Light Knight 2, KL Series light tower(s) shall be provided and installed on the completed unit.

The Command Light shall be covered by a five (5) year limited warranty from defects in materials and workmanship. An operation, maintenance, and parts manual shall be provided with the completed unit.

Light Tower Construction and Design

The Command Light assembly shall be of aluminum construction, with stainless steel shafts and bronze bushings for long life and low maintenance.

The electrically controlled unit shall not require usage of the vehicle's air supply for operation, thereby eliminating the chance for air leaks in the vehicle braking system. Hydraulic or pneumatic type floodlights are not acceptable alternatives to the specified all electric light tower.

The light tower shall be tested to in wind conditions of 90 mph (150 kph) minimum. Other type floodlights that have not been tested to these conditions are not acceptable.

The light tower shall be capable of overhanging the side or back of the vehicle to provide maximum illumination to the vicinity adjacent to the vehicle for the safety of emergency personnel in high traffic conditions. Any tower that is only capable of rotations at the top of a pole is not an acceptable alternative to the specified tower.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Light Tower Electrical System

The light tower shall be a two-stage articulating device with a lighting bank on top of the second stage capable of continuous 360 degree rotation. The light shall be elevated by electric linear actuators, one (1) actuator shall elevate the light bank and one (1) actuator shall adjust the light bank angle from 0 to 110 degrees. Power for the light bank shall be supplied through power collecting rings thus allowing continuous 360 degree rotation in either direction.

The tower base shall have a light that illuminates the envelope of motion during any movement of the light tower mast per NFPA 1901.

A red flashing or rotating light located in the driving compartment shall be illuminated automatically whenever the vehicles parking brake is not fully engaged, indicating that the light tower is not in stowed position, as required by NFPA 1901.

Light Tower Floodlights

The Command Light model KL415D-W2 shall be equipped with the following bank of floodlights:

Floodlight manufacturer:	Whelen Engineering
Number of lamp heads:	Four (4) Pioneer Plus PFH2BLED
Voltage:	12 VDC
Watts of each lamp head:	150 watt
Total watts of light tower:	750 watts
Total lumens of light tower:	71,000
Configuration:	The light heads shall be mounted with two (2) on each side of the light tower, giving two (2) vertical lines of two (2) when the lights are in the upright position.

Light Tower Paint

The light tower shall be electro-statically powder coated with a hammer tone gray color.

Light Tower Controls

The light tower(s) shall be operated with a hand-held 15-foot umbilical line remote control. The storage station for the remote control unit shall be equipped with a button to activate the "Auto-Park" automatic nesting feature. The remote control shall be located per the itemized compartment list and include;

Three (3) switches; one (1) for each pair of lights.

One (1) switch for light bank rotation.

One (1) switch for elevating lower stage.

One (1) switch for elevating upper stage.

One (1) switch for optional light bank rotation.

One (1) switch for the optional strobe.

One (1) indicator light to indicate when light bank is out of the roof nesting position.

One (1) indicator light to indicate when light bank is rotated to proper nesting position.

Light Tower Mounting

The specified light tower(s) shall be mounted on the roof of the body.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SCENE LIGHTS

The scene lighting shall be provided with specified upper side and/or rear warning lights.

TRAFFIC ADVISOR LIGHTS

A traffic advisor system shall be provided on rear of vehicle using; eight (8) Whelen Wide-angle ION series amber Super-LED lights with clear lens, and 25 Scan-Lock™ flash patterns. The center pair of lights shall be split amber/red. The red lights shall be connected to the brake light circuit on vehicle. Lights shall be individually mounted with chrome bezels and evenly distributed to rear, if split by a hose bed, or walkway.

The lights shall be controlled by the multiplexing system and provide; Left Arrow, Right Arrow, Center Out, and Wig-Wag patterns. The wig-wag light pattern shall be activated with the E-Master and can be switched to the other patterns at any time through the "TRAFFIC ADVISOR" menu on the Multiplex display.

DAVID CLARK INTERCOM SYSTEM

The following David Clark intercom system shall be provided and installed to improve the safety of firefighters and rescue professionals through enhanced communication and hearing protection. System shall have the following major components as minimum;

- One (1) U3816 Dual PTT Radio Interface headset jack for officer
- One (1) U3811 headset jack w/PTT For Driver
- Two (2) U3802 intercom headset jack for crew positions
- One (1) U3801 intercom headset jack for crew positions
- U3800 Control station
- Five (5) H3442 Dual Ear Headsets
- Necessary cables and connectors

Final location of all components shall be verified after chassis arrival.

INTERCOM SYSTEM INSTALLATION

The above listed intercom system shall be installed in the cab locations as follows;

Front of Cab

- Driver's – Mounted above the right shoulder position on ceiling.
- Officer's – Mounted above the left shoulder position on ceiling.

Rear Crew Area

- Driver's side rear facing – Above the right shoulder on the wall or ceiling.
- Rear facing center – Above the left shoulder on the ceiling.
- Officer's side rear facing – Above the left shoulder on the wall or ceiling.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

WARNING LIGHT PACKAGE

Each apparatus shall have a system of optical warning devices that meets or exceeds the requirements of this section.

The optical warning system shall consist of an upper and a lower warning level. The requirements for each level shall be met by the warning devices in that particular level without consideration of the warning devices in the other level.

For the purposes of defining and measuring the required optical performance, the upper and lower warning levels shall be divided into four (4) warning zones. The four zones shall be determined by lines drawn through the geometric center of the apparatus at 45 degrees to a line drawn lengthwise through the geometric center of the apparatus. The four (4) zones shall be designated A, B, C, and D in a clockwise direction, with zone A to the front of the apparatus.

Each optical warning device shall be installed on the apparatus and connected to the apparatus's electrical system in accordance with the requirements of this standard and the requirements of the manufacturer of the device.

A master optical warning system switch that energizes all the optical warning devices shall be provided.

The optical warning system on the fire apparatus shall be capable of two (2) separate signaling modes during emergency operations. One (1) mode shall signal to drivers and pedestrians that the apparatus is responding to an emergency and is calling for the right-of-way. One (1) mode shall signal that the apparatus is stopped and is blocking the right-of-way. The use of some or all of the same warning lights shall be permitted for both modes provided the other requirements of this chapter are met.

A switching system shall be provided that senses the position of the parking brake or the park position of an automatic transmission. When the master optical warning system switch is closed and the parking brake is released or the automatic transmission is not in park, the warning devices signaling the call for the right-of-way shall be energized. When the master optical warning system switch is closed and the parking brake is on or the automatic transmission is in park, the warning devices signaling the blockage of the right-of-way shall be energized. The system shall be permitted to have a method of modifying the two (2) signaling modes.

The optical warning devices shall be constructed or arranged so as to avoid the projection of light, either directly or through mirrors, into any driving or crew compartment(s). The front optical warning devices shall be placed so as to maintain the maximum possible separation from the headlights.

Steadily burning, non flashing optical sources shall be permitted to be used.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

UPPER LEVEL OPTICAL WARNING DEVICES

The upper-level optical warning devices shall be mounted as high and as close to the corner points of the apparatus as is practical to define the clearance lines of the apparatus. The upper-level optical warning devices shall not be mounted above the maximum height, specified by the device manufacturer.

ZONE A - FRONT WARNING LIGHTS

The light bar shall be supplied and installed by the cab/chassis manufacturer.

ZONES B AND D - SIDE WARNING LIGHTS

UPPER REAR CORNER WARNING LIGHTS

There shall be two (2) Whelen R416AF series Roto-Beam Super-LED beacons with amber lens provided on the rear of the body, one (1) each side in the upper corners. The high profile beacon will meet NFPA zone C upper requirements and is covered by a five year factory warranty.

The lights shall be controlled at the multiplex display(s) in the cab.

UPPER FORWARD CORNER WARNING LIGHTS

There shall be two (2) Whelen M9 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

Each light shall have a chrome flange.

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONE C - REAR WARNING LIGHTS

There shall be two (2) Whelen M9 V-series combination 180° red linear Super-LED warning lights with 45° perimeter scene lights (M9V2R) provided, one (1) each side. Perimeter scene lights will be turned on with specified scene lighting. Each light shall have a red lens over warning light and clear lens over perimeter light and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

LOWER LEVEL OPTICAL WARNING DEVICES

To define the clearance lines of the apparatus, the optical center of the lower-level optical warning devices in the front of the vehicle shall be mounted on or forward of the front axle centerline and as close to the front corner points of the apparatus as is practical.

The optical center of the lower-level optical warning devices at the rear of the vehicle shall be mounted on or behind the rear axle centerline and as close to the rear corners of the apparatus as is practical. The optical center of any lower-level device shall be between 18 in. and 62 in. (460 mm and 1600 mm) above level ground for large apparatus, and 18 in. and 48 in. (460 mm and 1600 mm) above level ground.

A midship optical warning device shall be mounted right and the left sides of the apparatus if the distance between the front and rear lower-level optical devices exceeds 25 ft (7.6 m) at the optical center. Additional midship optical warning devices shall be required, where necessary, to maintain a horizontal distance between the centers of adjacent lower-level optical warning devices of 25 ft (7.6 m) or less. The optical center of any midship mounted optical warning device shall be between 18 in. and 62 in. (460 mm and 1600 mm) above level ground.

ZONE A - FRONT WARNING LIGHTS

The warning lights shall be supplied and installed by the cab/chassis manufacturer. They shall be Whelen lights to complete an NFPA compliant lower level warning light system.

ZONES B AND D - CAB INTERSECTOR LIGHT (CAB FRONT CORNERS)

There shall be two (2) Whelen M6 series red linear Super-LED lights (M6R) provided, one (1) each side. Each light shall have a red lens and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONES B AND D - BODY LIGHT (PUMP PANEL)

There shall be two (2) Whelen surface mount ION Series LED light(s) with wide angle optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns. Component shall be covered by a five year Whelen factory warranty.

Each light shall have:

- Red LEDs
- Clear Lens
- Black Flange

Pump panel warning lights shall be provided with an interlock with "OK to Pump" circuit so that lights do not illuminate when pump in operation.

The lights shall be controlled at the multiplex display(s) in the cab.

There shall be two (2) Whelen M6 series red linear Super-LED lights (M6R) provided, one (1) each side. Each light shall have a red lens and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ZONES B AND D - BODY LIGHT (BODY WHEELWELL AREA)

There shall be two (2) Whelen M6 series red linear Super-LED lights (M6R) provided, one (1) each side. Each light shall have a red lens and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONES B AND D - BODY INTERSECTOR LIGHT (BODY REAR CORNERS)

There shall be two (2) Whelen ION Wide Series (6" x 1 3/4") red Super-LED surface mount lights (WIONSMCR) provided, one (1) on each side. The wide angle warning light shall incorporate six red Super-LEDs. The self-contained flashing light shall have 75 Scan-Lock™ flash patterns including steady burn with hi/low power and covered by a five year factory warranty. Each light shall have a clear lens and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONE C - REAR WARNING LIGHTS (LOWER REAR CORNERS)

There shall be two (2) Whelen M6 series red linear Super-LED lights (M6R) provided, one (1) each side. Each light shall have a red lens and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

FIRE PUMP SYSTEM

The following equipment shall be furnished and installed to supply water to the emergency scene:

SIDE MOUNT PUMP MODULE

The side mount pump enclosure shall be removable and supported from the chassis frame rails with spring type body mounts. This enclosure shall allow independent flexing of the pump enclosure from the body and allow for quick removal. The support structure shall be constructed of extruded aluminum tubing and angle.

All pump suction and discharge controls are to be mounted on the driver side pump operator's panel so as to permit operation of the pump from a central location. The fire pump, valves and controls shall be accessible for service and maintenance as required by applicable sections of NFPA standards.

The "master" gauges shall be suitably enclosed and mounted on a full pump compartment width "hinged" gauge panel constructed of the same material as the pump operators control panel, allowing access to the backside of all gauges and gauge lines. The individual gauges shall be mounted inline with the control handle or adjacent to the control handle. Panel is to include a stainless steel piano hinge, flush mounted chrome plated trigger latch, and stainless steel cable end stops. Electrical wiring and all gauge lines shall be properly tie wrapped to prevent kinking or cutting of the lines when the panel is opened.

The following controls and equipment shall be provided on the pump panel or within the pump enclosure:

- Primer system
- Pump and plumbing area LED service light(s).
- Pressure control device and/or throttle control.
- Fire pump and engine instruments.
- Pump intakes and discharge controls.
- Master intake and discharge gauges.
- Tank fill control.
- Tank suction control.
- Water tank level gauge.
- Pump panel LED light(s).

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

PUMP MODULE SERVICE ACCESS

The front of pump module shall have two (2) removable service access doors. Each door shall be easily removable with chrome plated trigger latches and over-sized hand holes for ease in removal and replacement. Doors shall be fabricated from 1/8" aluminum treadplate.

PUMP MODULE TOP

The top of pump module shall be fabricated from 3/16" aluminum NFPA compliant treadplate.

PUMP PANEL - SIDE MOUNT

The pump operator's panel, along with the lower streetside and curbside pump panels shall be constructed of smooth plate aluminum with powder coated paint finish, fastened to the pump enclosure with 1/4" stainless steel bolts.

The instrument area shall have a stainless steel continuous hinge that shall swing towards the front of the module for easy access to gauges.

STREETSIDE PUMP PANEL - BOLTED

The streetside pump panel shall be fastened to the pump enclosure with 1/4" stainless steel bolts and Nutserts.

CURBSIDE PUMP PANEL - BOLTED

The curbside pump panel shall be fastened to the pump enclosure with 1/4" stainless steel bolts and Nutserts.

TRANSVERSE COMPARTMENT

The upper section of pump module shall be provided with one (1) transverse storage compartment with hinged lift-up doors. The compartments will be designed for the following long tools and equipment:

- The list of items to be stored in the transverse module shall be determined at the pre-construction meeting.

STREETSIDE RUNNING BOARD - SIDE MOUNT PANEL

The streetside pump panel shall be equipped with a side running board. The running board shall extend along the width of the pump module.

The running board stepping surface shall be constructed of aluminum NFPA compliant tread plate, bolted in place with stainless steel fasteners.

The running board shall contain a hose well with a minimum of 9" width designed to carry 25' of 5.0" soft suction hose with hold down provisions.

Two (2) OnScene Velcro style straps shall be provided to hold suction hose in place.

A safety sign FAMA22, which warns of the need to secure hose, shall be visible to personnel at each hose storage area.

- One (1) OnScene 8" Access white LED ground light(s) shall be provided below the body. Light(s) shall be switchable but activated automatically when the park brake is set.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CURBSIDE RUNNING BOARD - SIDE MOUNT PANEL

The curbside pump panel shall be equipped with a side running board. The running board shall extend along the width of the pump module.

The running board stepping surface shall be constructed of aluminum NFPA compliant tread plate, bolted in place with stainless steel fasteners.

The running board shall contain a hose well with a minimum of 9" width designed to carry a 25' of 5.0" soft suction hose with hold down provisions.

Two (2) OnScene Velcro style straps shall be provided to hold suction hose in place.

A safety sign FAMA22, which warns of the need to secure hose, shall be visible to personnel at each hose storage area.

- One (1) OnScene 8" Access white LED ground light(s) shall be provided below the body. Light(s) shall be switchable but activated automatically when the park brake is set.

PUMP MODULE FINISH

The pump module framework shall be painted body color choice.

OPEN PUMP PANELS

The pump panels shall be an open design. No roll-up compartment doors are required to cover or protect pump panels.

PUMP MODULE HEATER

The pump module shall be provided with one (1) Red Dot 35,000 BTU hot water type heater(s). The heater(s) shall be connected to the chassis engine cooling system and have three-speed, 12 volt blower. The cooling system lines shall be insulated and be provided with 1/4 turn shut-off valves to isolate system, if required.

The pump operator's panel shall have an Innovative Controls switch panel for heat control switch with indicator light. Switch shall be constantly illuminated and labeled.

CROSS LAY

The specified pump module shall not have a cross lay provided.

SPEED LAY

The specified pump module shall not have a speed lay provided.

WATEROUS CU FIRE PUMP

A mid-ship mounted Waterous CU series full body fire pump shall be provided. The pump shall comply with all applicable requirements of the latest standards for automotive fire apparatus of the National Fire Protection Association, NFPA 1901, and shall have a rated capacity of 1,500 GPM (6,000 LPM) to 2,250 GPM (9,000 LPM) depending on final configuration.

WATEROUS PUMP ANODES

There shall be two (2) anodes provided with the fire pump. One (1) anode shall be installed in the left steamer port and one (1) shall be installed in the right steamer port.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

IMPELLERS

The pump impellers shall be bronze, specifically designed for the fire service and accurately balanced for vibration free running. The stripping edges shall be located on opposite sides of the impellers to reduce shaft deflection.

The impeller shaft shall be stainless steel, accurately ground to size and supported at each end by oil or grease lubricated anti-friction ball bearings for rigid, precise support. The bearings used on the impeller shaft shall be automotive type bearings, easily cross-referenced and readily available at normal parts or bearing stores.

FLAME PLATED IMPELLER HUBS

The impeller hubs shall be flame plated with tungsten carbide to a hardness approximately twice that of tool steel to assure maximum pump life and efficiency. During the flame plating process the base metal shall not be allowed to exceed a temperature of 300 degrees Fahrenheit to prevent altering the metallurgical properties of the impeller material.

IMPELLER WEAR RINGS

The pump shall be equipped with replaceable bronze wear rings for increased pump life and minimum maintenance cost. The wear rings shall be designed to fit into a groove in the face of the impeller hubs forming a labyrinth that, as the clearance increases with age, directs water from the discharge side in several directions eventually exiting outward, away from the eye of the impeller hub.

PUMP CASING

The pump casing shall be cast as two (2) horizontally split pieces. The casing shall be made of high tensile, close-grained gray iron with a minimum tensile strength of 40,000 PSI.

PUMP MANUAL

Two (2) Pump Operation & Maintenance manual(s) shall be supplied at the time of delivery.

PUMP TEST RATING

The fire pump shall be tested at 1,500 GPM (6,000 LPM) @ 150 PSI (1,134 Kpa).

PAINT FINISH

The pump manufacturer shall provide a black finish paint.

PUMP TRANSMISSION

The pump transmission shall be of the latest design, incorporating a high strength involute tooth-form Morse Hy-Vo chain capable of operating at high speeds while providing smooth and quiet transmission of power. Drive and driven sprockets shall be made of alloy steel with teeth of an involute form. Driveline shafts shall be made from alloy steel forgings, hardened and ground to size. Deep groove, anti-friction ball bearings shall be used throughout the pump transmission. The pump shift engagement shall be accomplished by a free sliding collar that uses an internal locking mechanism to insure that the collar will stay in road or pump position.

An interlock system shall be provided to prevent the pump drive system from being shifted out of "pump engaged" pumping mode of operation when the chassis transmission is in pump gear per NFPA 1901 section 16.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Primary lubrication for the pump transmission bearings, sprockets and chain shall be provided by a splash system. A supplementary pressure system shall also be employed which shall include a strainer, an oil circulation pump driven by the impeller shaft, and a spray bar inside the case to apply oil to the inside of the chain just before it engages the driven sprocket.

The pump and transmission shall be easily separable. A two-piece shaft shall be splined allowing for individual repair of either the pump or transmission, to keep down time to a minimum.

All driveline components shall have a torque rating equal to or greater than the final net engine torque.

AIR OPERATED PUMP SHIFT

The pump shift actuating mechanism shall be air operated from a valve in the cab identified as "PUMP SHIFT". Full instructions for shifting the pump shall be inscribed on the valve plate.

Two (2) green indicator lights shall be supplied in the cab; one (1) light shall indicate when the chassis transmission is in neutral and labeled "OK TO PUMP", and one (1) light shall indicate when the pump drive (PTO) has been engaged and labeled "PUMP ENGAGED".

Two (2) green indicator lights shall be supplied at the Pump Operator's panel adjacent to the engine throttle controls; one (1) light shall indicate when the pump drive has been engaged and labeled "THROTTLE READY", and one (1) light shall indicate when both the chassis transmission is in neutral and the pump drive (PTO) has been engaged and labeled "OK TO PUMP".

PUMP SHIFT MANUAL OVERRIDE

A manual pump shift override system shall be provided should a problem develop in the chassis air brake system. Controls for the override shall be located at the lower right hand corner of the left side pump panel. A "MANUAL PUMP SHIFT" label shall be provided near the pump shift controls.

The "Pump Engaged," "OK to Pump," "OK to Pump-and-Roll," and "Throttle Ready" indicators and the pump operator's panel engine speed advancement interlock system shall be operationally functional when the manual override device is used to shift the pump.

PAINT FINISH

The pump manufacturer shall provide a black finish paint.

PUMP DRIVELINE

The pump transmission driveline shall be supplied with 1710 series yokes and bearings to match the cab chassis driveline.

MECHANICAL SEALS

The pump shall be equipped with self-adjusting, maintenance free mechanical shaft seals that shall not require manual adjustment. These seals shall be designed in a manner such that they shall remain functional enough to permit continued use of the pump in the unlikely event of a seal failure.

SINGLE STAGE FIRE PUMP

The pump shall be a single stage centrifugal class "A" rated fire pump, designed specifically for the fire service

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

1/2" PUMP COOLER LINE

There shall be a 1/2" line installed from the discharge side of the pump to the water tank. The line shall be used to cool the pump during long periods of pumping when water is not being discharged. The pump cooler shall be controlled with a quarter-turn ball valve on main pump panel, and shall be clearly labeled "Pump Cooler".

PUMP COOLER CHECK VALVE

There shall be a check valve installed in the pump cooler line to prevent tank water from back flowing into the pump when it is not in use.

WATEROUS FIVE YEAR PUMP WARRANTY

The fire pump shall be warranted by Waterous for a period of five (5) years from the date of delivery to the Boulder Rural Fire Protection District.

FIRE PUMP TEST

The pump shall undergo a fire pump test per applicable sections of NFPA 1901 or 1906 standards, prior to delivery of the completed apparatus.

The test shall include at least the pumping test, the pumping engine overload test, the pressure control system test, the priming device tests, and a vacuum test.

The entire pump, both suction and discharge passages, shall be hydrostatically tested to a pressure of 500 psi (3400 kPa) for a minimum for 10 min.

The pump shall be capable of producing fire streams that are free from objectionable pulsation under all normal operating conditions.

The results of this test shall be furnished with the vehicle on delivery.

FIRE PUMP TEST LABEL

A test plate shall be provided at the pump operator's panel that gives the rated discharges and pressures together with the speed of the engine as determined by the certification test for each unit, the position of the parallel/series pump as used, and the governed speed of the engine as stated by the engine manufacturer on a certified brake horsepower curve

SAFETY SIGN

A safety sign FAMA25, which warns of the need for training prior to operating the apparatus, shall be located on the pump operators panel.

ALTITUDE REQUIREMENT

The apparatus shall be designed to meet the specified rating at 5,000 feet (1,525 meters) altitude.

PUMP DRAIN VALVE

The pump drain shall be controlled at the pump operator's panel and identified as "Pump Drain". The control shall be a Waterous push-pull type control that is easily actuated with a gloved hand.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

AIR PRIMING PUMP CONTROL

The priming pump shall be a Trident Emergency Products compressed air powered, high efficiency, multi-stage venturi based AirPrime System.

The priming pump shall be rigidly attached to the pump transmission and utilizes air supplied from the chassis air system to operate the pump primer. The AirPrime is more efficient and reliable than the conventional electric motor driven primers, and virtually eliminates the impact load on the vehicles electrical system improving the reliability of the vehicle. AirPrime also improves performance in the elapsed time for establishing water supply resulting in improved fire ground operations and safety.

The primer shall be capable of priming the pump through a 20' section of suction hose with a 10' lift within 30 seconds for pumps less than 1,500 gpm, and 45 seconds for pumps 1,500 gpm and larger.

AIRPRIME CONTROL

A manual rocker switch with Auto-Prime / Off / Manual-Prime shall be provided on main pump operator's panel.

DISCHARGE RELIEF VALVE

The discharge pressure relief shall be controlled by the electronic engine controlled device as specified.

6" SUCTION INLET - STREETSIDE

One (1) 6" (150 mm) un-gated suction intake shall be installed on the streetside pump panel to supply the fire pump from an external water supply. The intake threads shall be 6" NHM threads.

The suction fittings shall include a removable die-cast screen to provide cathodic protection for the pump thus reducing corrosion.

A short steamer barrel may be required to accommodate an intake valve without exceeding the legal overall body width.

SUCTION INTAKE VALVE, (6" / 150 mm)

An Akron Brass 7982 intake valve with 6" (150 mm) NHF thread and rocker lug on panel side shall be provided on suction intake. The intake valve shall be constructed of lightweight, corrosion resistant, hard-anodized aluminum and stainless steel. The valve shall have an adjustable (50-250 PSI) relief valve, 3/4" air bleeder that discharges at the same location as the pressure relief valve, 30° down angle inlet with adjustable rotational positions, a stainless ball sector, durable non-stick seat, and a minimum 4 1/2" diameter waterway. A position indicator shall be included to indicate position of ball. A 12.5" diameter hand wheel shall be included to operate valve open and close functions. The valve shall not exceed 7 PSI friction loss at 2,000 gpm and 14.875" depth and carry a 10 year warranty against corrosion and manufacturer defects.

- The intake shall be provided with a 5" Storz blind cap with hardcoat finish and retaining chain.

6" SUCTION INLET - CURBSIDE

One (1) 6" (150 mm) un-gated suction intake shall be installed on the curbside pump panel to supply the fire pump from an external water supply. The intake threads shall be 6" NHM threads.

The suction fittings shall include a removable die-cast screen to provide cathodic protection for the pump thus reducing corrosion.

A short steamer barrel may be required to accommodate an intake valve without exceeding the legal overall body width.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

SUCTION INTAKE VALVE (6" ELECTRIC)

The suction intake shall be provided with an Akron Brass 7960 series slow-operating, actuated type 6" (150 mm) butterfly valve with a 3/4" air bleeder valve behind pump panel. Valve shall have a 6" male NH thread through panel opening.

- The intake shall be provided with a 6" NHF swivel rocker lug x 5" Storz 30 degree down sweep elbow with hardcoat finish.
- The intake shall be provided with a 5" Storz blind cap with hardcoat finish and retaining chain.

MIV INTAKE RELIEF VALVE

An Akron Brass model 53 intake pressure relief valve shall be provided on the specified master intake valve. The intake pressure relief valve shall have a flange to allow mounting to a 4-bolt pump intake flange. The unit shall be adjustable from 50 to 250 psi and be factory set at 125 psi. Provisions for adjusting or servicing the valve {will/shall} be provided.

The relief outlet shall be directed below the pump with the discharge terminating in a 2-1/2" NSTM connection. The discharge shall be away from the pump operator and labeled "DO NOT CAP".

- An Akron 9323 Navigator Pro electric valve position controller and wire harness with full color LCD display visible from all angles, true position feedback, user programmable presets, % open text shown on valve bar graph, and VMUX capable integration shall be located on the pump operator's panel.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

HEAT EXCHANGER

A heat exchanger shall be provided by the cab chassis manufacturer on the pump driving engine cooling system that permits water from the discharge side of the pump to cool the coolant circulating through the engine cooling system without intermixing. The heat exchanger should maintain the temperature of the coolant in the pump drive engine not in excess of the engine manufacturer's temperature rating under all pumping conditions. A drain(s) should be provided to allow draining of the heat exchanger to prevent damage from freezing.

The cooling system shall be controlled by a 1/4 turn valve on the pump operator's panel.

INTAKE RELIEF VALVE

An Akron Brass model 53 intake pressure relief valve shall be provided. The intake pressure relief valve shall have a flange to allow mounting to a 4-bolt pump intake flange. The unit shall be adjustable from 50 to 250 psi and be factory set at 125 psi. Provisions for adjusting or servicing the valve {will/shall} be provided.

The relief outlet shall be directed below the pump with the discharge terminating in a 2-1/2" NSTM connection. The discharge shall be away from the pump operator and labeled "DO NOT CAP".

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

FOAM SYSTEM

The apparatus shall be equipped with a FoamPro 2001 electronic, fully automatic, variable speed, direct injection, discharge side foam proportioning system. The system shall be capable of handling Class A foam concentrates and most Class B foam concentrates. The foam proportioning operation shall be based on direct measurement of water flows, and remain consistent within the specified flows and pressures. System must be capable of delivering accuracy to within 5% of calibrated settings over the advertised operation range when installed according to factory standards. The system shall be equipped with a digital electronic control display suitable for installation on the pump panel. Incorporated within the control display shall be a microprocessor that receives input from the system flowmeter(s), while also monitoring foam concentrate pump output, comparing values to ensure that the operator preset proportional amount of foam concentrate is injected into the discharge side of the fire pump.

Paddlewheel-type flowmeter(s) shall be installed in the discharges specified to be "foam capable." When the use of more than one flowmeter is required, an interface electronics module will be provided to totalize these flows and send the flow total to the microprocessor in the computer control display.

The digital computer control display shall enable the pump operator to perform the following control and operation functions for the foam proportioning system:

- Provide push-button control of foam proportioning rates from 0.1% to 9.9%, in 0.1% increments
- Show current flow-per-minute of water
- Show total volume of water discharged during and after foam operations are completed
- Show total amount of foam concentrate consumed
- Simulate flow rates for manual operation
- Perform setup and diagnostic functions for the computer control microprocessor
- Flash a "low concentrate" warning when the foam concentrate tank(s) runs low
- Flash a "no concentrate" warning and shut the foam concentrate pump off, preventing damage to the pump, should the foam tank(s) empty

A 12-volt electric motor drive positive displacement foam concentrate pump, rated up to 2.5 gpm (9.5 L/min) @ 150 psi with operating pressures up to 400 psi (27.6 BAR), shall be installed in a suitable, accessible location. The system will draw a maximum of 40 amps @ 12 VDC. A pump motor electronic driver (mounted to the base of the pump) shall receive signals from the computer control display and power the 1/2 hp (0.40 kW) electric motor directly coupled to the concentrate pump in a variable speed duty cycle to ensure that the correct proportion of concentrate preset by the pump operator is injected into the water stream.

Full flow check valve shall be provided to prevent foam contamination of fire pump and water tank or water contamination of foam tank.

Components of the complete proportioning system shall include:

• Operator control module	• Low level tank switch
• Paddlewheel flowmeter	• Foam tank
• Pump and electric motor/motor driver	• Foam injection check valve
• Wiring harnesses	• Main waterway check valve

An installation and operation manual shall be provided for the unit, along with a one-year limited warranty by the manufacturer. The system must be installed and calibrated by a Certified FoamPro Dealer.

The system design shall have passed environmental testing which simulates heavy use on off-road mobile apparatus. Testing shall have been conducted in accordance to SAE standards.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

A means shall be provided to prevent water back flow into the foam proportioning system and the foam concentrate storage tank.

- One (1) Innovative Controls model 3003000, ¾" brass 90 degree ball type drain valve(s) with lift type handle which can be opened under pressure, with color coded label shall be provided. Valve(s) shall be located on bottom of pump panel or drain the lowest point in the plumbing.

HOSE THREADS

Hose threads shall be National Standard (NST) on all base threads on the apparatus intakes and discharges, unless otherwise specified. (NST and NH are the same thread)

PLUMBING SPECIFICATIONS

The fire pump plumbing system shall be fabricated with rigid stainless steel and or flexible piping with stainless steel fittings. Victaulic couplings shall be installed to permit flexing of the plumbing system and allow for quick removal of piping or valves for service. Flexible hose couplings shall be threaded stainless steel or Victaulic connections.

The fire pump and plumbing shall be hydrostatically tested in compliance to applicable sections of NFPA standards, with test results submit with the delivery documentation.

STAINLESS STEEL INTAKE MANIFOLD

The suction manifold assembly shall be fabricated with Schedule 10 type 304 stainless steel. All threaded fittings shall be a minimum of Schedule 10 stainless steel. The suction manifold assembly shall have radiused sweep elbows to minimize water turbulence into the suction volute.

The suction manifold shall be welded and pressure tested prior to installation. The stainless steel manifold assembly shall be attached to the pump intake volute with a heavy-duty, flexible Victaulic coupling.

The entire intake piping system, valves, bleeder valves, and intake closures, excluding the tank-to-pump line on the tank side of the valve, shall be capable of withstanding a hydrostatic pressure of 250 psi (1700 kPa).

STAINLESS STEEL DISCHARGE MANIFOLD

The discharge manifold assembly shall be fabricated with Schedule #10 type 304 stainless steel. All threaded fittings shall be a minimum of Schedule 10 stainless steel. The discharge manifold assembly shall have radiused sweep elbows to minimize water turbulence into the discharge header.

The manifold shall be welded and pressure tested prior to installation. The stainless steel manifold assembly shall be attached to the pump intake volute with a heavy-duty, flexible Victaulic coupling.

The entire discharge piping system; valves; drain cocks; and outlet closures, excluding the tank fill line on the tank side of the valve and CAF system piping and components that include valves that permit isolation from discharge pressure, shall be capable of withstanding a hydrodynamic discharge pressure of 500 psi (3400 kPa) or 100 psi (700 kPa) over the maximum discharge pressure capability rating of the pump, whichever is greater.

PLUMBING SYSTEM FINISH

The plumbing system shall not be painted. The piping and valves shall remain natural color.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

STAINLESS STEEL PLUMBING WARRANTY

The stainless steel plumbing shall be free of defects in material and workmanship for a period of ten (10) years, or 100,000 miles (or 160,934 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date.

The contractor shall supply details of their warranty information with their bid submission.

INTAKES

The pump shall have a sufficient number and size of intakes to perform the apparatus pump system certification test.

If the couplings on the suction hose carried on the apparatus are of a different size from that of the pump intake(s) or have means of hose attachment other than that provided on the intake(s), an adapter(s) shall be provided to allow connection of the suction hose to the pump intake(s).

Safety sign FAMA25, which warns of the need for training prior to operating the apparatus, shall be located on pump operator's panel. Label shall be in both English/French for units built for Canada;

WARNING: Death or serious injury might occur if proper operating procedures are not followed. The pump operator as well as individuals connecting supply or discharge hoses to the apparatus must be familiar with water hydraulics hazards and component limitations.

AVERTISSEMENT: La mort et de graves blessures peuvent survenir si la marche à suivre pour l'utilisation adéquate n'est pas effectuée. L'opérateur de la pompe, ainsi que les personnes qui raccordent les tuyaux d'alimentation et de refoulement à l'engin, doivent être familières avec le manuel de l'opérateur, les dangers liés à l'hydraulique et les restrictions relatives aux composantes.

Each intake shall have a removable or accessible strainer inside the connection. The strainer(s) shall restrict spherical debris that is too large to pass through the pump.

At least one (1) valved intake shall be provided that can be controlled from the pump operator's position. The valve and piping shall be a minimum 2-1/2 in. (65 mm) nominal size. If the intake is 2-1/2 in. (65 mm) nominal size, the intake shall be equipped with a female swivel coupling with NH threads.

Any 3 in. (75 mm) or larger intake valve except the tank-to-pump intake valve shall be a slow-operating valve.

Each valved intake shall be equipped with a bleeder valve having a minimum 3/4 in. (19 mm) pipe thread connection to bleed off air or water. The bleeder valve shall be operational without the operator having to get under the apparatus. If a valved appliance is attached to an intake, it shall be equipped with a 3/4 in. (19 mm) bleeder valve on each intake. Bleeder valves for valved intakes 4 in. (100 mm) and larger not located at the pump operator's panel shall be located where the bleeder valve controls are visible and operationally functional while the operator remains stationary at the valved intake position.

Each valved intake having a connection size larger than 3 in. (75 mm) shall be equipped with an adjustable automatic pressure relief device installed on the supply side of the valve to bleed off pressure from a hose connected to the valved intake. The automatic pressure relief device shall be adjustable from a minimum of 90 psi (620 kPa) to at least 185 psi (1275 kPa). The pressure relief device, when preset at 125 psi (860 kPa), shall not allow a pressure rise greater than 60 psi (400 kPa) at the device inlet while flowing a minimum of 150 gpm (570 L/min). The pressure relief device shall discharge to atmosphere.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

All intakes shall be provided with caps or closures capable of withstanding a hydrostatic gauge pressure of 500 psi (3400 kPa). Intakes having male threads shall be equipped with caps. Intakes having female threads shall be equipped with plugs. Where adapters for special threads or other means for hose attachment are provided on the intakes, closures shall be provided for the adapters in lieu of caps or plugs. Caps, plugs, or closures for 3-1/2 in. (90 mm) and smaller intakes shall remain secured to the apparatus when removed from the intakes.

If the suction inlets are to be equipped with a valve, Siamese, or adapter that will remain in place while the apparatus is in motion, that valve, Siamese, or adapter shall not project beyond the apparatus running board. The purchaser shall specify if any valve, Siamese, or adapter is to be permanently installed on an intake and identify the brand and model of such item.

The completed apparatus shall have the following intake(s);

2-1/2" INTAKE, STREETSIDE

There shall be one (1) 2-1/2" (65 mm) gated intake(s) located on pump panel. Each intake shall include:

- One (1) Akron Brass 8800 series Gen II, manual type 2-1/2" (65 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a chrome handle directly connected to valve.
- Each intake shall have a 2-1/2" (65 mm) NSTF chrome swivel adapter with strainer provided.
 - The specified adapter shall be provided with a 2-1/2" (65 mm) NSTM chrome plated plug with chain.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

2-1/2" INTAKE, CURBSIDE

There shall be one (1) 2-1/2" (65 mm) gated intake(s) located on pump panel. Each intake shall include:

- One (1) Akron Brass 8800 series Gen II, actuated type 2-1/2" (65 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - The specified Akron valve(s) shall be configured for 12 VDC electric actuation.
- An Akron 9333 Navigator Pro electric valve position controller and wire harness with full color LCD display visible from all angles, true position feedback, user programmable presets, % open text shown on valve bar graph, and VMUX capable integration shall be located on the pump operator's panel.
- Each intake shall have a 2-1/2" (65 mm) NSTF chrome swivel adapter with strainer provided.
 - The specified adapter shall be provided with a 2-1/2" (65 mm) NSTM chrome plated plug with chain.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TANK TO PUMP CHECK VALVE

There shall be a check valve between the pump suction and the booster tank valve. The check valve shall eliminate back flow into the water tank when the pump is connected to a pressurized source.

TANK TO PUMP VALVE

A 3-1/2" (89 mm) full flow ball valve shall be installed between the fire pump and the water tank. The connection between the tank and the pump shall be capable of the flow recommendations as set forth in the latest edition of NFPA 1901. A non collapsible flexible hose shall be incorporated into the tank to pump plumbing to allow movement in the line as the chassis flexes to avoid damage during normal road operation. The tank to pump valve shall be controlled from the pump operator's panel and labeled "TANK TO PUMP".

The tank to pump valve shall be as follows;

- One (1) Waterous 81961-1B series slow-operating 3-1/2" (89 mm) valve(s), chrome plated bronze ball. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a push/pull type chromed "T" handle connected to the valve. The valve handle will be pulled for the open valve position. The control handle shall be located adjacent to the plumbing connection.

DISCHARGES

A minimum of three (3) 2-1/2 in. (65 mm) outlets shall be provided on any pump rated at 750 gpm (3000 L/min) or greater, and a minimum of one (1) 2-1/2 in. (65 mm) outlet shall be provided on any pump rated at less than 750 gpm (3000 L/min).

The piping and valves supplying any preconnected 1-1/2 in. (38 mm), 1-3/4 in. (45 mm), or 2 in. (52 mm) hose line, including the piping to the preconnected hose storage areas shall be at least 2 in. (52 mm) in size.

All discharge outlet connections, except connections to which a hose will be preconnected, shall be equipped with caps or closures capable of withstanding a hydrostatic gauge pressure of 100 psi (700 kPa) over the maximum pump close-off pressure or 500 psi (3400 kPa), whichever is greater.

Where adapters are provided on the discharge outlet connections, the closures shall fit on the adapters.

Caps or closures for outlet connections smaller than 4 in. (100 mm) shall remain secured to the apparatus when removed from the connection.

Each discharge outlet shall be equipped with a valve that can be opened and closed smoothly at pump discharge gauge pressures of 250 psi (1700 kPa).

The flow-regulating element of each valve shall not change its position under any condition of operation that involves discharge pressures to the maximum pressure of the pump.

The means to prevent a change in position shall be incorporated in the operating mechanism and shall be permitted to be manually or automatically controlled.

Any 3 in. (75 mm) or larger discharge valve shall be a slow-operating valve.

All 1-1/2 in. (38 mm) or larger discharge outlets shall be equipped with a drain or bleeder valve having a minimum 3/4 in. (19 mm) pipe thread connection for draining or bleeding off pressure from a hose connected to the outlet.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

Any 2-1/2 in. (65 mm) or larger discharge outlet that is located more than 42 in. (1070 mm) above the ground and to which a hose is to be connected, but that is not in a hose storage area, shall be equipped with a sweep elbow of at least 30 degrees downward.

The completed apparatus shall have the following discharge(s);

FRONT DISCHARGE

2" DISCHARGE

There shall be one (1) 2" (52 mm) gated discharge(s) with control located on pump panel. Each discharge shall include:

- One (1) of the discharge(s) shall flow water and foam.
- One (1) Akron Brass 8900 series Gen II, manual type 2" (52 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a vertical swing chromed twist-lock handle connected to the valve, located at pump panel. Valve control shall have a side mount ICI chrome bezel.
- One (1) Innovative Controls NoShok 2-1/2" liquid filled gauge(s) with blue Nite-Glo LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.
- There shall be a 2" (52 mm) VFC x 1-1/2" (38 mm) NSTM brass or chrome plated 90 degree swivel elbow provided for each discharge.
- One (1) Innovative Controls model 3003000, 3/4" brass 90 degree ball type drain valve(s) with lift type handle which can be opened under pressure, with color coded label shall be provided. Valve(s) shall be located on bottom of pump panel or drain the lowest point in the plumbing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

STREETSIDE DISCHARGE

1" DISCHARGE DECON

There shall be one (1) gated discharge(s) with control located on pump panel. Each discharge shall include:

- One (1) of the discharge(s) shall flow water only.
- One (1) manual 1" valve(s) shall be provided.
 - Valve(s) shall be controlled with a chrome handle directly connected to valve.

Each discharge shall have a standard garden hose connection.

- One (1) Innovative Controls model 3003000, 3/4" brass 90 degree ball type drain valve(s) with lift type handle which can be opened under pressure, with color coded label shall be provided. Valve(s) shall be located on lower pump panel and drain the lowest point in the plumbing.

2-1/2" DISCHARGE - 250 GPM

There shall be one (1) 2-1/2" (65 mm) gated discharge(s) with control located on pump panel. Each discharge shall include:

- One (1) of the discharge(s) shall flow water only.
- One (1) Akron Brass 8800 series Gen II, manual type 2-1/2" (65 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a vertical swing chromed twist-lock handle connected to the valve, located at pump panel. Valve control shall have a side mount ICI chrome bezel.
- One (1) Innovative Controls NoShok 2-1/2" liquid filled gauge(s) with blue Nite-Glo LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.
- Each discharge shall have a 2-1/2" (65 mm) NSTF x 2-1/2" (65 mm) NSTM chrome plated 30 degree downsweep elbow provided.
 - The specified elbow shall be provided with a 2-1/2" (65 mm) NSTF chrome plated cap with chain.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CURBSIDE DISCHARGE

2-1/2" DISCHARGE - 250 GPM

There shall be one (1) 2-1/2" (65 mm) gated discharge(s) with control located on pump panel. Each discharge shall include:

- One (1) of the discharge(s) shall flow water only.
- One (1) Akron Brass 8800 series Gen II, manual type 2-1/2" (65 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a vertical swing chromed twist-lock handle connected to the valve, located at pump panel. Valve control shall have a side mount ICI chrome bezel.
- One (1) Innovative Controls NoShok 2-1/2" liquid filled gauge(s) with blue Nite-Glo LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.
- Each discharge shall have a 2-1/2" (65 mm) NSTF x 2-1/2" (65 mm) NSTM chrome plated 30 degree downsweep elbow provided.
 - The specified elbow shall be provided with a 2-1/2" (65 mm) NSTF chrome plated cap with chain.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

4" DISCHARGE - 625 GPM

There shall be one (1) 4" (100 mm) gated discharge(s) with control located on pump panel. Each discharge shall include:

- One (1) of the discharge(s) shall flow water only.
- One (1) Akron Brass 8600 series Gen II slow-operating, actuated type 3" (75 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
- An Akron 9333 Navigator Pro electric valve position controller and wire harness with full color LCD display visible from all angles, true position feedback, user programmable presets, % open text shown on valve bar graph, and VMUX capable integration shall be located on the pump operator's panel.
- Each discharge shall have a 4" (100 mm) rocker lug NSTF swivel x 5" (125 mm) Storz hardcoat finish 30 degree downsweep elbow provided.
 - The specified elbow shall be provided with a 5" (125 mm) Storz cap hardcoat finish with chain.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.
- One (1) Innovative Controls/NoShok 2-1/2" liquid filled gauge(s) with blue (water) LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text and blue (water) or red (foam) pie indicator.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

REAR STREETSIDE DISCHARGE

Each discharge(s) shall have a stainless steel trim ring.

2-1/2" DISCHARGE - 250 GPM

There shall be two (2) 2-1/2" (65 mm) gated discharge(s) with control located on pump panel. Each discharge shall include:

- Two (2) of the discharge(s) shall flow water and foam.
- Two (2) Akron Brass 8800 series Gen II, manual type 2-1/2" (65 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a vertical swing chromed twist-lock handle connected to the valve, located at pump panel. Valve control shall have a side mount ICI chrome bezel.
- Two (2) Innovative Controls NoShok 2-1/2" liquid filled gauge(s) with blue Nite-Glo LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.
- Each discharge shall have a 2-1/2" (65 mm) NSTF x 2-1/2" (65 mm) NSTM chrome plated 30 degree downsweep elbow provided.
 - The specified elbow does not require a cap with chain.
- Two (2) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

REAR CURBSIDE DISCHARGE

Each discharge(s) shall have a stainless steel trim ring.

2-1/2" DISCHARGE - 250 GPM

There shall be two (2) 2-1/2" (65 mm) gated discharge(s) with control located on pump panel. Each discharge shall include:

One (1) shall be far right below the hosebed.

One (1) shall be on the right side of the apparatus inboard of the above discharge.

- Two (2) of the discharge(s) shall flow water and foam.
- Two (2) Akron Brass 8800 series Gen II, manual type 2-1/2" (65 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a vertical swing chromed twist-lock handle connected to the valve, located at pump panel. Valve control shall have a side mount ICI chrome bezel.
- Two (2) Innovative Controls NoShok 2-1/2" liquid filled gauge(s) with blue Nite-Glo LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.
- Each discharge shall have a 2-1/2" (65 mm) NSTF x 2-1/2" (65 mm) NSTM chrome plated 30 degree downsweep elbow provided.
 - The specified elbow does not require a cap with chain.
- Two (2) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

MISCELLANEOUS DISCHARGE

3" DECK GUN DISCHARGE

There shall be one (1) 3" (75 mm) gated discharge located on the upper deck above the pump compartment. Piping shall rise high enough for a mounted deluge gun to be operated in a 360 degree circle to a lower angle of 15 degrees without being impeded by any part of the apparatus or equipment.

The discharge plumbing shall terminate as required by deck gun model. The discharge shall include:

- One (1) of the discharge(s) shall flow water only.
- One (1) Akron Brass 8600 series Gen II slow-operating, actuated type 3" (75 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - An Akron 9333 Navigator Pro electric valve position controller and wire harness with full color LCD display visible from all angles, true position feedback, user programmable presets, % open text shown on valve bar graph, and VMUX capable integration shall be located on the pump operator's panel.
- One (1) Class 1, 3/4" brass 90 degree ball type drain valve(s) shall be provided for the above plumbing item. There shall be a 1/4 turn control to manually open the drain valve(s) when the line is under pressure located on pump panel or drain the lowest point in the plumbing.
- One (1) Innovative Controls/NoShok 2-1/2" liquid filled gauge(s) with blue (water) LED backlighting activated with pump engagement.
 - Gauge(s) shall have a white background with black text and blue (water) or red (foam) pie indicator.
 - Gauge(s) shall have a range from 0 to 400 PSI.
 - The gauge shall have a die cast zinc, chrome plated bezel with color-coded labels insert and a color-coded gauge trim ring. Labels shall be UV and scratch resistant and meet SAE standards where applicable.

DECK GUN MONITOR

An Akron DeckMaster electric monitor model 3440 with 1,250 GPM (4,800 LPM) capacity, shall be provided with completed unit. The DeckMaster monitor is a technologically advanced, electrically controlled deck monitor with automated elevating capability. The unique design of the DeckMaster monitor allows electric elevation and positioning 26" above the base of the flange for operation over obstructions with the push of a switch with following features;

- 340° horizontal rotation with adjustable stops
- Vertical travel 90° above to 45° below horizontal
- Manual override for horizontal, vertical and elevation control
- Stow position set easily by the end user
- Automatic drain for freeze protection
- Diagnostic light for trouble-shooting
- Connection for deployed indicator light
- Flush mount panel control, 4-switch CAN control box including stow

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

TELESCOPING WATERWAY - ELECTRIC

The specified deck gun shall be mounted on an Akron High Riser 3406 12" electric riser.

The High Riser offers a full 3" waterway, hardcoat anodized finish, and built-in sensor for connection to "monitor raised" light or truck open compartment warning.

- 3" waterway
- 12" extension
- With unique three-piece design, the extremely compact device is only 18 1/2" (470 mm) when nested
- Electrically actuated 12 VDC
- Durable lightweight Pyrolite construction
- Manual override
- 5 year warranty
- Inlet option: 3" (75 mm) Victaulic or NPT
- Outlet options 3" (75 mm) or 4" (100 mm) flange

DECK GUN CONTROL

No remote control is provided with specified electric deck gun.

MASTER STREAM TIP

The specified deck gun shall be provide with an Akron Akromatic 1250 model 5177 Pyrolite electric master stream tip capable of flowing from 250 to 1,250 GPM (950 - 4,800 LPM) @ 80 (5.5 bars) PSI. Master stream tip shall have a manual override with an electric pattern control.

TANK FILL VALVE

There shall be one (1) 2" (52 mm) tank fill valve plumbed with 2" plumbing from the pump to the tank. Installation shall be completed with 2" rubber hose and stainless steel hose couplings. The tank fill valve shall be controlled from the operator's control panel and labled "TANK FILL".

- One (1) Akron Brass 8800 series Gen II, manual type 2" (52 mm) valve(s), Stainless Steel ball with HydroMax technology. Each valve shall be equipped with a Class 1 stainless steel weld type valve adapter on inlet side, and discharge side with drain port.
 - Valve(s) shall be controlled with a push/pull type chromed "T" handle connected to the valve. The valve handle will be pulled for the open valve position. The control handle shall be located adjacent to the plumbing connection.

PUMP PANEL

The side mount pump control panel shall be hinged, or bolted in place allowing it to be easily removed to gain access to plumbing components.

The pump controls shall be mounted on an aluminum control panel with a black powdercoat painted finish.

PUMP PANEL LOCATION

The pump control panel shall be side mounted.

The pump panel shall include the following items;

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

PUMP PANEL ACCESS

The pump panel shall be open to the side of the truck. The Pump Operator shall NOT be required to open a compartment door to access the pump control panel.

ENGINE GAUGES

The cab/chassis engine gauges shall be provided with the specified pump pressure governor system.

PRESSURE GOVERNOR and ENGINE MONITORING DISPLAY

A Fire Research PumpBoss series PBA401-D00 pressure governor and monitoring display kit shall be installed. The kit shall include a control module, intake pressure sensor, discharge pressure sensor, and cables. The control module case shall be waterproof and have dimensions not to exceed 6 3/4" high by 4 5/8". The control knob shall be 2" in diameter with no mechanical stops, have a serrated grip, and a red idle push button in the center. It shall not extend more than 1 3/4" from the front of the control module. Inputs for monitored engine information and outputs for engine control shall be on the J1939 databus. Inputs from the pump discharge and intake pressure sensors shall be electrical.

The following continuous displays shall be provided:

- Engine RPM; shown with four daylight bright LED digits more than 1/2" high
- Check engine and stop engine warning LEDs
- Engine oil pressure; shown on a dual color (green/red) LED bar graph display
- Engine coolant temperature; shown on a dual color (green/red) LED bar graph display
- Transmission Temperature: shown on a dual color (green/red) LED bar graph display
- Battery voltage; shown on a dual color (green/red) LED bar graph display
- Pressure and RPM operating mode LEDs
- Pressure / RPM setting; shown on a dot matrix message display
- Throttle ready LED.

A dot-matrix message display shall show diagnostic and warning messages as they occur. It shall show monitored apparatus information, stored data, and program options when selected by the operator. All LED intensity shall be automatically adjusted for day and night time operation.

The program shall store the accumulated operating hours for the pump and engine to be displayed with the push of a button. It shall monitor inputs and support audible and visual warning alarms for the following conditions:

• High Battery Voltage	• Low Engine Oil Pressure
• Low Battery Voltage (Engine Off)	• High Engine Coolant Temperature
• Low Battery Voltage (Engine Running)	• Out of Water (visual alarm only)
• High Transmission Temperature	• No Engine Response (visual alarm only).

The program features shall be accessed via push buttons located on the front of the control module. There shall be a USB port located at the rear of the control module to upload future firmware enhancements.

The governor shall operate in two control modes, pressure and RPM. No discharge pressure or engine RPM variation shall occur when switching between modes. A throttle ready LED shall light when the interlock signal is recognized. The governor shall start in pressure mode and set the engine RPM to idle. In pressure mode the governor shall automatically regulate the discharge pressure at the level set by the operator. In RPM mode the governor shall maintain the engine RPM at the level set by the operator except in the event of a discharge pressure increase. The governor shall limit a discharge pressure increase in RPM mode to a maximum of 30 psi. Other safety features shall include recognition of no water conditions with an automatic programmed response and a push button to return the engine to idle.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

MASTER INTAKE/PRESSURE GAUGES

There shall be one (1) Innovative Controls/NoShok 4" liquid filled gauge to display the Master Intake Pressure, and labeled "PUMP INTAKE".

There shall be one (1) Innovative Controls/NoShok 4" liquid filled gauge to display the Master Discharge Pressure. Gauge shall be labeled "PUMP DISCHARGE".

Both gauges shall have a die cast zinc, chrome plated bezel and color-coded. The left side (Pump Intake) bezel shall be color coded red, and the right side (Pump Discharge) bezel shall be colored black.

A test gauge port manifold shall be integrated into lower center bezel.

- Gauge(s) shall have a white background with black text.
- Gauge(s) shall have a range from -30" to 400 PSI.

PUMP SAFETY AND TEST LABELS

Safety, information, data, and instruction labels for apparatus shall be provided and installed at the operator's instrument panel.

The labels shall include rated capacities, pressure ratings, and engine speeds as determined by the certification tests. The no-load governed speed of the engine, as stated by the engine manufacturer, shall also be included.

The labels shall be provided with all information and be attached to the apparatus prior to delivery.

PUMP PANEL LIGHTING

All gauges and controls on the pump operator's panel shall be adequately illuminated by a full panel width shielded light assembly with full width OnScene Solutions LED light (each panel, if equipped). The light shall be activated by a weather-proof type switch on the pump operator's panel as well as automatically when pump is engaged. This switch shall also activate any area step lighting.

PUMP PANEL SWITCH PANEL

An Innovative Controls black back-lit switch panel shall be provided to control specified scene lighting or other control switching.

PUMP PANEL CAB TILT SWITCH

An Innovative Controls black back-lit switch panel shall be provided to control cab tilt function with indicator light and properly labeled.

LOW PRESSURE AIR OUTLET

There shall be one (1) air outlet connection to supply low pressure air for general maintenance. The outlet shall terminate in a 1/4" NPT threaded port. Air outlet shall be located on lower pump operator's panel. The connector shall be supplied by the Boulder Rural Fire Protection District.

POLY WATER TANK

The water tank capacity shall be approximately 600 US gallon. Certification of the tank capacity shall be recorded on the manufacturer's record of construction and shall be provided to the purchaser upon delivery of the apparatus.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

CONSTRUCTION

The water tank shall be of a specific configuration and designed to be completely independent of the body and to incorporate the lowest possible Center of Gravity. The transverse and longitudinal baffles shall be manufactured of a minimum of 3/8" polypropylene. All baffles shall be properly vented to permit movement of air and water between compartments. All baffles shall interlock with one another and are completely fused to each other as well as to the walls of the tank. All partitions and spacing shall comply with NFPA 1901. All exterior walls and interior baffles shall be welded to the floor of the tank. Tolerances in design allow for a maximum variation of 1/8" on all dimensions. All poly sheeting utilized in the construction of the tank shall be of a textured finish.

WATER FILL TOWER AND COVER

The tank shall have a combination vent and manual fill tower. The fill tower shall be constructed of 1/2" polypropylene sheet and shall have a minimum outside dimension of 8" (203mm) x 8" (203mm). The tower shall have a 1/4" thick removable polypropylene screen and a polypropylene hinged cover. The fill tower cover shall include a Label "WATER ONLY" that is blue in color with white letters indicating that it is a water-only fill tower. Inside the fill tower there shall be a combination vent/overflow pipe. The vent overflow shall be a minimum of schedule 40 polypropylene pipe with a minimum I.D. of 4" that is designed to run through the tank and shall be piped to discharge water behind the rear wheels as required in NFPA 1901 so as to not interfere with rear tire traction. The discharge of the overflow/vent shall be threaded to allow for a fitting and hose to be installed and routed below the fuel tank or rear axle to prevent flooding.

SUMP

The sump shall be constructed of a minimum of 1/2" polypropylene. When a front suction is required, a 3" schedule 40 polypropylene pipe shall be installed that will incorporate a dip tube from the front of the tank to the sump location. The sump shall have a minimum 3" N.P.T. threaded outlet on the bottom for a drain plug per NFPA. This shall be used as a combination clean-out and drain. All tanks shall have an anti-swirl plate located approximately 3" above the inside floor.

THREADED PORTS

There will be three (3) standard threaded Ports: one for the tank-to-pump suction Line, one for tank fill line and a one for a water level sensor. All threads shall be of National Pipe Taper specification unless otherwise specified.

MOUNTING AND SUPPORT

The tank shall be mounted to the sub-frame of the body with a barrier of 1/4" rubber between tank and any frame material. The rubber Isolator shall have a Rockwell rating of 60 durometer. The frame / cradle shall support the entire floor including the perimeter of the tank with a maximum unsupported area of 529 square inches (.341 sq m) for tanks equal to or less than 40" (1016 mm) tall and 400 square inches (.258 sq m) for tanks greater than 40" (1016 mm) tall.

WATER TANK LEVEL GAUGE

There shall be one (1) Innovative Controls SL series 10-LED water tank level gauge(s) for indicating water tank level. The tank level gauge shall indicate the liquid level on an easy to read display.

Each tank level gauge system shall include:

- A pressure transducer that is mounted on the outside of the tank in an easily accessible area.
- A super bright LED bar graph display with a visual alarm at 1/4 of a tank. The display shall also provide an output to activate an audible alarm or secondary visual alarm at 1/4 of a tank.
- A set of weather resistant connectors to connect the digital display to the pressure transducer and to the apparatus power.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

WATER TANK LEVEL INDICATOR

The one (1) cab chassis supplied and installed tank level indicator light(s) shall be connected to the water tank level system. Lights shall be de-activated whenever the parking brake is released.

POLY WATER TANK WARRANTY

The poly water tank shall be provided with a lifetime material and workmanship limited warranty. The manufacturer shall supply details of their warranty information with their bid submission.

FILL TOWER PROTECTION

The fill tower(s) shall be boxed in with an aluminum panel for protection from damage.

CLASS A POLYPROPYLENE FOAM CELL

There shall be one (1) 20 US gallon or 16.6 Imperial gallons polypropylene foam cell incorporated into the polypropylene water tank. This foam tank capacity shall be deducted from water tank size specified.

There shall be one (1) pressure/vacuum vent installed on the foam tank.

A minimum 1 in. (25 mm) inside diameter full flow drain valve and piping shall be provided at the lowest point of any foam concentrate tank. The drain shall be piped to drain directly to the surface beneath the apparatus without contacting other body or chassis components. Foam cell shall be drill and tapped for foam level gauge.

A label that reads "Foam Tank Fill" shall be placed at or near the foam concentrate tank fill opening.

A label that specifies the following shall be placed at or near any foam concentrate tank fill opening:

1. Type(s) of foam concentrate the system is designed to use.
2. Any restrictions on the type of foam concentrate that can be used with the system.
3. A FAMA 19 label that reads "Warning: Do Not Mix Brands and Types of Foam". In addition, label shall be in both English/French for units built for Canada; "*Avertissement : Ne pas mélanger les marques et les types d'émulseur*".

FOAM TANK LEVEL GAUGE

There shall be one (1) Innovative Controls SL series 10-LED foam tank level gauge(s) for indicating foam tank level. The gauge shall indicate the liquid level on an easy to read display.

Each tank level gauge system shall include:

- A pressure transducer that is mounted on the outside of the tank in an easily accessible area.
- A super bright LED bar graph display with a visual alarm at 1/4 of a tank. The display shall also provide an output to activate an audible alarm or secondary visual alarm at 1/4 of a tank.
- A set of weather resistant connectors to connect the digital display to the pressure transducer and to the apparatus power.

HOSE BED STORAGE AREA

Hose bed storage area shall be located over water tank and body, and shall exit at the rear of the apparatus. The interior of storage area shall be free from all projections such as nuts, sharp angles, or brackets that may damage equipment. The hose bed shall be no more than **60" above the road surface**.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ALUMINUM HOSE BED DECKING

The hose bed deck shall be constructed from 3" x 3/4" hollow aluminum extrusions welded into a one-piece grid to allow ventilation and water drainage. The extrusions shall have a radiused ribbed top surface. The deck will be completely removable for easy access to the booster tank. The booster tank fill tower shall be protected as necessary to prevent damage from equipment located in the storage area.

WALKWAY/STEP LIGHTS

There shall be four (4) OnScene Solutions Rough-Service 9" LED lights provided to illuminate the walkway or step area.

Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment.

Lighting shall provide illumination at a minimum level of 2 fc (20 lx) on all work surfaces, steps, and walkways. Lighting shall be switchable but activated automatically when the vehicle park brake is set.

HOSE BED STORAGE

The following fire hose shall be stored in hose bed storage area listed in order streetside to curbside;

- Hosebed section #1 shall provide storage for 300 feet of 1-3/4" hose preconnected and stored in removable tray.
- Hosebed section #2 shall provide storage for 300 feet of 2-1/2" hose preconnected and stored in removable tray.
- Hosebed section #3 shall provide storage for 1,000 feet of 5" LDH hose.
- Hosebed section #4 shall provide storage one (1) 100 feet 1-3/4" hose Apartment Pack and three (3) "U" Packs of 50' 3-1/2" each.
- Hosebed section #5 shall provide storage for 400 feet of 2-1/2" hose.
- Hosebed section #6 shall provide storage for 200 feet of 1-3/4" hose preconnected and stored in removable tray.
- Hosebed section #7 shall provide storage for 200 feet of 2-1/2" hose preconnected and stored in removable tray.

HOSE BED DIVIDER(S)

Three (3) adjustable aluminum hose bed divider(s) shall be provided in the hose bed storage area. The dividers(s) shall be fabricated from 3/16" smooth aluminum with 1" round split aluminum tubing welded to the top and rear edges. A radiused hand-hold opening shall be provided on rear of divider to assist in access to hose bed area. Hose pay-out shall be unobstructed by the divider.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

ALUMINUM HOSE BED COVER

A two-section hose bed cover shall be provided. Each door shall be fabricated from 1/8" NFPA aluminum treadplate with formed hat sections for bracing. Doors shall be hinged along each side of the hose body using stainless steel piano hinge. The top surface of each section shall slant down with the highest point in the center of the hose bed area and shall be supported from underneath by at least one (1) adjustable hose bed divider. Each section shall be constructed to support the weight of a 300 lb. person.

A flashing warning light signal shall be provided indicating when a hose bed door is not in a closed position as required by NFPA 1901.

There shall be one (1) 24" vertical handrail on each door to assist in raising and lowering hose bed door. Handrails shall be NFPA compliant 1-1/4" knurled 304 stainless steel with welded end stanchions.

Each door shall have a 36" OnScene LED light on the underside of the door that will be automatically activated when the door is opened.

HOSE BED END COVER

The opening at the end of hose bed shall have a 22 oz. marine grade vinyl attached to hose bed door(s) with yellow pulls with reflective bungee attached to each door and extend downward to bottom of hose bed to protect hose and equipment from weather and dust.

If two (2) doors are provided, the center where doors come together shall have a Velcro seam to join vinyl together. Bottom of each flap shall be weighted to help prevent flap from moving while truck is traveling.

Vinyl color shall be color coordinated with upper vehicle color, unless specified otherwise.

MANUAL ASSIST

Each hose bed door section shall utilize a manual type pneumatic cylinder to assist with opening and closing.

Boulder Rural Fire Protection District

Rescue Pumper, SVI #1168

EQUIPMENT PAYLOAD WEIGHT ALLOWANCE

In compliance with NFPA 1901 standards, the pumper shall be designed for an equipment loading allowance of 2,500 lbs. of Boulder Rural Fire Protection District provided equipment based on the body having more than 250 cu. ft. of storage space.

The equipment allowance shall be calculated at 5,500 lbs. The above paragraph is to match NFPA minimums.

EQUIPMENT

The following equipment shall be furnished with the completed pumper vehicle;

- One (1) container of assorted stainless steel nuts, bolts, screws and washers used in the construction of the apparatus shall be provided with the completed apparatus.
- There shall be two (2) Zico SAC-44-E NFPA approved folding aluminum wheel chocks provided for 44" diameter tires that together will hold the vehicle when loaded to its GVWR or GCWR, on a hard surface with a 20 % grade, with the transmission in neutral, and the parking brake released.
 - The wheel chock(s) shall be mounted ahead of rear wheels, below body on streetside.
- One (1) Duo-Safety 900-A series 24' 2-section extension ladder(s) shall be provided with the completed unit.
 - The ladder(s) shall be mounted on specified ladder rack.
- One (1) Duo-Safety 775A series 14' aluminum roof ladder(s) shall be provided with the completed unit.
 - The ladder(s) shall be mounted on specified ladder rack.
- One (1) Duo-Safety 585-A 10' aluminum folding ladder(s) shall be provided with the completed unit.
 - The ladder(s) shall be mounted on specified ladder rack.
- One (1) Super Vac Valor V16-BL-12-AC-SP, 16" Milwaukee battery electric variable speed ventilation fan(s) with two (2) 12 Ah batteries, two (2) battery chargers, and shore power inlet shall be provided with the completed unit.
 - The above specified ventilation fan(s) shall be shipped loose with the completed unit.
- One (1) Streamlight Fire Vulcan C4 LED flashlight(s) with shoulder strap shall be provided with 80,000 candela and 3 hour run time. Each flashlight shall be orange in color and have a 12 volt DC charger and vehicle mount kit. Each flashlight shall have an LED spotlight style bulbs and reflectors. The flashlight(s) shall be wired to battery direct unless otherwise specified by Boulder Rural Fire Protection District.

The flashlight(s) shall be mounted in the cab in the following locations;

- Two (2) Kocheck 6.0" x 10' Flexlite PVC flexible suction hose(s) shall be provided with completed unit. The hose shall have NH threaded, long handle couplings provided.

Suction Hose: 6" Low Level Strainer, Foot Valve

- The suction hose(s) shall be mounted on streetside above wheels in formed aluminum hard suction tray(s).
- Boulder Rural Fire Protection District supplied NFPA required fire hose and nozzles shall be provided on completed unit before placing vehicle in service.

REMAINING NFPA MINOR EQUIPMENT BY PURCHASER

All other minor equipment not specified above, but required by NFPA 1901 for pumpers, section 5.9.4 shall be supplied and mounted by Boulder Rural Fire Protection District before the unit is placed in emergency service.