

Fresno Fire Department

Fresno, CA

Heavy Rescue- SVI#1228

Production Specification



INTENT OF SPECIFICATIONS

It shall be the intent of these specifications to provide a complete apparatus equipped as hereinafter and as specified. With a view to obtaining the best results and the most acceptable apparatus for service in the Department, these specifications cover only the general requirements as to the type of construction and tests to which the apparatus must conform, together with certain details as to finish, equipment and appliances with which the successful bidder shall conform. Minor details of construction and materials where not otherwise specified are left to the discretion of the contractor, who shall be solely responsible for the design and construction for all features. The manufacturer shall provide loose equipment only when specified by the customer. The (NFPA) 1901, Standard for Automotive Fire Apparatus, unless otherwise specified as requested by the customer in these specifications, shall prevail.

The apparatus must meet all NFPA, DOT, ICC, AE, TRA, FMVSS and local state Motor Vehicle Requirements.

It is required that the apparatus be manufactured to current NFPA edition standards, all NFPA equipment (LOOSE EQUIPMENT) not specified in the specifications will not be provided by the contractor.

Bids shall only be considered from companies that have an established reputation in the field of fire apparatus construction that have been in business and construction for a minimum of twenty-five (25) years.

The bidder of the apparatus herein specified; shall be wholly owned (100%) and managed by a Company, Corporation, and/or Parent Company that is wholly based, and permanently resides in the United States of America.

The Company, Corporation, and/or Parent Company and all assets belonging to such; shall be wholly owned and managed (100%) by the entities specified above.

The bidder shall state the location of the manufacturing facility where the apparatus is to be built and the location of the parent company if a subsidiary of a manufacturer.

The bidder shall provide satisfactory evidence of their ability to construct the apparatus specified in the bidders manufacturing facilities.

The bidder's representation shall state the length of time representing the manufacturer of specified apparatus.

Due to the severe service requirements the department will impose on the apparatus as specified, each bidder shall provide a list of at least six (6) departments in which similar apparatus utilizing the brand of chassis proposed have been in service for over one year. This list shall include contact names and phone numbers.

The bid shall be accompanied by a set of "Contractor's Specifications" consisting of a detailed description of the apparatus being furnished under this contract which conform. Computer runoff sheets are not acceptable as "Contractor's Specifications". Item compliance shall be indicated in the "Yes/No" column of each item by all

Bidders. Note: Each bidder shall submit their bid in the same sequence as these specifications to allow the department to easily compare.

These specifications shall indicate size, type, model and make of all component parts and equipment.

QUALITY AND WORKMANSHIP

The design of the Apparatus shall embody the latest approved automotive engineering practices.

The workmanship must be of the highest quality in its respective field. Special consideration will be given to the following points: Accessibility of the various units, which require periodic maintenance, ease of operation and symmetrical proportions.

Construction shall be rugged and ample safety factors shall be provided to carry loads as specified and to meet both on and off road requirements and to speed conditions as set forth under "Performance tests and requirements".

Welding shall be employed in the assembly of the apparatus in a manner that will not prevent the ready removal of any component part for service or repair, with apparatus bodies of bolt together design not being acceptable.

All steel welding shall follow American Welding Society requirements for AWS D1.1:2012 Structural Welding Code for welding steel structural assemblies. All aluminum welding shall follow American Welding Society requirements for AWS D1.2/D1.2M:2003 Structural Welding Code for any type structure made from aluminum structural alloys. All sheet metal welding shall follow American Welding Society AWS D9.1M/D9.1:2006 Structural Welding code for Arc/Braze requirements of non-structural materials. All pressure pipe welding shall follow American Society of Mechanical Engineers ASME IX/ ASME B31:2010 requirements to the qualification of procedures in welding and brazing, in accordance with the ASME Boiler and Pressure Vessel Code and the ASME B31 Code for Pressure Piping. Flux core arc welding to use alloy rods, type 7000, American Welding Society AWS standards A5.20-E70T1. The manufacturer shall be required to have an American Welding Society certified welding inspector in plant during testing operations within working hours to monitor weld quality.

Employees classified as welders shall be tested and certified to meet American Welding Society and American Society of Mechanical Engineers welding codes.

DELIVERY

The bidder shall provide the number of calendar days from the date the bid is awarded to the delivery of the completed unit.

A qualified delivery engineer representing the contractor shall deliver the apparatus and instruct the Fire Department personnel in the proper operation, care and maintenance of the equipment delivered.

PERFORMANCE TESTS AND REQUIREMENTS

A road test shall be conducted with the apparatus fully loaded to its estimated in-service weight and shall be capable of the following performance while on dry paved roads that are in good condition and for a continuous run of ten (10) miles or more, during which time the apparatus shall show no loss of power or overheating. The transmission drive shaft or shafts and rear axles shall run quietly and be free from abnormal vibration or noise throughout the operating range of the apparatus. The successful bidder shall furnish a Weight Certificate showing weights on front axle, rear axles and total weight for the completed apparatus at time of delivery.

- A. The apparatus shall be capable of accelerating to 35 MPH (55 km/hr) from a standing start within 25 seconds on a level concrete highway without exceeding the maximum governed RPM of the engine.
- B. The apparatus, fully loaded, shall be capable of obtaining a minimum top speed of 50 MPH (80 km/hr) on a level dry concrete highway with the engine not exceeding its governed RPM (fully loaded).
- C. The service brakes shall be capable of stopping a fully loaded vehicle in 35ft (10.7 m) at 20 mph (32.2 km/hr) on a level concrete highway. The air brake system shall conform to Federal Motor Vehicle Safety Standards (FMVSS) 121.
- D. The apparatus, when fully loaded, shall have not less than 25 percent or more than 50 percent of the weight on the front axle, and not less than 50 percent nor more than 75 percent on the rear axle.
- E. The contractor shall have the Underwriter's Laboratories, LLC conduct the tests of the apparatus as in accordance with standard practices required by the Underwriter Laboratories, LLC (Guide for the Certification of Fire Department Pumper latest edition). A copy of all tests shall accompany the Apparatus. (For apparatus sold within Canadian ULC S515 latest revision shall prevail).
- F. The contractor shall furnish copies of the Manufacturer's record construction details when delivered.

INFORMATION REQUIRED

The manufacturer shall supply at time of delivery, a complete operation and maintenance manual covering the completed apparatus as delivered.

A Fire Apparatus Safety Guide published by Fire Apparatus Manufacturer's Association shall be provided with the apparatus upon delivery. This manual includes essential safety information for fire fighters, fire chiefs, apparatus mechanics, and fire department safety officers. The guide is applicable to municipal, wildland, and airport firefighting apparatus manufactured on either custom or commercial chassis.

A permanent plate shall be mounted in the driver's compartment to specify the quantity and type of the following fluids used in the vehicle: Engine oil, engine coolant, and chassis transmission fluid, generator fluid (if applicable) and drive axle lubrication fluid.

The manufacture shall supply the final certification of GVWR and GAWR on a nameplate affixed to the vehicle.

A permanent plate in the driver's compartment shall be installed, specifying the seating capacity of the enclosed cab.

Signs that state "OCCUPANTS MUST BE SEATED AND BELTED WHEN APPARATUS IS IN MOTION" shall be provided and will be visible from each seated position. An accident prevention sign shall be located at the rear step area of the apparatus. It shall warn all personnel that standing on the step while apparatus is in motion shall be prohibited.

LIABILITY

The bidder, if their bid is accepted, shall defend any and all suits and assume all liability for the use of any patented device or article forming part of the apparatus or any appliance provided under the contract.

GENERAL CONSTRUCTION

The apparatus shall be designed with due consideration to distribution of load between the front and rear axles, so that all specified equipment, including filled water tank, a full complement of personnel and fire hose will be carried without injury to the apparatus. Weight balance and distribution shall be in accordance with the recommendations of the (NFPA) 1901, Standard for Automotive Fire Apparatus, documentation.

The apparatus shall be designed so that all recommended daily maintenance checks can be performed easily by the operator without the need for hand tools. Apparatus components that interfere with repair or removal of other major components must be attached with fasteners (cap, screws, nuts, etc.) so that the components can be removed and installed with normal hand tools. These components must not be welded or otherwise permanently secured into place.

The GAWR and GVWR of the chassis shall be adequate to carry the fully equipped apparatus including all tanks filled, the specified hose load, unequipped personnel weight, ground ladders and a miscellaneous equipment allowance per NFPA criteria. It shall be the responsibility of the purchaser to provide the contractor with the weight of equipment to be carried if it is in excess of the allowance as set forth by NFPA.

The unequipped personnel weight shall be calculated at 250 lbs. per person times the maximum number of persons to ride on the apparatus.

The height of the fully loaded vehicle's center of gravity shall not exceed the chassis manufacturer's maximum limit.

The front to rear weight distribution of the fully loaded vehicle shall be within the limits set by the chassis manufacturer. The front axle loads shall not be less than the minimum axle loads specified by the chassis manufacturer, under full loads and all other loading conditions.

The difference in weight on the end of each axle, from side to side, when the vehicle is fully loaded and equipped shall not exceed 7 percent.

The apparatus shall be so designed that the various parts are readily accessible for lubrication, inspection, adjustment and repair.

Where special tools manufactured or designed by the contractor and are required to provide routine service on any component of the apparatus built or supplied by the contractor, such tools shall be provided with the apparatus.

EXCEPTIONS TO SPECIFICATIONS

The following specifications shall be strictly adhered to. Exceptions shall be allowed if they are equal to or superior to that as specified and providing they are listed and entirely explained on a separate page entitled "Exceptions to Specifications". The exceptions list to refer to specification page number and paragraph.

Proposals taking total exception to specifications or total exception to certain parts of the specifications such as Electrical Systems, Chassis, Body or Pump, will not be accepted.

Prototype units will not be acceptable. Apparatus shall be inspected upon completion for compliance with specifications.

Deviations will not be tolerated and will be cause for rejection of Apparatus unless they were originally listed in bidder's proposal and accepted in writing by the department.

If the bidder takes an exception, on the exception page, the bidder must state an option price to bring their specifications into full compliance with the Department specifications.

Failure to provide this information shall be cause to reject the proposal as being non-responsive.

Copied or run off sheets of these specifications shall be unacceptable and the bid will be rejected no exceptions.

PURCHASER'S RIGHTS

The Purchaser reserves the right to accept or reject any or all bids as it deemed in their best interests.

BID/PROPOSAL DRAWINGS

For purposes of evaluation, the bidder shall provide a drawing illustrating, but not limited to, the overall dimensions, wheelbase, and overall length of the proposed apparatus and other specified equipment, shall be required to be included with the bidder's proposal package.

The drawings shall be large "D" size (minimum 24.00 inches x 36.00 inches).

Smaller size drawings, "similar to" drawings or general sales drawings, shall not be acceptable.

Failure to provide a bid evaluation drawing in accordance with these specifications shall be cause for rejection of the bid proposal.

PRE-CONSTRUCTION DRAWINGS

After the award of the bid, the contractor shall provide detailed colored engineering drawings including, but not limited to, the overall dimensions, wheelbase, and overall length of the proposed apparatus for use during the pre-construction conference.

The drawings shall include, but shall not be limited to the right, left, top, front and rear views of the apparatus.

SINGLE SOURCE MANUFACTURER

Bids shall only be accepted from a single source apparatus manufacturer.

The definition of single source manufacturer is a company that designs and manufactures their products utilizing an approach that includes complete product integration, including the apparatus chassis, cab, and body modules being constructed, assembled, and tested on company premises only.

Warranties qualified to the chassis and body design construction (excluding vender component warranties such as engine, axles, transmission, and pumps, etc.) will be from a single source manufacturer and not separated between manufacturers (i.e. body and chassis). The bidder shall provide evidence of maintaining compliance to this requirement.

TAG-ON ORDERS-COOPERATIVE PURCHASING

Other fire departments, metropolitan regions, or municipalities may purchase apparatus and equipment from same manufacture similar to the Apparatus and Equipment that is the subject of this Contract held by the same manufacture. The following terms shall apply to any such tag-on orders:

(a) Changes - Tag-on orders utilizing the same specification as the Apparatus and Equipment that is the subject of this Contract in order to provide favorable pricing and lead-times to other buyers due to having such specification fully engineered. Limited changes will be permitted. Such changes will be captured in the pre-construction meeting and the price of any tag-on unit adjusted accordingly.

(b) Term – Tag-on orders may be placed for a term of one year after the Effective Date of this Contract.

(c) Escalation - Manufacture reserves the right to adjust the price of any tag-on order if material costs escalate during the term of this Contract, changes in regulations become effective (for example EPA, NFPA or other), or the tag-on order would cross a model year.

(d) Acceptance – Manufacture holding the contract reserves the right to accept or reject any tag-on orders under this Contract.

SURCHARGE

Notwithstanding anything to the contrary in this Agreement, if the costs to Seller of acquiring any of the raw materials (including without limitation actual raw materials and/or conversion costs) used in the production and supply of the product(s) and/or goods (including, without limitation, the costs of acquiring raw materials, costs associated with tariffs, labor costs, shipping costs, or any other costs) materially increase from the cost levels as of the date of this Agreement, the parties agree that (1) Buyer shall have the obligation to pay and reimburse to Seller such increased costs, or (2) Seller shall have the right in its discretion to terminate this Agreement, without further liability, upon ten (10) days' notice to buyer. For purposes hereof, a "material increase" is defined to mean 5% of the quoted product and/or goods.

FINITE ELEMENT ANALYSIS AND TESTING

Finite Element Analysis (FEA) shall be provided by the manufacturer.

Prototype bodies have been subjected to rigorous testing over varied terrains simulating different environmental conditions.

The purpose of such complex engineering methods of analysis shall be to ensure the longevity of the design by analyzing stress levels throughout the body and incorporating the structural supports wherever necessary.

There shall have been a minimum of three (3) different load cases (per DOT, FHWA, and TTMA recommended practice) applied and analyzed to properly display the different areas and levels of stresses that will be present under the various operating conditions of the apparatus.

In addition to the FEA analysis, the core product design shall be strain gauged instrumental to ensure validation of FEA results and "Real World" drive/apparatus driving conditions.

Analysis shall also have been conducted on the mounting system for the apparatus body and pump house. EXCEPTIONS TO THIS STATEMENT MAY BE CAUSE FOR IMMEDIATE REJECTION AND/OR BE CONSIDERED NON-COMPLIANT.

SUPPLIED INFORMATION & EXTRAS

The apparatus manufacturer shall supply two (2) copies of apparatus manuals with all manufactured apparatus.

The manuals shall include, but not be limited to: all component warranties, users' manuals and information for supplied products, apparatus engineering information including drawings and build prints, and whatever other pertinent information the manufacturer can supply to its customer regarding the said apparatus.

Included in the delivery of the unit, the manufacturer shall also include spare hardware and extra fasteners, paint for touch-up, information regarding washing and care procedures, as well as other recommendations for care and upkeep of the general apparatus.

The manufacturer shall also supply a manufacturer's record of apparatus construction details, including the following information:

- Owner name and address
- Apparatus manufacturer, model, and serial number
- Chassis make, model, and serial number
- GAWR of front and rear axles
- Front tire size and total rated capacity in pounds
- Rear tire size and total rated capacity in pounds
- Chassis weight distribution in pounds with water (if applicable) and manufacturer mounted equipment (front and rear)
- Engine make, model, serial number, rated horsepower, and no load governed speed
- Type of fuel and fuel tank capacity
- Electrical system voltage and alternator output in amps
- Battery make and model, capacity in CCA
- Paint numbers
- Weight documents from a certified scale showing actual loading on the front axle, rear axle(s), and overall vehicle (with the water tank full (if applicable) but without personnel, equipment, and hose)
- Written load analysis and results of the electrical system performance tests
- Transmission make, model, and type
- The engine manufacturer's certified brake horsepower curve for the engine furnished, showing the maximum no load governed speed

WARNING AND INFORMATION LABELS

All warning and informational labels (non-vendor specific) shall be provided in compliance with (NFPA) 1901, Standard for Automotive Fire Apparatus, and installed in the appropriate locations to alert the operator of potential hazards and operating instructions.

ON-LINE CUSTOMER INTERACTION

The manufacture shall provide the capability for online access through the manufacture's website. The customer shall be able to view digital photos of their apparatus in the specified phases of construction. The following phases will be captured and displayed on the manufacture's website:

1. Chassis when available at manufacturing facility
2. Body – Prior to Paint

3. Body – Painted
4. Assembly – 80% Complete

Due to the complex nature of fire apparatus and the importance of communication between the manufacture and customer, this line item is considered a critical requirement.

LIABILITY INSURANCE COVERAGE

In order to protect the department and its personnel, the bidder shall show proof that it has no less than \$10 million in liability insurance in force. A certificate of coverage shall be included in the bid package. Failure to carry liability insurance of at least this amount or failure to include proof of coverage shall be cause to reject the bidder's proposal.

GENERAL WARRANTY

The manufacturer shall provide a two (2) year warranty from the date of delivery.

In the case of a commercial chassis being used, the warranty on the chassis, engine, transmission, tires, storage batteries, generators, electrical lamps and other devices subject to deterioration is limited to the warranty of the manufacturer thereof and adjustments for the same are to be made directly with the manufacturer by the customer.

STRUCTURAL BODY WARRANTY

A structural Aluminum body warranty shall be provided by the apparatus manufacturer for products of its manufacture to be free from defects in material and workmanship under normal use and service for a period of ten (10) years.

PAINT WARRANTY

A Prorated Paint Warranty shall be provided by the apparatus manufacturer for products of its manufacture to be free from defects in material and workmanship, under normal use and service, for a period of ten (10) years.

MULTI-PLEXED ELECTRICAL WARRANTY

A four (4) year limited (V-MUX) multiplex system warranty, of Weldon Technologies, Inc.; shall be provided by the apparatus manufacture for parts and labor, while under normal use and service; against mechanical, electrical and physical defects from the date of installation.

The warranty shall exclude; sensors, shunt interface modules, serial or USB kits, transceivers, cameras, GPS, and electrical display screens, which shall be limited to a period of one a (1) year repair parts and labor from the date of installation.

FACTORY PRECONSTRUCTION CONFERENCE

The factory authorized Distributor shall be required, prior to manufacturing, to have a pre construction conference at the manufacturing facility with a factory representative present and individuals from the Fresno Fire Department to finalize all construction details.

The factories authorized distributor shall, at his expense, provide transportation, lodging, and meals. Any distance greater than 200 miles shall be by commercial air travel.

FINAL INSPECTION CONFERENCE

The factory authorized Distributor shall be required, during manufacturing, to have a final completion inspection conference at the site of the manufacturing facility with One (1) individuals from the Fresno Fire Department to inspect the apparatus after construction.

The factories authorized distributor shall, at his expense, provide transportation, lodging, and meals. Any distance greater than 200 miles shall be by commercial air travel.

LIABILITY INSURANCE COVERAGE

In order to protect the department and its personnel, the bidder shall show proof that it has no less than \$10 million in liability insurance in force. A certificate of coverage shall be included in the bid package. Failure to carry liability insurance of at least this amount or failure to include proof of coverage shall be cause to reject the bidder's proposal.

OVERALL HEIGHT REQUIREMENT

The overall height (OAH) of the vehicle shall be approximately “ (11'-8") from the ground, **and will not exceed**. This measurement shall be taken on flat ground with the tires properly inflated, in the unloaded condition, at that highest point of the vehicle.

OVERALL LENGTH REQUIREMENT

There is no overall length (OAL) restriction for this vehicle.

ANGLE OF APPROACH

The angle of approach for this vehicle shall not be less than eight (8) degrees when it is loaded to the estimated in-service weight as specified by the current edition of NFPA 1901.

ANGLE OF DEPARTURE

The angle of departure for this vehicle shall not be less than eight (8) degrees when it is loaded to the estimated in-service weight as specified by the current edition of NFPA 1901.

INTERNET IN-PROCESS SITE

The manufacturer shall post and maintain a website where the Fresno Fire Department will be able to view digital images of their apparatus as its being built. The digital images shall be posted once a week starting when the body begins production or when the cab/chassis arrives and shall continue until the final completion of unit.

ENGINEERING DRAWINGS

The evaluation of bids shall also be based on design, engineering reliability, and completeness of drawings. No Bidder's proposal shall be considered unless complete engineering drawings to these specifications are submitted with the request for proposal package. Failure to submit factory prepared blueprints with bid shall result in automatic rejection. Submission of "bid drawings" are in addition to "production drawings" which must be submitted for Fresno Fire Department approval prior to construction. Bid drawings shall allow the Fresno Fire Department the ability to fully evaluate required product.

The engineering drawings shall be produced on computer aided design (CAD) equipment to assure critical tolerance and detail only available with CAD equipment. The drawings shall be on "B" size paper, 17" x 11" in size, and views must be 1/4" = 1' - 0" scale. This shall allow the Fresno Fire Department the ability to compare drawings of all manufacturers on an "equal" basis. The drawings shall be completed only by the body manufacturer, and must be exactly to Fresno Fire Department specifications. Submission of "similar to" drawings or "statements referring to later submission of drawings after award of contract" shall be automatically rejected.

Since the request for proposal package will require extensive evaluation by Fresno Fire Department, all Bidders must submit exactly the same engineering drawings at the same scale, on the same size paper. For easy comparison of drawings, they must be on a 17" x 11" sheet as follows:

- All bid drawings will be stamped BID DRAWING.
- All items shown on the drawing will be pre-designed with regards to layout and functionality prior to the completion of the BID DRAWING.
- Two (2) 17" x 11" color drawings will be supplied with the bid proposal. Black and white or blue line drawings will not be accepted.
- There shall be five (5) views of the truck with the doors closed (Top, Left, Right, Front, Rear), four (4) views of the truck with the doors open (Top, Left, Right, Rear) and four (4) views of any walk-in area (Top, Left, Right, Rear).
- All compartment door openings and usable space shall be clearly shown in inches.
- The trucks overall length, height, width, wheelbase and cab-to-axle dimensions shall be clearly shown.
- The angles of approach and departure shall be shown in the maximum loaded condition to the nearest degree.
- All lighting packages will be clearly shown on the drawing and verified accurate per the most current NFPA standards (when applicable).
- The exterior view shall show all scene lights, marker lights, speakers, horns, exhaust, tow points, exterior outlets, windows, winch receivers, tow hitches, exterior ladders and any other item important to the function of the vehicle.
- The open view shall show all trays, shelves, air system components, hydraulic components, tool boards, storage modules and any other items important to the function of the vehicle.
- The interior view for all walk-in areas shall show all seating positions, desks, cabinets, windows, tech equipment, radio locations and any other item important to the function of the vehicle.
- Any changes to the BID drawing will require a revision which will be clearly annotated in the upper right hand side of the drawing showing the revision number, reason for the revision, date and who made the changes.

Text Block Items;

- Purchaser's name.
- Body size and material type.
- Chassis manufacturer and model number.

- Unit description.
- Wheelbase (WB) , Cab-to-axle (CA) distance.
- Overall length (OAL), Overall width, (OAW), Overall height (OAH).
- Scale, date, drawn by, drawing number and sheet number.

RESPONSIBILITY OF PURCHASER

It shall be the responsibility of the purchaser to specify the details of the apparatus in addition to the requirements in NFPA 1901 needed by the manufacturer to build the apparatus, including:

- 1) Requirements not uniquely specified in NFPA 1901, such as the type of apparatus desired.
- 2) Any features of the apparatus desired in addition to, or in excess of, the requirements in NFPA 1901.

After acceptance of the fire apparatus, the purchaser shall be responsible for ongoing training of personnel to develop and maintain proficiency regarding the proper and safe use of the apparatus and the associated equipment.

RESPONSIBILITY OF CONTRACTOR

The Contractor shall provide a detailed description of the apparatus, a list of equipment to be furnished, and other construction and performance details to which the apparatus shall conform. The detailed description of the apparatus shall include, but shall not be limited to,

1. Estimated In-Service Weight,
2. Wheelbase, Turning Clearance Radius,
3. Principal dimensions, Angle of Approach, Angle of Departure,
4. Transmission, Axle Ratios.

The Contractor's detailed description shall include a statement specifically describing each aspect of the delivered apparatus that will not be fully compliant with the requirements of this standard.

The purpose of these Contractor specifications shall be to define what the contractor intends to furnish and deliver to the purchaser.

Responsibility for the apparatus and equipment shall remain with the contractor until they are accepted by the purchaser.

VEHICLE STABILITY

ROLLOVER STABILITY

The apparatus shall meet the criteria defined below, or it shall be equipped with a stability control system defined below.

The apparatus shall meet the criteria defined in either of the following:

- 1) The apparatus shall remain stable to 26.5 degrees in both directions when tested on a tilt table in accordance with SAE J2180, *A Tilt Table Procedure for Measuring the Static Rollover Threshold for Heavy Trucks*.
- 2) The calculated or measured center of gravity (CG) shall be no higher than 80 percent of the rear axle track width.

Compliance shall be certified by testing, calculating, or measuring the apparatus or by comparing the apparatus to a compliant, substantially similar example apparatus and the certification shall be delivered with the fire apparatus.

The example apparatus shall be considered substantially similar if it includes a chassis with the same or higher CG height, the same or narrower rear axle track width, the same or greater water tank size and CG height, the same type of front and rear suspension and the same type and size of aerial device.

The apparatus shall be loaded with fuel, fire-fighting agents, hose, ladders, a weight of 250 lb in each seating position and weight equivalent to the Miscellaneous Equipment Allowance as defined in Table 12.1.2.

If the apparatus is designed to meet a specified higher equipment loading or larger hose bed capacity or to carry additional ground ladders, these greater loads shall be included in the testing, calculating or measuring.

The weight added to the fire apparatus for the purpose of test, calculation or measurement shall be distributed to approximate typical in-service use of the fire apparatus while not exceeding the manufacturer's published individual compartment weight ratings.

If the apparatus is equipped with a stability control system, the system shall have, at a minimum, a steering wheel position sensor, a vehicle yaw sensor, a lateral accelerometer and individual wheel brake controls.

FIRE APPARATUS PERFORMANCE

The fire apparatus shall meet the requirements of this standard at elevations of 2000 ft (600 m) above sea level.

The fire apparatus shall meet all the requirements of this standard while stationary on a grade of 6 percent in any direction.

The fire apparatus shall meet the requirements of this standard in ambient temperature conditions between 32°F (0°C) and 110°F (43°C).

HIGHWAY PERFORMANCE

The apparatus, when loaded to its estimated in-service weight, shall be capable of the following performance while on dry, paved roads that are in good condition:

- 1) Accelerating from 0 to 35 mph (55 km/hr) within 25 seconds on a 0 percent grade
- 2) Attaining a speed of 50 mph (80 km/hr) on a 0 percent grade
- 3) Maintaining a speed of at least 20 mph (32 km/hr) on any grade up to and including 6 percent

The maximum top speed of fire apparatus with a GVWR over 26,000 lb (11,800 kg) shall not exceed either 68 mph (109 km/hr) or the manufacturer's maximum fire service speed rating for the tires installed on the apparatus, whichever is lower.

If the combined water tank and foam agent tank capacities on the fire apparatus exceed 1250 gal (4732 L), or the GVWR of the vehicle is over 50,000 lb (22,680 kg), the maximum top speed of the apparatus shall not exceed either 60 mph (95 km/hr) or the manufacturer's maximum fire service speed rating for the tires installed on the apparatus, whichever is lower.

SERVICEABILITY

The fire apparatus shall be designed to allow the manufacturer's recommended routine maintenance checks of lubricant and fluid levels to be performed by the operator without lifting the cab of a tilt-cab apparatus or without the need for hand tools.

Where special tools are required for routine service on any component of the apparatus, such tools shall be provided with the apparatus.

Apparatus components that interfere with repair or removal of other major components shall be attached with fasteners, such as cap screws and nuts, so that the components can be removed and installed with ordinary hand tools. These components shall not be welded or otherwise permanently secured into place.

FIRE APPARATUS DOCUMENTATION

The contractor shall supply, at the time of delivery, at least one (1) copy of the following documents:

- 1) The manufacturer's record of apparatus construction details, including the following documents:
 - a) Owner's name and address
 - b) Apparatus manufacturer, model, and serial number
 - c) Chassis make, model, and serial number
 - d) GAWR of front and rear axles and GVWR
 - e) Front tire size and total rated capacity in pounds (kilograms)
 - f) Rear tire size and total rated capacity in pounds (kilograms)
 - g) Chassis weight distribution in pounds (kilograms) with water and manufacturer-mounted equipment (front and rear)
 - h) Engine make, model, serial number, rated horsepower and related speed, and governed speed; and if so equipped, engine transmission PTO(s) make, model, and gear ratio
 - i) Type of fuel and fuel tank capacity
 - j) Electrical system voltage and alternator output in amps
 - k) Battery make, model, and capacity in cold cranking amps (CCA)
 - l) Chassis transmission make, model, and serial number; and if so equipped, chassis transmission PTO(s) make, model, and gear ratio

- m) Ratios of all driving axles
 - n) Maximum governed road speed
 - o) Pump make, model, rated capacity in gallons per minute (liters per minute where applicable), maximum discharge pressure capability rating, and serial number
 - p) Pump transmission make, model, serial number, and gear ratio
 - q) Auxiliary pump make, model, rated capacity in gallons per minute (liters per minute where applicable), and serial number
 - r) Water tank certified capacity in gallons or liters
 - s) Foam tank (if provided) certified capacity in gallons (liters)
 - t) Aerial device type, rated vertical height in feet (meters), rated horizontal reach in feet (meters), and rated capacity in pounds (kilograms)
 - u) Paint manufacturer and paint number(s)
 - v) Company name and signature of responsible company representative
 - w) Weight documents from a certified scale showing actual loading on the front axle, rear axle(s), and overall fire apparatus (with the water tank full but without personnel, equipment, and hose)
- 2) Certification of compliance of the optical warning system (*see 13.8.16*)
 - 3) Siren manufacturer's certification of the siren (*see 13.9.1.1*)
 - 4) Written load analysis and results of the electrical system performance tests (*see 13.14.1 and Section 13.15*)
 - 5) Certification of slip resistance of all stepping, standing, and walking surfaces (*see 15.7.4.5*)
 - 6) If the apparatus has a fire pump, the pump manufacturer's certification of suction capability (*see 16.2.4.1*)
 - 7) If the apparatus is equipped with a fire pump and special conditions are specified by the purchaser, the pump manufacturer's certification of suction capacity under the special conditions (*see 16.2.4.2*)
 - 8) If the apparatus has a fire pump, a copy of the apparatus manufacturer's approval for stationary pumping applications (*see 16.3.1*)
 - 9) If the apparatus has a fire pump, the engine manufacturer's certified brake horsepower curve for the engine furnished, showing the maximum governed speed (*see 16.3.2.2*)
 - 10) If the apparatus has a fire pump, the pump manufacturer's certification of the hydrostatic test (*see 16.5.2.2*)
 - 11) If the apparatus has a fire pump with a maximum discharge pressure capability rating that exceeds the hydrostatic test pressure of 16.5.2.1, the pump manufacturer's certification of the hydrodynamic test
 - 12) If the apparatus has a fire pump, the certification of inspection and test for the fire pump (*see 16.13.1.1.5 or 16.13.1.2.4 as applicable*)
 - 13) If the apparatus is equipped with an auxiliary pump, the apparatus manufacturer's certification of the hydrostatic test (*see Section 17.13*)
 - 14) When the apparatus is equipped with a water tank, the certification of water tank capacity (*see Section 18.6*)
 - 15) If the apparatus has an aerial device, the certification of inspection and test for the aerial device (*see Section 19.24*)
 - 16) If the apparatus has an aerial device, all the technical information required for inspections to comply with NFPA 1911
 - 17) If the apparatus has a foam proportioning system, the foam proportioning system manufacturer's certification of accuracy (*see 20.10.4.2*) and the final installer's certification the foam proportioning system meets this standard (*see 20.11.2*)
 - 18) If the system has a CAFS, the documentation of the manufacturer's pre delivery tests (*see Section 21.9*)
 - 19) If the apparatus has a line voltage power source, the certification of the test for the power source (*see 22.15.7.2*)
 - 20) If the apparatus is equipped with an air system, air tank certificates (*see 24.5.1.2*), the SCBA fill station certification (*see 24.9.6*), and the results of the testing of the air system installation (*see 24.14.5 and 24.15.4*)
 - 21) Any other required manufacturer test data or reports

OPERATIONS AND SERVICE DOCUMENTATION

The contractor shall deliver with the fire apparatus complete operation and service documentation covering the completed apparatus as delivered and accepted.

The documentation shall address at least the inspection, service, and operations of the fire apparatus and all major components thereof.

The contractor shall also deliver with the fire apparatus the following documentation for the entire apparatus and each major operating system or major component of the apparatus:

- 1) Manufacturer's name and address
- 2) Country of manufacture
- 3) Source for service and technical information
- 4) Parts replacement information
- 5) Descriptions, specifications, and ratings of the chassis, pump (if applicable), and aerial device (if applicable)
- 6) Wiring diagrams for low voltage and line voltage systems to include the following information:
 - a) Pictorial representations of circuit logic for all electrical components and wiring
 - b) Circuit identification
 - c) Connector pin identification
 - d) Zone location of electrical components
 - e) Safety interlocks
 - f) Alternator–battery power distribution circuits
 - g) Input/output assignment sheets or equivalent circuit logic implemented in multiplexing systems
- 7) Lubrication charts
- 8) Operating instructions for the chassis, any major components such as a pump or aerial device, and any auxiliary systems
- 9) Precautions related to multiple configurations of aerial devices, if applicable
- 10) Instructions regarding the frequency and procedure for recommended maintenance
- 11) Overall apparatus operating instructions
- 12) Safety considerations
- 13) Limitations of use
- 14) Inspection procedures
- 15) Recommended service procedures
- 16) Troubleshooting guide
- 17) Apparatus body, chassis and other component manufacturer's warranties
- 18) Special data required by this standard
- 19) A material safety data sheet (MSDS) for any fluid that is specified for use on the apparatus

The contractor shall deliver with the apparatus all manufacturer's operations and service documents supplied with components and equipment that are installed or supplied by the contractor.

NFPA REQUIRED DOCUMENTATION FORMAT - USB FLASH DRIVE

The vehicle construction details and the operations and service documentation as required per NFPA 1901 latest edition shall be provided on a USB Flash Drive. These manuals shall be divided into sections for ease of reference. There shall be two (2) USB flash drives provided with the completed vehicle.

FIRE APPARATUS SAFETY GUIDE

A Fire Apparatus Safety Guide published by Fire Apparatus manufacturer's Association shall be provided with delivered vehicle. This manual includes essential safety information for fire fighters, fire chiefs, apparatus mechanics, and fire department safety officers. The guide is applicable to municipal, wildland, and airport fire fighting apparatus manufactured on either custom or commercial chassis.

STATEMENT OF EXCEPTIONS

The final-stage manufacturer shall deliver with the fire apparatus either a certification that the apparatus fully complies with all requirements of this standard or alternatively, a Statement of Exceptions specifically describing each aspect of the completed apparatus that is not fully compliant with the requirements of this standard at the time of delivery.

The Statement of Exceptions shall contain, for each noncompliant aspect of the apparatus or missing required item, the following information:

- 1) A separate specification of the section of the applicable standard for which compliance is lacking
- 2) A description of the particular aspect of the apparatus that is not in compliance therewith or required equipment that is missing
- 3) A description of the further changes or modifications to the delivered apparatus that must be completed to achieve full compliance
- 4) Identification of the entity that will be responsible for making the necessary post delivery changes or modifications or for supplying and installing any missing required equipment to the apparatus to achieve full compliance with this standard

Prior to or at the time of delivery of the apparatus, the Statement of Exceptions shall be signed by an authorized agent of the entity responsible for final assembly of the apparatus and by an authorized agent of the purchasing entity, indicating mutual understanding and agreement between the parties regarding the substance thereof.

CARRYING CAPACITY

The GAWR and the GCWR or GVWR of the chassis shall be adequate to carry the weight of the completed vehicle when loaded to its estimated in-service weight. The manufacturer shall establish the estimated in service weight during the design of the vehicle.

The estimated in-service weight shall include the following:

1. The chassis, body and tank(s)
2. Full fuel, lubricant, and other chassis or component fluid tanks or reservoirs
3. Full water and other agent tanks
4. *250 lb (114 kg) in each seating position
5. Fixed equipment such as pumps, aerial devices, generators, reels and air systems as installed
6. Ground ladders, suction hose, designed hose load in their hose beds and on their reels
7. An allowance for miscellaneous equipment that is the greatest of the following:
 - a) The values shown for items 1 - 7
 - b) A purchaser-provided list of equipment to be carried with weights
 - c) A purchaser-specified miscellaneous equipment allowance

The manufacturer shall engineer and design the fire apparatus such that the completed apparatus, when loaded to its estimated in-service weight, with all movable weights distributed as close as is practical to their intended in-service configuration, does not exceed the GVWR.

A final manufacturer's certification of the GVWR or GCWR, along with a certification of each GAWR, shall be supplied on a label affixed to the vehicle.

The fire apparatus manufacturer shall permanently affix a high-visibility label in a location visible to the driver while seated.

The label shall show the height of the completed unequipped fire apparatus in feet and inches (meters), the length of the completed fire apparatus in feet and inches (meters), and the GVWR in tons (metric tons).

Wording on the label shall indicate that the information shown was current when the apparatus was manufactured and that, if the overall height changes while the vehicle is in service, the fire department must revise that dimension on the plate.

Apparatus Type	Equip. Storage Area	Apparatus Size	Equipment Allowance	
			lb.	kg.
Special Service Fire Apparatus	Minimum of 120 cu ft (3.4 cu mt) of enclosed compartmentation.	10,000 lb to 15,000 lb (4,500 kg to 7,000 kg) GVWR	2,000	910
		15,001 lb to 20,000 lb (7,001 kg to 9,000 kg) GVWR	2,500	1,135
		20,001 lb to 30,000 lb (9,001 kg to 14,000 kg) GVWR	3,000	1,350
		30,001 lb to 40,000 lb (14,001 kg to 18,000 kg) GVWR	4,000	1,800
		40,001 lb to 50,000 lb (18,001 kg to 23,000 kg) GVWR	6,000	2,700
		50,001 lb to 60,000 lb (23,001 kg to 27,000 kg) GVWR	8,000	3,600
		60,001 lb and up (27,001 kg) GVWR	10,000	4,500

TESTING

ROAD TEST

Each apparatus shall be tested by the manufacturer before delivery to verify that it meets the following criteria;

Tests shall be conducted at a location and in a manner that does not violate local, state or provincial, or federal traffic laws. Tests shall be conducted on a dry, level, paved surface that is free of loose material, oil, or grease. Tests shall be conducted with the water and foam tanks full (water or product).

The apparatus shall accelerate from 0 to 35 mph (55 km/hr) within 25 seconds. The apparatus shall attain a speed of 50 mph (80 km/ hr).

The auxiliary braking system, if so equipped, shall function as intended by the auxiliary braking system manufacturer.

The air service brakes shall bring the apparatus to a complete stop from a speed of 20 mph (32.2 km/hr) in a distance not exceeding 35 ft (10.7 m).

The hydraulic service brakes shall bring the apparatus to a complete stop from a speed of 30 mph (48.2 km/hr) in a distance not exceeding 88 ft (26.8 m).

LOW VOLTAGE - ELECTRICAL SYSTEM PERFORMANCE TEST

The vehicles low voltage electrical system shall be tested and certified by the manufacturer. The certified test results shall be delivered with the completed vehicle. Tests shall be performed when the air temperature is between 0°F and 110°F (-18°C and 43°C).

TEST SEQUENCE

The following three (3) tests shall be performed in the order in which they appear below. Before each test, the batteries shall be fully charged until the voltage stabilizes at the voltage regulator set point and the lowest charge current is maintained for ten (10) minutes. Failure of any of these tests shall require a repeat of the sequence.

1. RESERVE CAPACITY TEST

The engine shall be started and kept running until the engine and engine compartment temperatures are stabilized at normal operating temperatures and the battery system is fully charged. The engine shall be shut off and the minimum continuous electrical load shall be activated for ten (10) minutes.

All electrical loads shall be turned off prior to attempting to restart the engine. The battery system shall then be capable of restarting the engine. Failure to restart the engine shall be considered a test failure of the battery system.

2. ALTERNATOR PERFORMANCE TEST

TEST AT IDLE

The minimum continuous electrical load shall be activated with the engine running at idle speed. The engine temperature shall be stabilized at normal operating temperature. The battery system shall be tested to detect the presence of battery discharge current. The detection of battery discharge current shall be considered a test failure.

TEST AT FULL LOAD

The total continuous electrical load shall be activated with the engine running up to the engine manufacturer's governed speed. The test duration shall be a minimum of two (2) hours. Activation of the load management system shall be permitted during this test.

An alarm sounded by excessive battery discharge, as detected by the warning system required in 13.3.4, or a system voltage of less than 11.8 V dc for a 12 V nominal system, 23.6 V dc for a 24 V nominal system, or 35.4 V dc for a 42 V nominal system for more than 120 seconds shall be considered a test failure.

3. LOW VOLTAGE ALARM TEST

The following test shall be started with the engine off and the battery voltage at or above 12 V for a 12 V nominal system, 24 V for a 24 V nominal system or 36 V for a 42 V nominal system.

With the engine shut off, the total continuous electrical load shall be activated and shall continue to be applied until the excessive battery discharge alarm activates. The battery voltage shall be measured at the battery terminals.

The test shall be considered a failure if the alarm does not sound in less than 140 seconds after the voltage drops to 11.70 V for a 12 V nominal system, 23.4 V dc for a 24 V nominal system, or 35.1 V for a 42 V nominal system.

The battery system shall then be able to restart the engine. Failure to restart the engine shall be considered a test failure.

LOW VOLTAGE - ELECTRICAL SYSTEM PERFORMANCE TEST

DOCUMENTATION

The manufacturer shall deliver the following with the fire apparatus:

- 1) Documentation of the electrical system performance tests
- 2) A written electrical load analysis, including the following:
 - a) The nameplate rating of the alternator
 - b) The alternator rating
 - c) Each of the component loads specified that make up the minimum continuous electrical load
 - d) Additional electrical loads that, when added to the minimum continuous electrical load, determine the total continuous electrical load
 - e) Each individual intermittent electrical load

UL 120/240 VAC CERTIFICATION

The 120/240 volt electrical system shall be third-party, independent, audit-certified through Underwriters Laboratory (UL) to the current edition of NFPA 1901 to perform as listed below;

The prime mover shall be started from a cold start condition, and the unloaded voltage and frequency shall be recorded.

The line voltage electrical system shall be loaded to at least 100% of the continuous rated wattage stated on the power source specification label. Testing with a resistive load bank shall be permitted.

The power source shall be operated in the manner specified by the apparatus manufacturer as documented on instruction plates or in operation manuals. The power source shall be operated at a minimum of 100% of the continuous rated wattage as stated on the power source specification label for a minimum of two (2) hours.

The load shall be adjusted to maintain the output wattage at or above the continuous rated wattage during the entire 2-hour test.

The following conditions shall be recorded at least every 1/2 hour during the test:

- 1) The power source output voltage, frequency and amperes
- 2) The prime mover's oil pressure, water temperature and transmission temperature, if applicable
- 3) The power source hydraulic fluid temperature, if applicable
- 4) The ambient temperature and power source air inlet temperature

The following conditions shall be recorded once during the test for power sources driven by dedicated auxiliary internal combustion engines:

- 1) Altitude
- 2) Barometric pressure
- 3) Relative humidity

If the generator is driven by the chassis engine and the generator allows for operation at variable speeds, the chassis engine speed shall be reduced to the lowest rpm allowed for generator operation and the voltage and frequency shall be recorded.

The load shall be removed and the unloaded voltage and frequency shall be recorded.

Voltage shall be maintained within $\pm 10\%$ of the voltage stated on the power source specification label during the entire test. Frequency shall be maintained within ± 3 Hz of the frequency stated on the power source specification label during the entire test.

The total continuous electrical loads, excluding those loads associated with the equipment defined in NFPA 22.15.7.3.11.2, shall be applied during the testing unless an auxiliary engine drives the power source.

If the apparatus is equipped with a fire pump, the 2-hour certification test of the power source shall be completed with the fire pump pumping at 100% capacity at 150 psi (1000 kPa) net pump pressure. The test shall be permitted to be run concurrently with the pump certification test.

DOCUMENTATION

The results of each test shall be recorded on an appropriate form and provided with the delivery of the fire apparatus.

DIELECTRIC VOLTAGE WITHSTAND TEST

The line voltage wiring and permanently connected devices and equipment shall be subjected to a dielectric voltage withstand test of 900 volts for one (1) minute. The testing shall be performed after all body work has been completed.

The test shall be conducted as follows:

- 1) Isolate the power source from the panel board and disconnect any solid state low voltage components
- 2) Connect one lead of the dielectric tester to all the hot and neutral buses tied together
- 3) Connect the other lead to the fire apparatus frame or body
- 4) Close any switches and circuit breakers in the circuit(s)
- 5) Apply the dielectric voltage for one (1) minute in accordance with the testing equipment manufacturer's instructions

The electrical polarity of all permanently wired equipment, cord reels and receptacles shall be tested to verify that wiring connections have been properly made.

Electrical continuity shall be verified from the chassis or body to all line voltage electrical enclosures, light housings, motor housings, light poles, switch boxes and receptacle ground connections that are accessible to fire fighters in normal operations.

If the apparatus is equipped with a transfer switch, it shall be tested to verify operation and that all non grounded conductors are switched.

Electrical light towers, floodlights, motors, fixed appliances and portable generators shall be operated at their full rating or capacity for 30 minutes to ensure proper operation.

WARRANTY

A full statement shall be provided of the warranties for the vehicle(s) being bid. Warranties should clearly describe the terms under which the vehicle manufacturer accepts responsibility for the cost to repair defects caused by faulty design, quality of work or material and for the applicable period of time after delivery.

Cost of repairs refers to all costs related thereto including, but not limited to, the cost of materials and the cost of labor.

The Body Manufacturer shall warrant all materials and accessories used on the vehicle(s), whether fabricated by manufacturer or purchased from an outside source and will deal directly with the Fresno Fire Department on all warranty work.

GENERAL LIMITED WARRANTY - TWO (2) YEARS

The vehicle shall be free of defects in material and workmanship for a period of two (2) years or 36,000 miles (or 57,936 kilometers), whichever occurs first starting thirty (30) days after the original invoice date.

The Contractor must be the "single source" coordinator of all warranties on the vehicle.

LOW VOLTAGE ELECTRICAL WARRANTY - FIVE (5) YEARS

The vehicle low voltage electrical system shall be free of defects in material and workmanship for a period of five (5) years or 60,000 miles (or 96,561 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date.

STRUCTURAL WARRANTY - TEN (10) YEARS

The body shall be free of structural or design failure or workmanship for a period of ten (10) years, or 100,000 miles (or 160,934 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date.

UNDERCOAT WARRANTY

The body undercoating shall have a warranty provided by the manufacturer for the lifetime of the vehicle or twenty (20) years, whichever occurs first. The warranty shall be transferable between vehicle owners. Should the undercoating material applied to the underside of the body and wheel wells of the vehicle ever flake off, peel, chip or crack due to drying out, the damaged area shall be re-sprayed without charge to the vehicle owner.

PAINT LIMITED WARRANTY - TEN (10) YEARS

The body shall be free of bubbling or peeling as a result of a defect in the method of manufacture for a period of ten (10) years or 100,000 miles (or 160,934 kilometers), whichever occurs first, starting thirty (30) days after the original invoice date. **Pro-rated warranties will not be acceptable.**

GRAPHICS LIMITED WARRANTY

The 3M graphics installation shall be warranted for a period of two (2) years. The 3M materials installed on completed vehicle shall be warranted for seven (7) years. The 3M Diamond grade film (if specified) shall be warranted for ten (10) years.

CONSTRUCTION PERIOD

The completed vehicle shall be delivered within four hundred ninety (490) days after pre-construction meeting and receipt and approval of any signed change orders from Fresno Fire Department.

Contractor shall not be held liable for delays of chassis delivery due to accidents, strikes, floods or other events not subject to their control. Contractor shall provide written notice to Fresno Fire Department as to delays and to what extent these delays have in completing vehicle within the stated construction time period.

DELIVERY AND DEMONSTRATION

The Contractor shall be responsible for the delivery of the completed unit to the Fresno Fire Department's location. On initial delivery of the apparatus, the Contractor shall supply a qualified representative to demonstrate the apparatus and provide initial instruction to representatives of the Fresno Fire Department regarding the operation, care and maintenance of the apparatus and equipment supplied at Fresno Fire Department location.

The Delivery Engineer shall set delivery and instruction schedule with the person appointed by Fresno Fire Department.

After delivery of the apparatus, the Fresno Fire Department shall be responsible for ongoing training of its personnel to proficiency regarding the proper and safe use of the apparatus and associated equipment.

CAB CHASSIS SPECIFICATION

Spartan

CAB TO AXLE DIMENSION

Cab to axle to center of rear tandems will be 190.5".

CHASSIS MODIFICATIONS

LUBRICATION AND TIRE DATA PLATE

A permanent label in the driving compartment shall specify the quantity and type of the following fluids used in the vehicle and tire information:

- Engine oil
- Engine coolant
- Chassis transmission fluid
- Pump transmission lubrication fluid . . (if applicable)
- Pump priming system fluid, if applicable . . (if applicable)
- Drive axle(s) lubrication fluid
- Air conditioning refrigerant . . (if applicable)
- Air conditioning lubrication oil . . (if applicable)
- Power steering fluid
- Cab tilt mechanism fluid . . (if applicable)
- Transfer case fluid . . (if applicable)
- Equipment rack fluid (if applicable)
- CAFS air compressor system lubricant . . (if applicable)
- Generator system lubricant . . (if applicable)
- Front tire cold pressure
- Rear tire cold pressure
- Maximum tire speed ratings

VEHICLE DATA PLATE

A permanent label in the driving compartment which indicates the following:

- Filter part numbers for the;
 - Engine
 - Transmission
 - Air
 - Fuel
- Serial numbers for the;
 - Engine
 - Transmission
- Delivered Weights of the Front and Rear Axles
- Paint Brand and Code(s)
- Sales Order Number

OVERALL HEIGHT, LENGTH DATA PLATE (US)

The fire apparatus manufacturer shall permanently affix a high-visibility label in a location visible to the driver while seated.

The label shall show the height of the completed unequipped vehicle in feet and inches (meters), the length of the completed vehicle in feet and inches (meters to nearest 1/10th), and the GVWR in tons (metric tons).

Wording on the label shall indicate that; "The information shown was current when the apparatus was manufactured. If the overall height changes while the vehicle is in service, the fire department must revise that dimension on the plate".

PERSONNEL CAPACITY

A label that states the number of personnel the vehicle is designed to carry shall be located in an area visible to the driver.

SEAT BELT WARNING - FAMA06/07

A safety sign FAMA06 shall be visible from each seat that is not equipped with occupant restraint and therefore not intended to be occupied while the vehicle is in motion.

A safety sign FAMA07, which warns of the importance of seat belt use, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

EQUIPMENT MOUNTING FAMA10

A safety sign FAMA10, which warns of the need to secure items in the cab, shall be visible inside the cab.

FIRE SERVICE TIRES - FAMA12

A safety sign FAMA12, which warns of the special requirements for fire service-rated tires, shall be visible to the driver entering the cab of any apparatus so equipped.

HELMET WARNING - FAMA15

A safety sign FAMA15, which warns not to wear helmets while the vehicle is in motion, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

CLIMBING METHOD - FAMA23

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

REAR STEP CROSSWALK WARNING - FAMA24

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

FINAL STAGE MANUFACTURER VEHICLE CERTIFICATION

A final stage manufacturer vehicle certification label shall be provided and installed in the driver cab door jamb area.

OEM FRONT BUMPER REPLACEMENT

The standard OEM bumper shall be removed and replaced with a custom bumper design. A 2" x 2" x 1/4" welded steel tubing framework shall be bolted to the OEM bumper mount location extending bumper 28". The framework is designed as an under slung "L" shape to allow for a deeper compartment storage above.

An SVI Edge contoured one-piece, fully welded steel construction front bumper shall be bolted in place of the OEM bumper. The front bumper {will/shall} be fabricated from formed 7 gauge steel and welded to create contoured edges for an aesthetically pleasing design and improved front approach angle. Two (2) 3/4" steel tow eyes shall be provided on front with 2" opening. Bumper painted finish shall match lower cab paint color.

The top of the 28" extension shall be enclosed with 3/16" NFPA compliant aluminum treadplate. A large compartment shall be recessed into extension, 75" wide x 18" front-back, x 10" deep formed from 3/16" smooth aluminum. Additional options added ie: winch, air horns, recessed siren or speakers, make take away from compartment dimensions.

A 5" high single lid shall cover compartment fabricated from 1/8" aluminum tread plate with stainless steel hinges, chrome lift handle, two (2) butterfly type latches, and two (2) gas shock type hold open devices, one (1) at each end. A "Not a Step" label shall be provide on outer lid surface.

Bumper compartment shall have **one (1)** OnScene 36" Access LED lights mounted to light inside the compartment area to provide a minimum of 2 fc (20 lx) at any location on the floor of the compartment without any equipment in the compartment. Light shall be automatically activated when door is opened. A flashing warning light signal shall be provided indicating when parking brake is released that a compartment door is not in a closed position as required by NFPA 1901.

- Mount(s) shall be provided and installed for one (1) Fresno Fire Department supplied ram(s).
- Mounts will be supplied and installed for one (1) Fresno Fire Department supplied cutter(s).
- Mounts will be supplied and installed for one (1) Fresno Fire Department supplied spreader(s).
- **There shall mounting for two (2) battery chargers.**
- **There shall be one (1) 110V outlet powered by Gen/Shore**

RECESSED INTERSECTION LIGHTING

The **sides front corners** of front bumper extension shall have recessed pans for specified intersection lighting.

AIR HORNS - BUMPER MOUNTED

AIR HORNS

Shall be Cab-Chassis supplied.

MOTOR DRIVEN SIREN

There shall be a Federal model Q2B motor driven rotary siren with chrome plated grill and housing, recess in the extended front bumper. The siren shall be wired through the master warning light switch, and properly wired with heavy copper cable for minimum voltage drop.

The siren shall be located on the streetside of the front bumper.

There shall be a siren brake installed in the rocker switch control panel to activate the siren brake.

SIREN ACTIVATION

The siren activation shall be provided by cab/chassis manufacturer.

CHROME BELL

A chrome plated bell shall be **customer** supplied and **SVI installed** on the curbside of the front bumper extension with a pull cord in the cab.

BELL ACTIVATION

The specified Bell shall be controlled by a pull cord routed into the Officer's Dash area. Pull rope shall be routed through 1/4" stainless steel eyelets and terminate in transverse orientation as base of Dash Panel. Care shall be taken to not interfere with the deployment of any Airbags.

FRONT BUMPER

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with a black hammertone powder coat paint finish located at the front bumper for use with removable rope anchor point and/or a portable electric winch (if specified).
 - There shall be one (1) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
 - The receiver(s) shall have one (1) rubber cover(s) provided.

FRONT BUMPER RECIEVER, SIDES

There shall be two (2) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located, one (1) on streetside, and one (1) on curbside of front bumper extension for use with removable rope anchor and/or a portable electric winch (when specified).

- There shall be two (2) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
- The receiver(s) shall have two (2) rubber cover(s) provided.

SIREN SPEAKER

Two (2) Federal Signal model ES100, 100 watt siren speakers shall be provided with model ESFMT polished trim ring recess mounted, one (1) on the streetside and one (1) on the curbside of the front bumper.

SPEAKER GRILLE

The specified speaker(s) shall have a ~~Federal "F" style~~ grille over speaker with polished stainless steel finish. **With Fresno Logo.**

AIR INTAKE SYSTEM

An air filter shall be provided in the engine's air intake system by the customer cab/chassis manufacturer.

Air inlet restrictions shall not exceed the engine manufacturer's recommendations.

The air inlet shall be equipped with a means of separating water and burning embers from the air intake system.

This requirement shall be permitted to be achieved by either of the following methods:

1. Provision of a device such that burning particulate matter larger than 0.039 in. (1.0 mm) in diameter cannot reach the air filter element.
2. Provision of a multi screen ember separator capable of meeting the test requirements defined in the Parker Hannafin, Racor Division, publication LF 1093-90, *Ember Separation Test Procedure*, or an equivalent test.

EXHAUST DIVERTER

An exhaust diverter valve shall be located in-line of exhaust tubing and controlled from driver's position to re-route exhaust discharge. Exhaust diverter valve shall be constructed from 14 gauge stainless steel material with air actuated control.

As a default, the exhaust shall always discharge to curbside just ahead of rear wheels, and when selected the exhaust shall discharge to a vertical exhaust pipe, extending above the body height 12".

The exhaust piping and discharge outlet shall be located or shielded so as not to expose any portion of the apparatus or equipment to excessive heating.

Exhaust pipe discharge shall be directed away from any operator's position.

Where parts of the exhaust system are exposed so that they are likely to cause injury to operating personnel, protective guards shall be provided.

- Exhaust Diverter shall actuate automatically when the Park Brake is applied.
- The tail pipe(s) shall terminate in a standard straight cut pipe.
- The tail pipe(s) shall terminate parallel to rear axle and flush with body.

SEAT BELT COLOR

Section 14.1.3.3 of the NFPA 1901 Standards, requires all seat belt webbing in cab to be bright red or bright orange in color, and the buckle portion of the seat belt shall be mounted on a rigid or semi rigid stalk such that the buckle remains positioned in an accessible location.

SEAT BELT WEB LENGTH - CUSTOM CAB

Sections 14.1.3.2 and 14.1.3.3 of the NFPA 1901 standards, require the effective seat belt web length for a Type 1 lap belt for pelvic restraint to be a minimum of 60", and a Type 2 pelvic and upper torso restraint-style seat belt assembly to be a minimum of 110".

The chassis seat belt web length as supplied by the custom chassis manufacturer shall be compliant to NFPA Standards 14.1.3.2 and 14.1.3.3.

SEAT BELT / VDR SYSTEM - CUSTOM CAB

The seat belt warning and vehicle data recorder systems shall be provided by the cab/chassis manufacturer.

TIRE PRESSURE VISUAL INDICATORS

The tire pressure visual indicators shall be supplied by the cab and chassis manufacturer.

Ship Loose

HELMET STORAGE

No helmet storage is required in the cab driving area. A safety sign FAMA15, which warns not to wear helmets while the vehicle is in motion, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

HELMET STORAGE

No helmet storage is required in the cab crew area. A safety sign FAMA15, which warns not to wear helmets while the vehicle is in motion, shall be visible from each seat that is intended to be occupied while the vehicle is in motion.

CAB INTERIOR COMPONENT PAINT COLOR

Powder coat shall be ~~hammer tone black. Cardinal T013-BK62~~ **onyx black to match chassis supplied finish.**

HUB AND NUT COVERS

The cab and chassis supplied front and rear wheels hub caps and wheel nut covers shall be installed prior to delivery of completed unit.

MUDFLAPS

There shall be a full width 1/4" rubber mudflap with no logo provided and installed behind rear set of tires to prevent throwing road debris and lower road spray.

A custom laser-cut design shall be **cut from stainless steel sheet and bolted to mudflap; "FRESNO FIRE" in font matching graphics package and overlaid with red reflective vinyl with white outline.**

AIR BRAKE SYSTEM QUICK BUILD-UP

The air brake quick build-up system shall be supplied from the cab/chassis manufacturer.

The quick buildup system shall provide sufficient air pressure so that the apparatus has no brake drag and is able to stop under the intended operating conditions following the 60-second buildup time.

CHASSIS AIR TANK VALVES

The cab/chassis air brake system tank drains shall be extended to Class 1 brass petcock valves with chrome plated zinc handle located on forward streetside lower body or as per tank locations. Each air tank and valve shall be inter-piped with black reinforced nylon tubing. Brass compression type fittings shall be used on the nylon tubing, meeting all DOT requirements.

Each handle shall be properly labeled to identify each tank.

- **Routed to streetside aft of the underbody compartment.**

ROAD EMERGENCY SAFETY KIT

The DOT required reflective triangles, warning flares, and fire extinguisher shall be provided by cab and chassis supplier.

CREW CAB INTERIOR COMPONENTS

CAB A-PILLAR GRAB HANDLES

Both chassis supplied A-Pillar grab handles shall be flipped/rotated 180 deg on there current mounts to place the handle forward of the A-Pillar to provide more space on both sides of the dash for Steering wheel and Laptop computer.

CAB DASH USB PORTS

Add two (2) Kussmaul dual rocker switch USB charging ports to the cab dash, center panel. One (1) will be located in the right side lower corner, inboard of the Officer PTT switch and the other will be located between the Climate Controls and Radio Cutout provided by Chassis.




Image provide in folder.

CAB DESK AND CABINETS

REAR CAB COMPONENT LAYOUT

The following components shall be provided in the rear area of cab, final layout to be determined at pre-construction meeting.

Rear Cab: Desk/Cabinets, Not Provided

CAB INTERIOR CABINET - OVERHEAD (EMS COMPT TO CEILING)

There shall be two (2) rear facing overhead cabinet(s) provided on interior. Each cabinet shall be constructed of 1/8" smooth finish aluminum ~~approximately 14" high x 14" deep x 26" wide~~. If cab is specified with air bags, the interior cabinet(s) will be mounted clear of the deployment area.

- **All hardware used on interior components shall be black oxide coated stainless steel similar to McMaster 91249A244.**
- **This will include black latches and powder coated hinges.**
- **Bi Fold Doors**
- The compartment light(s) shall be controlled by a switch actuated by the compartment door.
- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- Two (2) OnScene Access white LED light(s) mounted in cabinet(s).
- There shall be two (2) vertically adjustable shelves in each of the above cabinets.

CAB INTERIOR CABINET - BEHIND ENGINE TUNNEL

CAB CABINET WITH UPPER SLIDING COMMAND DESK

The rear crew area of cab directly behind engine tunnel shall be provided with a lower cabinet with hinged double **bi-fold** doors. A command desk with lift-up slanted surface with storage area below shall be provided on top of lower cabinet. Cabinet shall be approximately 46" wide x 28" high x 21" deep.

The lift-up slanted surface desk top shall have a stainless steel hinged top to gain access to the storage area below with an approximate 30" height from floor at front of desk. Cabinet shall be approximately 43" wide x 4" high at back and 2" high at front x 24" deep and slide-out toward rear cab seating approx. 21".

Both the cabinet and desk shall be fabricated of .125" smooth aluminum. A 1" vertical lip shall be provided at the lower edge of the writing surface to prevent items from sliding off. The entire lift up desk lid shall be painted with a white smooth finish and include a vinyl dry-erase material on the exterior writing surface.

- **All hardware to be black oxide coated stainless steel with black hinges and latches.**
- There shall be one (1) 120 VAC outlet(s) located ~~under~~ **above** desk against the back edge.
- There shall be one (1) 120 VAC, 20 amp custom fabricated outlet strip provided with four (4) 20 amp duplex outlets. Strip shall be approximately As wide as desk design allows. long.

- Outlet(s) shall be powered by both the on-board generator and shore power system through a relay system.

CAB, CAB DESK, CABINET - VDC COMPONENTS

- There shall be one (1) Blue Sea Systems ST series blade type fuse block(s) with screw type terminals for both positive and negative buss with cover provided for distribution of up to twelve (12) 30 amp, 12 VDC circuits.
- The fuse block shall be protected by a 60 amp maxi fuse located at the source.
- Fuse block shall be wired battery direct.
- Fuse block shall be located in the top left interior corner.
- Two (2) 12 VDC **Kussmaul USBC and USBA** dual charger port(s) shall be provided in cabinet with dust cover. **Located on the top of the sliding desk beside the outlet bar.**
- Power port shall be wired battery direct.
- Power port shall be located in the top ~~left interior corner.~~ **On top of the sliding desk.**
- The compartment light(s) shall be controlled by a switch actuated by the compartment door.
- Cabinet(s) shall be provided with vertically mounted shallow aluminum Shelf-Trac for specified component installation.
- There shall be two (2) adjustable shelf/shelves in the above cabinet(s). Each shelf shall have a 1.25" vertical lip at front to contain items while vehicle is in motion.
- One (1) OnScene Access white LED, full height compartment light, vertically mounted.

CHASSIS SUPPLIED EMS CABINETS - LOWER DRIVER & OFFICER

- **ADD** Cargo netting of 1" - 2" nylon webbing shall be provided over cabinet opening with automotive seatbelt style latches.
- The compartment light(s) shall be controlled by a latching, black rocker switch with amber indicator light. The switch shall be labeled as "COMPARTMENT LIGHTS" with a black and chrome label bezel.

CAB MISCELLANEOUS EQUIPMENT

The following items shall be provided in cab as follows;

- **Two (2) OnScene Solutions red/white 8" led rough service lights above desk on inboard side walls of cabinets. With three (3) way switching located at on lower side walls of the cabinets.**

CAB EXTERIOR COMPARTMENT MODIFICATIONS

The following cab compartments shall be modified as follows;

EMS COMPARTMENT EQUIPMENT

The cab provided streetside EMS compartment shall be provided with the following:

- **Add stainless steel scuff plates around compartment openings with tightly mitered seams. (Spartan Chassis Option has 1/8" - 1/4" Gaps at seams between the Stainless Steel)**
- **Add rubberized webbing as a door check to prevent the door from opening into the Cab Entry door and/or Grab Handle. Strap should be long enough to keep the door approximately 6" away from grab handle. Strap shall be bolstered with square aluminum plates and be wrapped around one of the plates (see Cab Entry Door check straps).**

EMS COMPARTMENT EQUIPMENT

The cab provided curbside EMS compartment shall be provided with the following:

- **Add stainless steel scuff plates around compartment openings with tightly mitered seams. (Spartan Chassis Option has 1/8" - 1/4" Gaps at seams between the Stainless Steel)**
- **Add rubberized webbing as a door check to prevent the door from opening into the Cab Entry door and/or Grab Handle. Strap should be long enough to keep the door approximately 6" away from grab handle. Strap shall be bolstered with square aluminum plates and be wrapped around one of the plates (see Cab Entry Door check straps).**

STREETSIDE FUEL FILL

There shall be one (1) fuel fill door located in the streetside exterior wheel well panel, behind the rear axle. The fill door shall be fabricated from brushed stainless steel **and painted job color**.

There shall be a permanent label with the text "DIESEL FUEL ONLY" located adjacent to the fuel fill access.

DEF FLUID FILL

The DEF fluid fill shall be as supplied by commercial cab/chassis manufacturer.

ELECTRONIC SIREN

One (1) Whelen model **295HFSA7** electronic siren control with selectable 100 or 200 watt output, dual function, with removable microphone, and California Title 13 compliant shall be provided and installed in cab within easy reach of Driver. Siren power shall be wired through the master warning light switch.

- **Mount remote head in pod housing the Transmission Shift Pad.**

The specified siren functions shall be controlled by siren mounted switches.

BODY DESIGN

The importance of public safety associated with emergency vehicles requires that the construction of this vehicle meet the following specifications. These specifications are written to establish the minimum level of quality and design. All Bidders shall be required to meet these minimum requirements.

It is the intent of these specifications to fully describe the requirements for a custom built emergency type vehicle. In order to extend the expected service life of this vehicle, the body module shall be removable from the chassis frame and be capable of being installed on a new chassis.

The sheet metal material requirements, including alloy and material thickness, throughout the specifications are considered to be a minimum. Since such materials are available to all Manufacturers, the material specifications shall be strictly adhered to.

The fabrication of the body shall be formed sheet metal. Formed components shall allow the Fresno Fire Department to have the body repaired locally in the case where any object has struck the body and caused damage. The use of proprietary extrusions will prevent the Fresno Fire Department from such repair and shall NOT be used. All fabricated body components to be cut by a laser or water-jet for superior cut edge quality.

Following construction of the subframe, which supports the apparatus body, the sheet metal portion of the body shall be built directly on the subframe. The joining of the subframe and body shall be of a welded integral construction.

The sheet metal fabrication of the body shall be performed using inert gas continuous feed welders only. The entire body shall be welded construction. The use of pop rivets in any portion of structural construction may allow premature failure of the body structure. Therefore, pop rivets shall NOT be used in the construction of the structural portions of the body. This includes side body sheets, inner panels of compartment doors, and any other structural portions of the body.

EXTERIOR ALUMINUM BODY

The fabrication of the body shall be constructed from aluminum 3003H-14 alloy smooth plate. This shall include compartment front panel, vertical side sheets, side upper rollover panels, rear panels and compartment door frames.

The body compartment floors and exterior panels shall be constructed with not less than 3/16" (.187) aluminum 3003H-14 smooth plate. Interior compartment dividing walls shall be constructed with not less than 1/8" (.125) aluminum 3003H-14 smooth plate. Lighter gauge sheet metal will not be acceptable in these areas.

The door side frame openings shall be formed "C" channel design. An electrical wiring conduit raceway running the full length of exterior compartments shall be provided. This raceway shall contain all 12 volt wiring running to the rear of the apparatus, permitting easy accessibility to wiring.

Individual compartment modules, with dead air space voids between compartments, shall not be an acceptable method of compartment construction.

The compartments shall be an integral part of the body construction. Compartment floors from front of body to ahead of rear axle, also from rear axle to rear of body shall be single one-piece sections. Compartment floors shall be preformed, then positioned in body and welded into final position.

Compartment floors shall have a "sweep-out" design with door opening threshold positioned lower than compartment floor, permitting easy cleaning of compartments. Angles, lips, or door moldings are not acceptable in the base of

compartment door opening. One-way rubber drain valves shall be provided in compartment floors so that a water hose may be used to flush-out compartment area.

All exterior seams in sheet metal below frame, and around the rear wheel well area shall be welded and caulked to prevent moisture from entering the compartments. All other interior seams and corners shall be sealed with silicone based caulk prior to painting.

Only stainless steel bolts, nuts, sheet metal screws and/or aluminum screws shall be used in mounting exterior trim, hardware and equipment.

Exterior compartments shall have louvers in lower back wall of compartment for ventilation.

WALKWAY/ROOF COMPARTMENT SUPPORT

The upper body floor structure shall be integral with the body sheet metal construction and shall be an all welded assembly. Bolted or glued assemblies shall not be accepted, .

All seams in roof material shall be fully and continuously welded to prevent entry of moisture.

There shall be a total of four (4) 2" x 2" x 1/4" 6061-T6 alloy aluminum "C" channels running the length of body, two (2) on each outboard side. These "C" channels shall be used for roof support and in addition shall be used for mounting of any specified reels. This open "C" channel design along with special reel mounting clips allows for a universal location of any specified reels within each compartment.

In between the two (2) center "C" channels running the length of body shall be 2" x 2" x 1/4" 6061-T6 alloy aluminum tubing running perpendicular to walkway and welded in place on approximate 16" centers to support roof and/or walkway structure specified. Spacing greater than 16" that can allow oil canning of walkway shall not be allowed, .

A 2" formed radius shall be provided along the body sides and utilized as a wiring trough. The use of aluminum extrusions in this area shall not be acceptable, .

BODY SUBFRAME

The chassis frame rails shall be fitted with 1/4" custom extruded UHMW polyethylene rail cap to isolate the body frame members from direct contact with chassis frame rails.

The body subframe shall be constructed from 6061T6 aluminum alloy tubing. Subframe shall consist of two (2) 2" x 6" x 1/4" aluminum tubes, the same width as the chassis frame rails, NO EXCEPTION. Welded to this tubing shall be cross members of 2" x 6" x 1/4" aluminum. These cross members shall extend the full width of the body to support the compartments. Cross members shall be located at front and rear of the body, below compartment divider walls, and in front and rear of wheel well opening. Additional aluminum cross members shall be located on 16" centers, or as necessary to support walkway or heavy equipment.

To form the frame, the tubing shall be beveled and welded at each joint using 5356 aluminum alloy welding wire.

BODY MOUNTING

The body subframe shall be fastened to the chassis frame with six (6) spring loaded body mounts. Each mount shall be configured using a two-piece encapsulated slide bracket. The two (2) brackets shall be fabricated of heavy duty 1/4" thick steel and shall have a powder coat finish to prevent any corrosion. Each mounting assembly shall utilize two (2) 3/4" diameter x 6" long grade 8 bolts and two (2) heavy duty springs. The assembly design shall allow the body and subframe to act as one (1) component, separate from the chassis. As the chassis frame twists under driving conditions, the spring mounting system shall eliminate any stress from being transferred into the body. The spring loaded body mounts shall also prevent frame side rail or body damage caused by unevenly distributed stress and strains due to load and chassis movement.

Body mountings that do not allow relief from chassis movement will not be acceptable.

12" REAR STEP BUMPER

The full width rear bumper shall be constructed from 2" x 2" x 1/4" aluminum tubing frame and covered with 3/16" NFPA compliant aluminum tread plate. The bumper shall extend from the rear vertical body panel 12" and provide a rear step with a minimum of 1/2" space at body for water drainage.

- **Rear bumper compartments approx. 12"t x 12"d x 24"w shall be install on top of bumper outboard of center staircase. (ref. Charlotte 1065-1066)**
 - **Exterior of compartment shall be painted job color, top lid/door will be Treadplate with jeep latch, stainless steel hinge and a gas strut stay.**
 - **Rear face of compartment shall have chevron overlays matching rear body chevron.**

Rear bumper shall be provided with one (1) 4.75" aluminum Grip-Strut insert(s) **in the center part of bumper (Stairway area)** for improved slip resistance.

REAR TOW EYES

There shall be two (2) heavy duty rear mounted tow eyes securely attached to the chassis frame and mounted above the rear bumper. The tow eyes shall be fabricated from 1" thick steel plate with a 3" diameter opening. Tow eyes shall have a **RED wet paint** finish.

GROUND LIGHTS

There shall be two (2) OnScene 8" Access white LED lights installed below bumper capable of providing illumination at a minimum level of 2 fc (20 lx) on ground areas within 30 in. (800 mm) of the edge of the vehicle in areas designed for personnel to climb onto or descend from the vehicle to the ground level.

Lighting shall be switchable but activated automatically when the vehicle park brake is set.

WHEEL WELL EXTERIOR PANEL

The exterior panel of the body wheel well enclosure shall be constructed from 3/16" smooth aluminum panels.

STAINLESS STEEL BODY FENDERETTES

The body wheel well openings shall be provided with round radius, polished stainless steel fenderettes. The fenderettes shall be bolted and easily replaceable if damaged. The fenderettes shall be installed using nylon washers to space them slightly away from the body to reduce buildup of moisture and/or debris.

WHEEL WELL LINERS

The wheel wells shall be provided with an easily removable polymer, circular inner fender liner. The inner liner shall be bolted to the wheel well with stainless steel bolts and spaced away from the wheel well so the liner will not accumulate dirt or water.

SCBA CYLINDER COMPARTMENTS

There shall be five (5) SCBA cylinder storage compartments located, three (3) on curbside, and two (2) on streetside of rear tandem wheel well area.

The outer compartments shall have a painted aluminum door assembly with a positive catch latch. Door shall be painted primary lower body color. Each compartment shall allow the storage of one (1) SCBA cylinder or a fire extinguisher up to 8" in diameter x 22" deep.

The center compartments (between tandems axles) shall have a drop-down painted aluminum door with a positive catch latch and stainless steel hinge. Door shall be painted primary lower body color. This compartment shall allow for the storage of three (3) SCBA cylinders or a fire extinguishers up to 8" in diameter x 22" deep.

The doors shall activate the "Hazard Warning Light" in the cab when not in the closed position.

REAR BODY HANDRAILS

There shall be two (2) Hansen International 24" x 1-1/8" vertical handrails on rear body. Handrails shall be NFPA compliant formed from anodized aluminum with knurled anti-slip finish.

Each handrail shall be back-lit with a Safetylite, 12 VDC white LED light tube. Lights shall be activated with headlight and park brake set circuits.

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

WHEEL WELL STEP

Between the tandem rear tires (one each side) shall be a heavy duty fabricated single foot step to assist in access to wheel well compartments. Step surface to be fabricated of non-slip aluminum grating with structure to body sub-frame that resist flexing or bending under the weight of single person.

There shall be a 24" vertical handrail each side of body between wheel well compartments.

BODY PAINT SPECIFICATIONS

BODY PAINT PREPARATION

After the body and components have been fabricated they shall be disassembled so when vehicle is complete there shall be finish paint beneath the removable components. The body shall be removed from chassis during the paint process to insure proper paint coverage. The body and components shall be metal finished as follows to provide a superior substrate for painting.

The exterior (and interior, if painted) body shall undergo a thorough cleaning process starting with a biodegradable phosphoric acid solution to begin the etching process followed by a complete clear water rinse. The next step shall consist of a chemical conversion coating applied to seal the metal substrate and become part of the metal surface for greater film adhesion.

All bright metal fittings, if unavailable in stainless steel or polished aluminum, shall be chrome plated. Iron fittings shall be copper under plated prior to chrome plating.

PAINT PROCESS

The paint process shall follow the strict standards set forth by PPG Industries guidelines. Painters applying PPG products will be PPG Certified Commercial Technicians, and re-certified every two (2) years. The body shall go through the following paint process;

- 1) Clean bare metal with a wax and grease remover using low lint rags.
- 2) Inspect, straighten, and hammer high points, grind all seams, sharp edges, and welds. DA sand entire paintable surfaces using 24-180 grit dry paper. Plastic fill all low spots and DA sand fill areas using 36-180 grit dry paper. Apply pinhole filler and DA sand areas using 80-180 grit dry paper.
- 3) Re-clean bare metal using a wax and grease remover and low lint rags.
- 4) Within 24 hours, a PPG Delfleet® epoxy color primer with proper hardener for corrosion resistance using a pressure pot spray gun and applying 2-5 full wet coats or 1.5-8.0 dry mils max. achieving full hiding and allow to air dry 60 minutes @ 70°F or bake for 45 minutes @ 140°F degree.
- 5) Inspect, putty fill, and dry guild coat entire body surface and DA sand using 180-400 grit dry paper.
- 6) Re-clean bare metal using a wax and grease remover using low lint rags.
- 7) A PPG Delfleet® primer sealer with proper hardener and thinner shall be sprayed using a pressure pot spray gun and applying 1 full wet coat or 1.0-2.0 dry mils achieving full hiding and allow to flash off in spray booth for minimum of 60 minutes @ 70°F.
- 8) A PPG Delfleet® FBCH basecoat (color) with proper hardener and dry additive shall then be sprayed using a pressure pot set @ 45-60 PSI and achieving full hiding or 1.5-2.0 wet mils and allow to flash off in spray booth 45-60 minutes before applying clearcoat.
- 9) A PPG Delfleet® clearcoat with proper hardener and thinner shall be sprayed using a pressure pot spray gun and applying 2-3 full wet coats or 5.0 wet mils for a uniform gloss and allow to flash off in spray booth 10 minutes and bake for 120-140 minutes @ 125°F (surface temp.).
- 10) After cooling, DA sand heavy orange peel or runs using 1000 grit dry sand paper and final DA sand using 1500-2000 grit dry sand paper. Wipe off all surfaces to remove dust and debris. Buff unit as needed using 3M rubbing compound and a white wool pad and inspect until all sand scratches are removed.
- 11) Polish as needed using 3M Perfect-It-Polish and a black foam pad, repeat as necessary and inspect until all sand scratches are removed.

PAINT - ENVIRONMENTAL IMPACT

The contractor shall meet or exceed their current State regulations concerning paint operations pollution control and shall include measures to protect the atmosphere, water and soil. PPG Delfleet® Evolution paint shall be free of all heavy metal (lead & chromate) components. Paint emissions from sanding and painting shall be filtered and collected. All paint wastes shall be disposed of in an environmentally safe manner. Solvents used in cleanup operations shall be collected, sent off-site for distillation and returned for reuse.

FASTENERS

Prior to the assembly and reinstallation of exterior components; i.e. warning and DOT lights, handrails, steps, door hardware, and miscellaneous items, a Mylar isolation tape, or gasket shall be used to prevent damage to the finish painted surface. These components shall be fastened to body using either a plastic insert into body metal with stainless steel screws or zinc coated nut-surts into body surface using stainless steel bolts to prevent corrosion from dissimilar metals.

ELECTROLYSIS CORROSION CONTROL

The vehicle shall be assembled using ECK brand or similar corrosion control compound on all high corrosion potential areas.

ECK protects aluminum and stainless steel against electrolytic reaction, isolates dissimilar metals and gives bedding protection for hardware and fasteners. ECK contains anti-seizing lubricant for threads. ECK is dielectric and perfect for use with electrical connectors.

PAINT FINISH - SINGLE COLOR

The body shall be painted with a single color of PPG Delfleet® Evolution per Fresno Fire Department approved paint spray out provided.

- Paint Color: Match cab/chassis supplied paint color.

BODY UNDERCOATING

The entire underside of body shall be sprayed with black automotive undercoating. Undercoating shall cover all areas underside of body and wheel well area to help prevent corrosion under the vehicle.

UNDERCOAT WARRANTY

The body undercoating shall have a warranty provided by the manufacturer for the lifetime of the vehicle or twenty (20) years, whichever occurs first. The warranty shall be transferable between vehicle owners. Should the undercoating material applied to the underside of the body and wheel wells of the vehicle ever flake off, peel, chip or crack due to drying out, the damaged area shall be re-sprayed without charge to the vehicle owner.

PAINT WARRANTY

The vehicle shall be provided with a ten (10) year non-prorated warranty to the original owner. Warranty is provided by PPG Inc. A warranty sheet with all conditions and maintenance procedures shall be provided with the delivered vehicle. **Pro-rated warranties will not be acceptable.**

COMPARTMENT INTERIOR FINISH

The interior of all exterior body compartments shall be a "Maintenance Free" smooth unpainted finish. All body seams shall be finished with a caulk sealant for both appearance and moisture protection.

REFLECTIVE STRIPE REQUIREMENTS

Material

All retroreflective materials shall conform to the requirements of ASTM D4956, *Standard Specification for Retroreflective Sheeting for Traffic Control*, Section 6.1.1 for Type I Sheeting.

All retroreflective materials used that are colors not listed in ASTM D4956, Section 6.1.1, shall have a minimum coefficient of retro-reflection of 10 with observation angle of 0.2 degrees and entrance angle of -4 degrees.

Any printed or processed retroreflective film construction used shall conform to the standards required of an integral colored film as specified in ASTM D4956, Section 6.1.1.

Minimum Requirements

A retroreflective stripe(s) shall be affixed to at least 50 percent of the cab and body length on each side, excluding the pump panel areas, and at least 25 percent of the width of the front of the vehicle, not including mirrors or other protrusions.

The stripe or combination of stripes shall be a minimum of 4 in. (100 mm) in total width.

The 4 in. (100 mm) wide stripe or combination of stripes shall be permitted to be interrupted by objects (i.e., receptacles, cracks between slats in roll up doors) provided the full stripe is seen as conspicuous when approaching the apparatus.

A graphic design shall be permitted to replace all or part of the required striping material if the design or combination thereof covers at least the same perimeter length(s).

GRAPHICS PROOF (Match signed approval)

A color graphics proof of the reflective striping layout shall be provided for approval by Fresno Fire Department prior to installation. The graphics proof shall be submitted to Fresno Fire Department on 8.5" x 11" sheets with front, sides, rear and plan views, each on one (1) sheet. In addition if there is any special art work an additional sheet shall be provided showing all details. **Note:** The graphics color proof may not reflect the correct paint break lines on the chassis and body please refer to the paint section of your specifications for correct paint break lines.

REFLECTIVE STRIPE - CAB SIDE

The reflective stripe material shall be 4" wide, 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

There shall be a 1" Scotchlite reflective stripe located 1" above and a second 1" Scotchlite reflective stripe located 1" below the main stripe.

- This reflective stripe shall be white in color.

REFLECTIVE STRIPE - CAB FRONT

The reflective stripe material shall be 4" wide, 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

There shall be a 1" Scotchlite reflective stripe located 1" above and a second 1" Scotchlite reflective stripe located 1" below the main stripe.

- This reflective stripe shall be white in color.

CHEVRON STRIPE - CAB BUMPER

A reflective stripe shall be affixed to the front of cab. The stripe or combination of stripes shall be a minimum of 4 in. (100 mm) in total width.

The approximate 10" wide Chevron retroreflective stripe shall be affixed to at least 25 percent of the width of the front of the apparatus with retroreflective striping in a chevron pattern sloping downward and away from the centerline of the vehicle at an angle of 45 degrees. Each stripe shall be 6" width. Chevron panels shall have a 3M UV over laminate to protect from UV rays, scene damage, and everyday use. Chevron panels shall have a minimum 10 year warranty for material failure, and colorfastness.

- The stripe material shall be 3M Scotchlite 680 series graphic film.

All retroreflective materials required shall conform to the requirements of ASTM D 4956, *Standard Specification for Retroreflective Sheeting for Traffic Control*, Section 6.1.1 for Type I Sheeting.

~~This reflective chevron stripe shall be red in color to provide a ghosted effect.~~

REFLECTIVE STRIPE - CAB DOOR INTERIOR

Any door of the apparatus designed to allow persons to enter or exit the apparatus shall have at least 96 in.2 (62,000 mm2) of retroreflective material affixed to the inside of the door.

The stripe material shall be 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

REFLECTIVE STRIPE - BODY SIDES

The reflective stripe material shall be 4" wide, 3M Scotchlite 680 series graphic film.

- This reflective stripe shall be white in color.

There shall be a 1" Scotchlite reflective stripe located 1" above and a second 1" Scotchlite reflective stripe located 1" below the main stripe.

- This reflective stripe shall be white in color.

The stripe shall remain in a straight line from the front of the front of cab to the rear body.

CHEVRON REFLECTIVE STRIPE - REAR CENTER/SIDE PANELS

At least 50 percent of the rear-facing vertical surfaces, visible from the rear of the apparatus, excluding any pump panel areas not covered by a door, shall be equipped with retroreflective striping in a chevron pattern sloping downward and away from the centerline of the vehicle at an angle of 45 degrees. Each stripe shall be 6" width.

The rear side panels and center of the body shall have a chevron style reflective stripe, extending from bumper to full body height. Chevron panels shall have a 3M UV over laminate to protect from UV rays, scene damage, and everyday use. Chevron panels shall have a minimum 10 year warranty for material failure, and colorfastness.

The stripe material shall be 3M Diamond Grade.

This reflective chevron stripe shall alternate red and fluorescent yellow-green in color.

LETTERING

GRAPHICS PROOF

A color graphics proof of the lettering layout shall be provided for approval by Fresno Fire Department prior to installation. The graphics proof shall be submitted to Fresno Fire Department on 8.5" x 11" sheets with front, sides, rear and plan views, each on one (1) sheet. In addition if there is any special art work an additional sheet shall be provided showing all details.

The following lettering shall be provided and installed on the completed unit as follows;

SIDE CAB DOOR LETTERING

There shall be four (4) 6" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be white in color. **"11"**

UPPER BODY SIDE LETTERING

There shall be twenty (20) 10" high SuperGold letters furnished and installed on the vehicle. Lettering shall have a clear 3M UV Protective Over Laminate applied before installation.

"FRESNO FIRE"

There shall be twenty two (22) 5" high SuperGold letters furnished and installed on the vehicle. Lettering shall have a clear 3M UV Protective Over Laminate applied before installation.

"HEAVY RESCUE"

REAR BODY LETTERING

FRONT OF CAB LETTERING

There shall be six (6) 3" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be white in color. **"FRESNO"**

There shall be six (6) 6" high reflective letters furnished and installed on the vehicle.

- This reflective lettering shall be red in color. **"RESCUE"**

SUPPLIED DECALS

The bidder shall install four (4) Fresno Fire Department supplied decal(s) on the vehicle, located on the.

EXTERIOR COMPARTMENT DOORS

ROLL-UP DOOR CONSTRUCTION - ROBINSON (ROM)

The vehicle shall be equipped with R•O•M Series IV roll-up exterior compartment doors. The R•O•M roll-up doors shall be complete with the following features;

Each shutter slat, track, bottom rail, and drip rail shall be constructed from anodized 6063 T6 aluminum. Shutter slats shall feature a double wall extrusion 0.315" thick with a concave interior surface to minimize loose equipment jamming the shutter door closed. Shutter slats shall feature an interlocking end shoe to prevent side to side binding of the shutter door during operation. Slat must have interlocking joints with an inverted locking flange. Slat inner seal shall be a one piece PVC extrusion; seal design will be such to prevent metal to metal contact while minimizing dirt and water from entering the compartment.

Shutter door track shall be one piece design with integral overlapping flange to provide a clean finished look without the need of caulk. Door track shall feature an extruded Santoprene rubber double lip low profile side seal with a silicone co-extruded back to reduce friction during shutter operation.

Shutter bottom rail shall be a one piece double wall extrusion with integrated finger pull. Finger pull shall be curved upward with a linear striated surface to improve operator grip while operating the shutter door. Bottom rail shall have a smooth contoured interior surface to prevent loose equipment from jamming the shutter door. Bottom rail seal shall be made from Santoprene; it will be a double "V" seal to prevent water and debris from entering compartment. Bottom rail lift bar shall be a one piece "D" shaped aluminum extrusion with linear striations to improve operator grip during operation. Lift bar shall have a wall thickness of 0.125". Lift bar shall be supported by no less than two pivot blocks; pivot blocks shall be constructed from Type 66 Glass filled reinforced nylon for superior strength. Bottom rail end blocks shall have incorporated drain holes which will allow any moisture that collects inside the extrusion to drain out.

Shutter door shall have an enclosed counter balance system. Counter balance system shall be 4" in diameter and held in place by two (2) heavy duty 18 gauge zinc plated plates. Counter balance system shall have two (2) over-molded rubber guide wheels to provide a smooth transition from vertical track to counter balance system; no foam material of any kind shall be permitted or used in this area.

The R•O•M Series IV roll-up compartment doors shall be free of manufacturing defects for a period of up to 7 years from date of purchase provided doors are used under conditions of normal use, regular periodic maintenance and service is performed, and doors were installed in accordance with R•O•M's instructions.

ROM DOOR BOTTOM RAIL

All exterior compartment doors shall have the standard 3.0" tall bottom rail extrusion for easy one (1) hand opening and closing.

BODY HEIGHT MEASUREMENTS

The vertical body dimensions shall be as follows:

AHEAD OF REAR AXLE

	<u>Description</u>	<u>Dimension</u>
A	Bottom of Subframe to Top of Body	88.7"
B	Bottom of Subframe to Bottom of Body	22.5"
C	Total Body Height	111.2"
D	Compartment Height Above Frame	48.0"
E	Compartment Height Below Frame	25.0"
F	Vertical Door Opening:	

-with roll-up door	65.0"
-with hinged door	68.5"

ABOVE REAR AXLE

	<u>Description</u>	<u>Dimension</u>
G	Vertical Door Opening - Above Rear Wheel	
	-with roll-up door	34.0"
	-with hinged door	37.5"

BEHIND REAR AXLE

	<u>Description</u>	<u>Dimension</u>
H	Bottom of Subframe to Bottom of Body	20.0"
I	Compartment Height Above Frame	48.0"
J	Compartment Height Below Frame	22.5"
K	Vertical Door Opening:	
	-with roll-up door	62.0"
	-with hinged door	65.5"

GENERAL

	<u>Description</u>	<u>Dimension</u>
L	Top of Body to Bottom of Drip Rail	38.5"

(Dimensions are approximate and subject to change during construction or design process.)

SEVEN (7) UPPER BODY COMPARTMENTS (OPEN)

The forward transverse compartment shall be 90.0" long x 27.0" wide x 33.5" deep. There shall be six (6) compartments parallel to the sides of the body, three (3) on each side. Each of these compartments shall be 74.0" long x 28.0" wide x 33.5" deep. The side compartments shall be open under each door sill to allow for long equipment. Each compartment shall be integral with the body construction, and will not be bolted or add-on modules. The outside walls of each compartment will be double walled to prevent equipment from denting the outside painted surface.

Each compartment shall have a lift-up type compartment door hinged on the outboard side. Each door shall be fabricated from 3/16" aluminum tread plate. Each door shall have two (2) pneumatic type cylinders, one (1) at each end, attached to cast aluminum brackets mounted to the interior surface of the door to hold the door in both the opened and closed positions. Each door shall be mounted using multiple 16" long, equally spaced, 14 gauge stainless steel hinges, with 1/4" stainless steel pin. A polyester barrier film gasket shall be placed between stainless steel hinge and the body mounting surface as necessary to prevent corrosion caused by dissimilar metals.

Each compartment door shall overlap a 2" vertical lip on the body roof to prevent entry of moisture and sealed with automotive type rubber molding to provide a weather resistant seal.

Each roof compartment door shall have a chrome 7" handle bolted to center of each door.

Each compartment shall have a 13/16" drain hole located in floor of compartment with a 1" flexible drain tube that terminates below body.

Each compartment shall have a horizontally mounted OnScene Solutions LED light on the underside of the door. The light and NFPA door ajar system shall be automatically activated by an individual switch per compartment.

- **Forward, curbside compartment shall be sealed from all other compartments with no wire raceway vents and shall include two (2) chrome cowl vents (ambulance/boat bilge).**
- **Curbside fwd fuel compartment shall have four (4) plastic trays, one (1) stake holder, one (1) pipe module, and one (1) double stack picket module per sales drawing detail.**

TRANSVERSE ROOF COMPARTMENT - SHELF TRAC

The transverse front or rear roof compartment shall be provided with side wall horizontally mounted aluminum Shelf-Trac welded to the walls for vertical partition installation and adjustability.

- **Addition Shelf Trac will be install in a two (2) strip per compartment lid layout; Installed one (1) on either side of the support channel on the underside of lid.**

ROOF COMPARTMENT - VERTICAL PARTITION

There shall be one (1) vertical partition(s) provided in the roof compartment(s). The partition(s) shall be used to retain or hold equipment in place during travel. Each partition shall be fabricated from 3/16" smooth aluminum and bolted to specified Shelf-Trac for ease of adjustment.

SIDE ROOF COMPARTMENT - SHELF TRAC

The upper body side compartments shall be provided with horizontally mounted aluminum Shelf-Trac welded to the walls for vertical partition installation and adjustability.

- **Addition Shelf Trac will be install in a two (2) strip per compartment lid layout; Installed one (1) on either side of the support channel on the underside of lid.**

ROOF COMPARTMENT - VERTICAL PARTITION

There shall be six (6) vertical partition(s) provided in the roof compartment(s). The partition(s) shall be used to retain or hold equipment in place during travel. Each partition shall be fabricated from 3/16" smooth aluminum and bolted to specified Shelf-Trac for ease of adjustment.

UPPER BODY WALKWAY

A 34" wide, upper body walkway shall be provided at the center of body and recessed into the roof structure. The walkway shall be fabricated from NFPA compliant 3/16" aluminum tread plate with continuously welded cross seams to prevent moisture penetration into apparatus body, No Exceptions. The walkway shall be supported with 2" x 2" tubing on 14" - 22" centers.

13/16" drains shall be installed at front of walkway connected to 1" flexible drain tubes that will terminate below the body.

WALKWAY/STEP LIGHTS

There shall be four (4) OnScene Solutions Rough-Service 9" LED lights provided to illuminate the walkway or step area.

Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment.

Lighting shall provide illumination at a minimum level of 2 fc (20 lx) on all work surfaces, steps, and walkways. Lighting shall be switchable but activated automatically when the vehicle park brake is set.

ROOF ACCESS STAIRWAY

The rear of the body shall be provided with a minimum 34" wide roof access stairway recessed into the side rear compartments. Stairs treads shall be 9 1/2" minimum depth and formed from 3/16" NFPA compliant aluminum tread plate with uniformed riser height design. Stair treads will be continuously welded into side walls. Bolt-in tread design will not be acceptable.

Roll-out ladder design requiring set-up time and 8 plus feet behind apparatus or vertical ladders that do not allow firefighter to safely ascend or descend with equipment will not be acceptable.

STAIRWAY HANDRAILS

There shall be two (2) handrails provided, one (1) on each side wall of recessed center stairway providing three-points of contact at all times for safer access to roof compartments. The handrails shall be angled for optimum use during ingress or egress of the upper walkway area.

Handrails shall be NFPA compliant 1-1/4" knurled 304 stainless steel with welded end stanchions.

WALKWAY/STEP LIGHTS

There shall be two (2) OnScene Solutions Rough-Service 9" LED lights provided to illuminate the walkway or step area.

Each light shall be mounted in an extruded aluminum housing to protect against damage from personnel or equipment.

Lighting shall provide illumination at a minimum level of 2 fc (20 lx) on all work surfaces, steps, and walkways. Lighting shall be switchable but activated automatically when the vehicle park brake is set.

STEP COMPARTMENT(S) - LOWER

There shall be one (1) compartment(s) located in the roof access stairway area below frame level. Each compartment shall have a horizontally hinged lift-up door. Each compartment shall be manufactured to prevent road debris, dirt and moisture from entering. Each compartment(s) shall be 33" wide x 24" high x maximum depth based on chassis mounted components and requirements for structural integrity of the body.

Each compartment shall have an OnScene LED light that shall automatically activate when the door is opened and wired to the NFPA required hazard warning light provided in the cab.

- **Portable winch storage.**
- The hinged door(s) shall have a stainless steel 6" offset bent D-ring locking handle. A gasket shall be placed between handle and door. Door latch shall be a single point latch flush mounted to exterior door panel.
- The specified portable winch shall be mounted in compartment using a heavy duty "U" shaped channel. Winch receiver tube and mounting pin shall be utilized to hold in place during travel.

STEP COMPARTMENT - UPPER

There shall be one (1) upper compartment located directly below walkway area. The compartment shall have a horizontally hinged brushed stainless steel door. The compartment shall be manufactured to prevent road debris, dirt and moisture from entering. The compartment shall be approximately 26" wide x 8" high x maximum depth available.

- **There shall be an adjustable stop at 16' for lumber storage.**
- **Ten (10) 10' pvc tubes with capped ends.**

Each Compartment shall have an OnScene LED light that shall be automatically activated when the door is opened and wired to the NFPA required hazard warning light provided in the cab.

Devices to secure specified equipment, compartment dividers, or UHMW plastic angles, or sheeting will be used for storage of specified equipment as required to prevent damage to equipment.

- The hinged door(s) shall have a stainless steel 6" offset bent D-ring locking handle. A gasket shall be placed between handle and door. Door latch shall be a single point latch flush mounted to exterior door panel.

FOLD-DOWN STEP

There shall be one (1) 30" wide fold-down step located at the bottom of the roof access stairway to reduce the distance from the ground to the first step. The step surface shall be NFPA compliant aluminum treadplate. The step shall manually fold up into the stairway with an over-center gas shock to hold step in position during travel. The step shall activate the "Hazard Warning Light" in the cab when not in the stowed position.

- **Add Grip strut insert into step.**

REAR BODY HANDRAILS

There shall be two (2) Hansen International 24" x 1-1/8" vertical handrails on rear body. Handrails shall be NFPA compliant formed from anodized aluminum with knurled anti-slip finish.

Each handrail shall be back-lit with a Safetylite, 12 VDC white LED light tube. Lights shall be activated with headlight and park brake set circuits.

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

STAIR TREAD SAFETY DELINEATION

For increased visibility and safety, the front edge of walkway at top of stairway and each step including the front edge of bumper shall have two (2) rows of 3M™ Diamond Grade™ reflective squares provided between the diamond pattern of stepping surface to delineate stair tread edges.

The squares shall be red in color.

BODY WIDTH DIMENSIONS

The body shall be 100.0" wide, and 102.0" wide at drip rails. Interior compartment depth dimensions shall be approximately:

<u>Area Description</u>	<u>Dimension</u>
Transverse above subframe	95.0"
Compartment depth below subframe	24.5"

STREETSIDE COMPARTMENT - FRONT (S1)

The interior useable compartment width shall be approximately 64.5" wide.

The compartment door opening shall be approximately 57.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be two (2) Austin Front Drawer Release (FDR) 400 lbs. slide-out tray(s) approximately 24" deep and as wide as the compartment layout or door opening permits. The FDR on front of tray will deduct 1.5" from specified depth. The tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length.

These two (2) trays will be in the right side lower part of compartment.

- The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 47" deep and as wide as the compartment layout or door opening permits located above the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 ½".

- Vertical partition(s) shall be provided on slide-out tray base dividing the tray into left and right sides. Each vertical partition shall be horizontally adjustable; mounted on aluminum Shelf Trac on tray floor. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.

Install to equally divide fore and aft portions of the tray.

- The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) OnScene Solutions 83 series aluminum tray base with 70% extension, and rating of 1,000 lbs. Slide-out tray(s) base shall be full width (street/curb) and as wide as the compartment layout or door opening permits, capable of extending out either side of the body located above the level of the chassis frame rails. Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed, 40% extended and 70% extended positions. Each tray top shall be fabricated from 3/16" 3003 aluminum sheet shall have welded corners to form a box type tray surface with an internal depth of approximately 3 1/2".

- The above component(s) shall have a smooth un-painted finish.

- There shall be one (1) transverse module fabricated from 3/16" (.188) 3003H-14 aluminum alloy smooth sheet. The module will be designed for the following long tools and equipment:

- One (1) Fresno Fire Department supplied stokes basket(s). ~~Manufacturer, model number and dimensions of the stokes basket(s) shall be provided during the pre-construction meeting.~~
- **Cascade Rescue 2 piece, 85"l x 27"w x 9"t**

- There shall be one (1) OnScene Solutions Velcro cargo straps provided to secure the stored equipment.

- There shall be three (3) Zico 1000 series KD-UH walkaway type SCBA air pack bracket(s) with high cycle coated spring clips and angled foot plate (no CRS strap inc.).
- **To be installed, on the front of the vertical partition as shown in drawing.**
- The floor of the compartment above the frame rails shall be extended to the interior edge of the door. The floor shall have a 2" vertical lip and a 1" return to increase strength.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- The controls for the specified light tower(s).
- The controls for the specified awning(s).
- There shall be one (1) 120 VAC outlet(s) located ~~in compartment on the forward lower section rearward~~ wall.
 - The outlet receptacle(s) shall be 20 amp, straight-blade (NEMA 5-20R).
 - Outlet(s) shall be powered by both the on-board generator and shore power system through a relay system.
- The 12 volt electrical distribution panel shall be located in the front lower compartment.
- **Install Blue Sea Charger in or above 12V Panel.**
- There shall be one (1) underbody storage compartment provided and installed below the compartment(s) ahead or rear wheels. Storage compartment shall be constructed from 1/8" aluminum 3003H-14 alloy smooth plate and shall be approximately **7"** high x 24" deep x **100" wide**. The compartment shall be reinforced to prevent flexing or damage

when loaded. Compartment shall have a hinged drop down compartment door constructed of 1/8" aluminum . Door shall have a full width stainless steel piano hinge with a 1/4" stainless steel pin. Latching of the door shall be with a D-ring 1/4 turn latch with slam latche(s) for holding compartment door closed.

- **Compartment and door shall be powder coated 60% gloss black.**

STREETSIDE COMPARTMENT - AHEAD OF REAR WHEELS (S2)

The interior useable compartment width shall be approximately 64.5" wide.

The compartment door opening shall be approximately 57.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be two (2) adjustable shelf/shelves approximately 70" deep. Each shelf shall be fabricated from 3/16" 3003 aluminum sheet with a 2" vertical flange along the front and rear edges.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be two (2) Austin Front Drawer Release (FDR) 400 lbs. slide-out tray(s) approximately **24"** deep and as wide as the compartment layout or door opening permits. The FDR on front of tray will deduct 1.5" from specified depth. The tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length.

To be installed over floor mounted tool chest, one tray immediately above the other.

- The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 47" deep and as wide as the compartment layout or door opening permits located above

the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 1/2".

- **Top Tray will be a poly tray compartmentalized for power tool storage (see sales drawing and confirm via 3D model with customer).**
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) bolt-in vertical compartment partition(s) provided dividing the compartment into fore and aft sides. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.

To be supplied and installed approximately 12" forward of aft wall of compartment, same width as vertical exhaust plenum space.

- The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) transverse module fabricated from 3/16" (.188) 3003H-14 aluminum alloy smooth sheet. The module will be designed for the following long tools and equipment:
 - Two (2) Fresno Fire Department supplied **Dewalt Miter Saw Table**.
 - One (1) Fresno Fire Department supplied **Skedco** rescue tri-pod.
 - Two (2) Fresno Fire Department supplied **pass load devices at end of Little Giant Overhaul** ladder(s).
 - **Module shall have a 1" lip or block to retain items.**
- There shall be one (1) module fabricated from 3/16" (.188) 3003H-14 aluminum alloy smooth sheet. The module will be designed for the following long tools and equipment:
 - Two (2) Fresno Fire Department supplied long tool(s) shall be installed after delivery. **Hi-Lift Jack**
- One (1) Custom C-Tech 50"W X 20.82"H X 22.5"D tool chest shall be supplied and installed in the lower compartment below the extended floor.
C-Tech will be raw aluminum/ or painted Silver.
- The floor of the compartment above the frame rails shall be extended to the interior edge of the door. The floor shall have a 2" vertical lip and a 1" return to increase strength.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- There shall be one (1) 120 VAC outlet(s) located in compartment on the ~~forward~~ **rear, upper right** wall **below extended floor**.
 - The outlet receptacle(s) shall be 20 amp, straight-blade (NEMA 5-20R).
 - Outlet(s) shall be powered by both the on-board generator and shore power system through a relay system.

- One (1) OnScene 8" Access white LED ground light(s) shall be provided below the body. Light(s) shall be switchable but activated automatically when the park brake is set.
- Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

STREETSIDE COMPARTMENT - ABOVE REAR WHEELS (S3)

The interior useable compartment width shall be approximately 56.5" wide.

The compartment door opening shall be approximately 49.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 47" deep and as wide as the compartment layout or door opening permits located above the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 ½".
 - **Two (2)** Vertical partition(s) shall be provided on slide-out tray base dividing the tray into left and right sides. Each vertical partition shall be horizontally adjustable; mounted on aluminum Shelf Trac on tray floor. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.
 - The above component(s) shall have a smooth un-painted finish.

- There shall be a transverse plywood storage module for full 4' x 8' sheets of plywood without altering the size. The module shall be fabricated from 3/16" (.188) 3003H-14 aluminum alloy sheet and shall have hinged retainer doors at each end to hold plywood in place. Storage module shall hold the following sheets of plywood;
 - Eight (8) Fresno Fire Department supplied sheets of 4' x 8' x 1" sheets of plywood.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

STREETSIDE COMPARTMENT - ABOVE REAR WHEELS (S4)

The interior useable compartment width shall be approximately 56.5" wide.

The compartment door opening shall be approximately 49.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) bolt-in vertical compartment partition(s) provided dividing the compartment into fore and aft sides. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) storage module(s) for air bags. The module shall be fabricated from 1/8" (.125) 3003H-14 aluminum alloy sheet. Circular notches shall be provided along the front edge to ease the access to the air bags. Each bay shall be sized to hold the air bag and a matching piece of 1/2" plywood (plywood not provided).

Module shall be designed to store the following air bags;

- **One (1) KPI-3 - 6 x 12**
- **Two (2) KPI-17 - 15 x 21**
- **Two (2) KPI-28 - 20 x 26**
- **Two (2) KPI-32 - 24 x 24**
- **One (1) KPI-55 - 32 x 32**

- **One (1) B/K low pressure Air Cushion - 32 x 32 x 2**
- **One (1) extra slot (see sales drawing).**
- There shall be two (2) OnScene Solutions Velcro cargo straps provided to secure the stored equipment.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

STREETSIDE COMPARTMENT - REAR (S5)

The interior useable compartment space shall be approximately 70.5" wide.

The compartment door opening shall be approximately 63.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) OnScene Solutions 83 series aluminum tray base with 70% extension, and rating of 1,000 lbs. Slide-out tray(s) base shall be full width (street/curb) and as wide as the compartment layout or door opening permits, capable of extending out either side of the body located above the level of the chassis frame rails. Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed, 40% extended and 70% extended positions. Each tray top shall be fabricated from 3/16" 3003 aluminum sheet shall have welded corners to form a box type tray surface with an internal depth of approximately 3 1/2".
 - Vertical partition(s) shall be provided on slide-out tray base dividing the tray into left and right sides. Each vertical partition shall be horizontally adjustable; mounted on aluminum Shelf Trac on tray floor. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.

– **Paratech Strut and Hydrafusion Mounting.**

Paratech Rescue Support System

This is a list of our current Paratech rescue support system. We will need some extra room to grow as our list of equipment continues to expand.

Quantity	Part #	Description
4	22796360	72" - 116" Acme Thread LongShore Strut 610 (Gold)
3	22796206	19" - 25" AcmeThread Strut (Gray)
3	22796200	25" - 36" AcmeThread Strut (Gray)
3	22796202	37" - 58" AcmeThread Strut (Gray)
2	22796342	24" Strut Extension (Gold)
2	22796356	48" Strut Extension (Gold)
2	22796024	24" Strut Extension (Gray)
2	22796036	36" Strut Extension (Gray)
2	22796012	12" Strut Extension (Gray)
2	22796017	6" Strut Extension (Gray)
4	22796180C	12" x 12" Hinged Base
8	22796060	6" Square Swivel Base
4	22796070	6" Square Rigid Base
4	22796025	Multi Base
4	22796270	Contour Base
2	22796035	6" Strut Converter

List provided on perfect truck form

- The above component(s) shall have a smooth un-painted finish.
- There shall be two (2) slide-out smooth aluminum vertical tool board(s) approximately 24" deep. Each tool board(s) vertical exterior edge shall have a double 90 degree formed edge to provide an easy grip handle. The top and bottom of tool board(s) shall be provided with Accuride 9300 series slide tracks. Each board shall be rated for a maximum 200 lbs. evenly distributed load. Each tool board shall utilize a pneumatic cylinder to hold the tool board in both the opened and closed positions.
 - The vertical tool board material shall be 3/16" (.188) 3003H-14 aluminum alloy sheet.
 - The above component(s) shall have a smooth un-painted finish.
 - Each tool board will be bolted to compartment floor.
- There shall be one (1) bolt-in vertical compartment partition(s) provided dividing the compartment into fore and aft sides. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.

To be mounted aft of high pressure airbag storage module.

- The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) removable plastic tool box(s) with hand holes for carrying. Each tool box shall be fabricated from ½" (.50) textured finish polypropylene sheet.
- **12" T x 8.5" W x 23" L**
 - There shall be one (1) OnScene Solutions Velcro cargo straps provided to secure the **customer supplied and installed Honda EU2000i generator(s) in a drip tray in the lower left portion of the compartment.**
- The floor of the compartment above the frame rails shall cover the area directly above the frame rails ONLY (non-extended floor).
- One (1) Hannay ECR1618-17-18 electric cable reel(s) capable of storing 200' of 10/3 electric cable. Reel(s) shall be designed to hold 110% of the capacity of cord length, with fully enclosed 45 amp, three (3) conductor collector rings. Reel(s) shall be mounted to channel structure that allows for side-to-side adjustment of reel position.
 - Power rewind control(s) shall be in a position where the operator can observe the rewinding operation and not be more than 72 in. (1830 mm) above the operator's standing position, and shall be marked with a label indicating its function and shall be guarded to prevent accidental operation.
 - A label shall be provided in a visible location adjacent to reel with following information: Current rating, Current type, Phase, Voltage, and Total cord length.
 - The cable reel shall be equipped with 200' of 10/3 SEOW black cable, a molded plastic ball clamp, and a single heavy duty L5-30 twist-lock female plug at the end.

- One (1) Akron model EJBX series, cast aluminum electrical power distribution box with gray powder coat painted finish shall be provided. The power distribution box shall meet all requirements described in NFPA 1901. The power distribution box shall include the following outlets mounted on a backlit face plate;
 - A 12" pigtail that terminates in an L5-30 configuration to match the cable on the cord reel. The outlet configuration shall include:
 - One (1) 120 VAC, L5-15 dual twist lock receptacles
 - One (1) 120 VAC, L5-15 dual twist lock receptacles
 - One (1) 120 VAC, L5-15 dual twist lock receptacles
 - One (1) 120 VAC, 5-20 duplex straight-blade receptacle
- One (1) Akron Brass model EJB-VMT aluminum treadplate vertical mounting bracket for specified power distribution box shall be provided and mounted in compartment **left of the reel**.
- The fairlead roller shall be mounted directly to the reel.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

CURBSIDE COMPARTMENT - FRONT (C1)

The interior useable compartment width shall be approximately 64.5" wide.

The compartment door opening shall be approximately 57.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be two (2) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 47" deep and as wide as the compartment layout or door opening permits located above the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 ½".
 - Vertical partition(s) shall be provided on slide-out tray base dividing the tray into left and right sides. Each vertical partition shall be horizontally adjustable; mounted on aluminum Shelf Trac on tray floor. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.

Install to equally divide fore and aft portions of the tray.
 - The above component(s) shall have a smooth un-painted finish.

- There shall be one (1) OnScene Solutions 83 series aluminum tray base with 70% extension, and rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 94" deep; capable of extending out either side of the body located above the level of the chassis frame rails. (Specified in opposite side compartment.)
- There shall be a transverse storage module which extends from the opposite side of the body (specified in opposite side compartment).
 - There shall be two (2) OnScene Solutions Velcro cargo straps provided to secure the stored equipment.
 - There shall be one (1) storage module(s) for **air hose kit**.
 - There shall be one (1) OnScene Solutions Velcro cargo straps provided to secure the stored equipment.
- There shall be three (3) Zico 1000 series KD-UH walkaway type SCBA air pack bracket(s) with high cycle coated spring clips and angled foot plate (no CRS strap inc.).
- There shall be four (4) "J" style rope or equipment hook(s) for mounting of electrical extension cords or rescue ropes.
- The floor of the compartment above the frame rails shall be extended to the interior edge of the door. The floor shall have a 2" vertical lip and a 1" return to increase strength.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- An Innovative Controls black back-lit switch panel shall be provided to control cab tilt function with indicator light and properly labeled.
- The controls for the specified awning(s).
- There shall be one (1) 120 VAC outlet(s) located in compartment on **120/240V bulkhead**.
 - The outlet receptacle(s) shall be 20 amp, straight-blade (NEMA 5-20R).
 - Outlet(s) shall be powered by both the on-board generator and shore power system through a relay system.
- There shall be one (1) underbody storage compartment provided and installed below the compartment(s) ahead or rear wheels. Storage compartment shall be constructed from 1/8" aluminum 3003H-14 alloy smooth plate and shall be approximately **7"** high x 24" deep x **100" wide**. The compartment shall be reinforced to prevent flexing or damage when loaded. Compartment shall have a hinged drop down compartment door constructed of 1/8" aluminum . Door shall have a full width stainless steel piano hinge with a 1/4" stainless steel pin. Latching of the door shall be with a D-ring 1/4 turn latch with slam latch(s) for holding compartment door closed.
- **Compartment and door shall be powder coated 60% gloss black.**

CURBSIDE COMPARTMENT - AHEAD OF REAR WHEEL (C2)

The interior useable compartment width shall be approximately 64.5" wide.

The compartment door opening shall be approximately 57.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) 400 lbs. slide-out tray(s) approximately 24" deep and as wide as the compartment layout or door opening permits. The tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length. The tray assembly shall utilize a pneumatic cylinder mounted on underside to hold the tray in both the extended and closed positions.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) 400 lbs. slide-out tray(s) approximately 24" deep and as wide as the compartment layout or door opening permits. Each tray shall be vertically adjustable. Each tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length. The tray assembly shall utilize a pneumatic cylinder mounted on underside to hold the tray in both the extended and closed positions.
 - The above component(s) shall have a smooth un-painted finish.

- There shall be one (1) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 47" deep and as wide as the compartment layout or door opening permits located above the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 ½".
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) bolt-in vertical compartment partition(s) provided dividing the compartment into fore and aft sides. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.
Locate even with fore edge of plenum for vertical exhaust.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be a transverse storage module which extends from the opposite side of the body (specified in opposite side compartment).
- The floor of the compartment above the frame rails shall be extended to the interior edge of the door. The floor shall have a 2" vertical lip and a 1" return to increase strength.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- One (1) OnScene 8" Access white LED ground light(s) shall be provided below the body. Light(s) shall be switchable but activated automatically when the park brake is set.
- Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

CURBSIDE COMPARTMENT - ABOVE REAR WHEEL (C3)

The interior useable compartment width shall be approximately 56.5" wide.

The compartment door opening shall be approximately 49.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 47" deep and as wide as the compartment layout or door opening permits located above the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 ½".
 - Vertical partition(s) shall be provided on slide-out tray base dividing the tray into left and right sides. Each vertical partition shall be horizontally adjustable; mounted on aluminum Shelf Trac on tray floor. The vertical partition(s) shall be 3/16" (.188) 3003H-14 alloy smooth aluminum sheet.

Install to equally divide fore and aft portions of the tray.

- The above component(s) shall have a smooth un-painted finish.

- There shall be a transverse plywood storage module which extends from the opposite side of the body (specified in opposite side compartment).
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
- There shall be one (1) 120 VAC outlet(s) located in compartment on the forward wall, **below plywood module.**
 - The outlet receptacle(s) shall be 20 amp, straight-blade (NEMA 5-20R).
 - Outlet(s) shall be powered by both the on-board generator and shore power system through a relay system.

CURBSIDE COMPARTMENT - ABOVE REAR WHEEL (C4)

The interior useable compartment width shall be approximately 56.5" wide.

The compartment door opening shall be approximately 49.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) OnScene Solutions 81 series aluminum tray base with rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 60" deep and as wide as the compartment layout or door opening permits located above the level of the chassis frame rails. Slide base shall extend depth specified, less 4". Each slide base shall have a cable operated, spring loaded latch complimented by a large hand opening and red pull handle (Pull to Release) which will lock the tray in the closed and full extension positions. Each tray shall be fabricated from 3/16" 3003 aluminum sheet and shall have welded corners to form a box type tray surface with an internal depth of approximately 3 ½".
There will be Drip trays added to tray for the saw storage.
 - The above component(s) shall have a smooth un-painted finish.
- Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.

CURBSIDE COMPARTMENT - BEHIND REAR AXLE (C5)

The interior useable compartment space shall be approximately 70.5" wide.

The compartment door opening shall be approximately 63.2" wide.

This compartment shall have a R•O•M series IV roll-up door.

- The roll-up door slats and the door track components shall be painted to match the single tone exterior color.
- The door shall be equipped with a CPI harsh environment mechanical type door ajar switch located inside compartment interior door track to activate compartment lighting and door ajar signal in cab when door is opened.
- A keyed J236 cylinder lock shall be provided on bottom rail of the roll-up door.
- The roll-up doors shall be manually operated with a key.
- One (1) 1" wide elastic nylon strap shall be provided to assist in closing the compartment door. The strap shall be fastened to the lower left inside door sill with a nickel plated Footman loop secured to back of door. The strap shall extend from door to a nickel plated Footman loop secured to wall or vertical slot of Shelf-Trac on left side of the door opening.
- One (1) aluminum drip pan/door guard shall be provided below door roll area. Drip pan/door guard shall have thumb nuts making it easily removable without tools with a maintenance-free, un-painted finish. A plastic drain line shall be provided on each end of the drip pan to lower door threshold.
- Compartment threshold protection shall be provided on the bottom edge of the compartment door sill. The threshold protection shall be an extruded aluminum shape with an un-painted anodized finish.

COMPARTMENT LAYOUT

- There shall be vertically mounted aluminum Shelf-Trac welded to compartment walls for specified component installation. Shelf-Trac extrusion shall have side extruded channels for use in mounting or securing special ancillary items, without need for drilling into body.
- There shall be one (1) 400 lbs. slide-out tray(s) approximately 24" deep and as wide as the compartment layout or door opening permits. The tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length. The tray assembly shall utilize a pneumatic cylinder mounted on underside to hold the tray in both the extended and closed positions.
 - The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) 400 lbs. slide-out tray(s) approximately 30" deep and as wide as the compartment layout or door opening permits. The tray top shall be fabricated from 3/16" 3003 aluminum sheet with a 3" vertical lip and welded corners to form a box type tray surface. The sliding tracks shall extend 100% of the slide length. The tray assembly shall utilize a pneumatic cylinder mounted on underside to hold the tray in both the extended and closed positions.
- **Tray will be dog legged and extend inboard beyond the 30" slides.**

- The above component(s) shall have a smooth un-painted finish.
- There shall be one (1) OnScene Solutions 83 series aluminum tray base with 70% extension, and rating of 1,000 lbs. Slide-out tray(s) base shall be approximately 94" deep; capable of extending out either side of the body located above the level of the chassis frame rails. (Specified in opposite side compartment.)
- The floor of the compartment above the frame rails shall be extended to the interior edge of the door. The floor shall have a 2" vertical lip and a 1" return to increase strength.
- One (1) Hannay ECR1618-17-18 electric cable reel(s) capable of storing 200' of 10/3 electric cable. Reel(s) shall be designed to hold 110% of the capacity of cord length, with fully enclosed 45 amp, three (3) conductor collector rings. Reel(s) shall be mounted to channel structure that allows for side-to-side adjustment of reel position.
 - Power rewind control(s) shall be in a position where the operator can observe the rewinding operation and not be more than 72 in. (1830 mm) above the operator's standing position, and shall be marked with a label indicating its function and shall be guarded to prevent accidental operation.
 - A label shall be provided in a visible location adjacent to reel with following information: Current rating, Current type, Phase, Voltage, and Total cord length.
 - The cable reel shall equipped with 200' of 10/3 SEOW black cable, a molded plastic ball clamp, and a single heavy duty L5-30 twist-lock female plug at the end.
- One (1) Akron model EJBX series, cast aluminum electrical power distribution box with gray powder coat painted finish shall be provided. The power distribution box shall meet all requirements described in NFPA 1901. The power distribution box shall include the following outlets mounted on a backlit face plate;
 - A 12" pigtail that terminates in an L5-30 configuration to match the cable on the cord reel. The outlet configuration shall include:
 - One (1) 120 VAC, L5-15 dual twist lock receptacles
 - One (1) 120 VAC, L5-15 dual twist lock receptacles
 - One (1) 120 VAC, L5-15 dual twist lock receptacles
 - One (1) 120 VAC, 5-20 duplex straight-blade receptacle
- One (1) Akron Brass model EJB-VMT aluminum treadplate vertical mounting bracket for specified power distribution box shall be provided and mounted in compartment on **rear wall**.
- The fairlead roller shall be mounted directly to the reel.
- One (1) Hannay EF1520-17-18 low pressure air hose reel(s) shall be provided in this compartment. Reel shall be designed to hold 110% of the capacity needed.
 - Power rewind control(s) shall be in a position where the operator can observe the rewinding operation and not be more than 72 in. (1830 mm) above the operator's standing position, and shall be marked with a label indicating its function and shall be guarded to prevent accidental operation.

- A label shall be provided in a visible location adjacent to reel with following information: (1) Utility air or breathing air, (2) Operating pressure, (3) Total hose length, (4) Hose size (ID).
- The hose reel shall equipped with 200' of 3/8" Parker Series 7092 GST II low pressure air hose rated for 300 PSI maximum pressure. A molded plastic ball clamp shall be provided on the hose to stop it at the 4-way roller. The hose shall be Red in color with blue color coded end.

Utility Air System

- ~~The non-emergency air supply shall be from auxiliary air side of the cab chassis air brake system. The air circuit shall be equipped with a pressure protection valve (PPV) to protect air brake system from loss of pressure from tool useage. (Note: Per NFPA 24.12.1, The chassis air brake system shall not be used for emergency use applications such as airbags, tools, air reels, and other rescue applications).~~
 - A reel shut-off valve, 0 - 125 psi adjustable low pressure regulator, and 0 - 300 psi gauge shall be provided on an aluminum control panel with flow diagram graphic overlay near the air reel location, not exceeding 72" from ground.
- The fairlead roller shall be mounted directly to the reel.
 - Two (2) OnScene Access white LED, full height compartment lights, vertically mounted.
 - There shall be one (1) 240 VAC outlet(s) located in compartment mounted on the forward wall.
 - The outlet receptacle(s) shall be 30 amp, twist-lock (NEMA L6-30R).
 - Outlet(s) shall be powered through the on-board generator system.
 - Two (2) 3-1/2" x 3-1/2" black plastic louvered vents shall be provided in the lower compartment.

ROOF ACCESS STAIRWAY

The rear of the body shall be provided with a recessed center stairway in lieu of a compartment.

UPPER BODY COMPARTMENT - STREETSIDE

Above the exterior streetside compartments shall be an upper body compartment for storage of long equipment. The compartment shall be integral with the body construction, and will not be bolted or added on modules. The outside walls of compartment will be double walled to prevent equipment from denting the outside painted surface. The compartment shall be approximately (insert actual dimensions).

Access to the compartment shall be from a rear facing lift-up compartment door. Door shall be fabricated from 3/16" smooth aluminum with full length 14 gauge stainless steel hinge, with 1/4" stainless steel pin, 6" non-locking stainless steel "D" ring handle, and a gas cylinder door holder. A polyester barrier film gasket shall be placed between stainless steel hinge and any dissimilar metals as necessary to prevent corrosion. Door shall overlap body surface to prevent entry of moisture and sealed with automotive type rubber molding to provide a weather resistant seal.

Compartment shall have a flush mounted light near door opening that will be automatically activated when door is opened, and wired to compartment door ajar warning light provided in cab.

Devices to secure equipment, compartment dividers, or UHMW plastic angles, or sheeting will be used for storage of specified equipment as required to prevent damage to equipment.

A step shall be provided above bumper directly below compartment to assist in access to compartment storage. Step shall be fabricated from NFPA compliant aluminum treadplate with minimum 8" depth, width sized to fit space available.

The compartment will be designed to store the following equipment;

- One (1) pieces of wood lumber. Size of lumber to be provided during the pre-construction meeting.

REAR BODY HANDRAILS

There shall be **one (1)** Hansen International 24" x 1-1/8" **horizontal** handrails on rear body. Handrails shall be NFPA compliant formed from anodized aluminum with knurled anti-slip finish.

Each handrail shall be back-lit with a Safetylite, 12 VDC white LED light tube. Lights shall be activated with headlight and park brake set circuits.

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

UPPER BODY COMPARTMENT - CURBSIDE

Above the exterior curbside compartments shall be an upper body compartment for storage of long equipment. The compartment shall be integral with the body construction, and will not be bolted or added on modules. The outside walls of compartment will be double walled to prevent equipment from denting the outside painted surface. The compartment shall be approximately (insert actual dimensions).

Access to the compartment shall be from a rear facing lift-up compartment door. Door shall be fabricated from 3/16" smooth aluminum with full length 14 gauge stainless steel hinge, with 1/4" stainless steel pin, 6" non-locking stainless steel "D" ring handle, and a gas cylinder door holder. A polyester barrier film gasket shall be placed between stainless steel hinge and any dissimilar metals as necessary to prevent corrosion. Door shall overlap body surface to prevent entry of moisture and sealed with automotive type rubber molding to provide a weather resistant seal.

Compartment shall have a flush mounted light near door opening that will be automatically activated when door is opened, and wired to compartment door ajar warning light provided in cab.

Devices to secure equipment, compartment dividers, or UHMW plastic angles, or sheeting will be used for storage of specified equipment as required to prevent damage to equipment.

A step shall be provided above bumper directly below compartment to assist in access to compartment storage. Step shall be fabricated from NFPA compliant aluminum treadplate with minimum 8" depth, width sized to fit space available.

The compartment will be designed to store the following equipment;

One (1) Shall be configured to contain the following timbers:

Four (4) 4" x6" x16'

Four (4) 4" x4" x16'

Eight (8) 2" x6" x12'

REAR BODY HANDRAILS

There shall be **one (1)** Hansen International 24" x 1-1/8" **horizontal** handrails on rear body. Handrails shall be NFPA compliant formed from anodized aluminum with knurled anti-slip finish.

Each handrail shall be back-lit with a SafetyLite, 12 VDC white LED light tube. Lights shall be activated with headlight and park brake set circuits.

A safety sign FAMA23, which warns of the proper climbing method, shall be visible to personnel entering the cab and at each designated climbing location on the body.

A safety sign FAMA24, which warns personnel not to ride on the vehicle, shall be located at the rear step areas and at any cross walkways.

BODY OPTIONS AND UPGRADES

PLASTIC FLOOR AND SHELF TILE

Dri-Dek 12" x 12" x 9/16", self-draining plastic inter-locking material shall be cut to size and cover all compartment floors, shelves, and trays.

- The plastic floor tile shall be black.
- The plastic edge trim shall be black.

ROPE ANCHOR OR PORTABLE WINCH RECEIVERS

The completed unit shall have an integrated receiver or anchor system for use with removable rope anchor point and/or a portable electric winch, when specified.

Receivers or anchors installed at any location on the apparatus for use as removable winch anchors shall be designed and affixed to provide at least a 2.0 to 1 straight line pull no-yield safety factor over the load rating of the removable winch.

Receivers or anchors installed at any location on the apparatus for use with rope operations shall be designed and affixed to the apparatus to provide at least a 9,000 lbf (40,000 N) no-yield condition with a straight line pull.

A safety sign FAMA28 shall be located on or near each receiver or anchor stating the maximum straight line pull rating.

Side receiver(s) (if specified) shall have the following load rating:

	<u>STRAIGHT PULL</u>	<u>SAFETY FACTOR</u>
Rope Tie Off:	600 Lbs.	15:1
Winch:	5,000 Lbs.	2:1

Front and/or rear receiver(s) (if specified) shall have the following load rating:

	<u>STRAIGHT PULL</u>	<u>SAFETY FACTOR</u>
Rope Tie Off:	600 Lbs.	15:1
Winch:	Winch Load Rating (9,000 Lbs. Max)	2:1

The following items shall be provided to accomplish rope rescue and/or portable winch operation;

ROOF LOCATIONS

- Four (4) rope anchor point receiver(s) shall be provided and located on outboard edges of body roof area. The receiver(s) shall be manufactured using 2" x 2" x 1/4" wall steel trailer style receiver tube welded to 6" x 4" x 1/2" thick steel plate base and bolted to body structure. Anchor point will add 3-1/4" to body height and does not extend beyond body (without anchor point). The receiver assembly shall have a black powder coat paint finish. Each receiver location shall have a stainless steel scuff plate to protect paint on upper body. Reinforcements to body shall be added as necessary to increase the structural integrity and to provide a working weight rating of 600 lbs., with a 9,000 lbs. maximum load based upon using a 15:1 safety factor to match typical 1/2" rescue rope ratings.

ACCESSORIES

- Four (4) removable rope anchor(s) shall be provided for use with upper body specified receivers. Each rope anchor shall be fabricated from 3/4" steel, 2" high x 11.5" long with a 3" OD/2" ID eyelet. Eyelet end shall have radiused edge to prevent damage to rope or carabineer. Each rope anchor shall have a black powder coat paint finish.
- A steel 5/8" x 3" hitch pin shall lock the rope anchor into the receiver tube.

ACCESSORIES

- Two (2) removable rope anchor(s) shall be provided for use with lower body specified receivers. Each rope anchor shall be fabricated from 3/4" steel, 2" high x 11.5" long with a 3" OD/2" ID eyelet. Eyelet end shall have radiused edge to prevent damage to rope or carabineer. Each rope anchor shall have a black powder coat paint finish.
- A steel 5/8" x 3" hitch pin shall lock the rope anchor into the receiver tube.
- An aluminum mounting bracket shall be provided to store rope anchor(s) inside a body compartment as close to receiver location as possible.

PORTABLE WINCH

- One (1) Warn Zeon 8-S multi-mount, 8,000 lb. 12 VDC electric winch shall be provided with the completed unit. Winch shall be capable of being mounted to the vehicle by inserting the 2" tube of carrier into a properly rated receiver and pinned into place for use. Winch shall be supplied with 100' of 3/8" synthetic rope with pinned utility hook. A 12' remote control shall be provided that permits the operator to stand at a safe operating distance from the cable and winch. Winch shall have a black powder coat paint finish with a limited lifetime warranty.

STREETSIDE WHEEL WELL

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located on the streetside of the body in the forward wheel well panel area for use with removable rope anchor and/or a portable electric winch (when specified).
 - There shall be one (1) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
 - One (1) 12" x 2" M x 2" F winch mounting adapter(s) shall be provided. Winch adapter will extend the specified portable winch 6" from receiver. An aluminum mounting bracket shall be provided to store winch adapter(s) inside a body compartment as close to receiver location as possible.
 - The receiver(s) shall have one (1) rubber cover(s) provided.

STREETSIDE WHEEL WELL

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located on the streetside of the body in the rearward wheel well panel area for use with removable rope anchor and/or a portable electric winch (when specified).
 - The receiver(s) shall have one (1) rubber cover(s) provided.

CURBSIDE WHEEL WELL

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located on the curbside of the body in the forward wheel well panel area for use with removable rope anchor and/or a portable electric winch (when specified).
 - There shall be one (1) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
 - One (1) 12" x 2" M x 2" F winch mounting adapter(s) shall be provided. Winch adapter will extend the specified portable winch 6" from receiver. An aluminum mounting bracket shall be provided to store winch adapter(s) inside a body compartment as close to receiver location as possible.
 - The receiver(s) shall have one (1) rubber cover(s) provided.

CURBSIDE WHEEL WELL

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located on the curbside of the body in the rearward portion of the wheel well panel for use with removable rope anchor and/or a portable electric winch (when specified).
 - The receiver(s) shall have one (1) rubber cover(s) provided.

REAR BUMPER

- There shall be one (1) 2" x 2" x 1/4" wall steel receiver tube(s) with black hammertone powder coat paint finish located at the rear bumper for use with removable rope anchor point and/or a portable electric winch (when specified).
 - There shall be one (1) 12 VDC plug(s) with quick connect provided to power a Warn portable winch. All 12 VDC cables to be sized according to Warn and installation for intended use.
 - The receiver(s) shall have one (1) rubber cover(s) provided.

LOWER SIDE BODY PROTECTION - RUB RAIL

OnScene Solutions rub rails shall be provided below the compartment door openings on both the streetside and curbside.

The rub rail shall be fabricated from 6063 extruded aluminum, measuring approximately 2-3/4" high x 1-3/8" thick with tapered aluminum end caps. The rub rail shall be bolted to the body using stainless steel bolts and 1-1/2" diameter x 5/8" thick rubber mount isolators to prevent damage to the body.

The rails shall incorporate LED clearance marker lighting recessed into the rail fascia to avoid damage to the light in case of impact. The rub rail shall have an accessory mounting track integrated into the backside of the rail to allow mounting of accessories such as ground lighting.

3M™ Diamond Grade™ striping shall be provided in the rub rail. The striping shall be white in color.

ROLL-OUT AWNING STREETSIDE

A Carefree Mirage, 110 Volt AC powered, Lateral Arm Acrylic Patio Awning with Direct Response Electronics shall be installed on the body. The Direct Response Electronics includes easy-to-use controls and a Motion Detection System. The awning shall have a system to detect canopy motion, the most important element to prevent wind/weather damage. The awning shall automatically retract when the canopy reaches a certain level of movement, you determine the movement level on the control panel.

The 110V motor shall be completely sealed and UL approved. The awning pitch shall be adjusted to up to 30"

The awning shall be 21' wide with a 10' projection, (size refers to box length; actual fabric length will be 8" shorter.)

The Mirage shall be covered by a "Two and Four" Limited Warranty - Two years 100% parts, labor, & freight on canopy, four years 100% parts, labor, and freight on motor, electronics, roller & hardware. Warranty covers manufacturer's defects only. Wind and rain damage are not covered.

A red flashing or rotating light located in the driving compartment shall be illuminated automatically whenever the vehicles parking brake is not fully engaged, indicating that the awning is not in stowed position, as required by NFPA 1901.

- The Firesist HUV awning fabric color shall be crimson red (#88003-000).

The specified awning above shall be recess mounted into upper body side. An aluminum box enclosure shall be fabricated and recessed into upper body side for awning mounting and painted same color as upper body. The recessed awning shall add approximately 1.5" to body width.

AWNING HOUSING COLOR

The awnings standard white housing color shall be re-painted to match upper body color.

AWNING LED LIGHTS

The specified awning shall be provided with white LED lights under lead rail. Lights shall be turned on automatically when awning is extended, and turned off when awning is stowed.

ROLL-OUT AWNING CURBSIDE

A Carefree Mirage, 110 Volt AC powered, Lateral Arm Acrylic Patio Awning with Direct Response Electronics shall be installed on the body. The Direct Response Electronics includes easy-to-use controls and a Motion Detection System. The awning shall have a system to detect canopy motion, the most important element to prevent wind/weather damage. The awning shall automatically retract when the canopy reaches a certain level of movement, you determine the movement level on the control panel.

The 110V motor shall be completely sealed and UL approved. The awning pitch shall be adjusted to up to 30"

The awning shall be 21' wide with a 10' projection, (size refers to box length; actual fabric length will be 8" shorter.)

The Mirage shall be covered by a "Two and Four" Limited Warranty - Two years 100% parts, labor, & freight on canopy, four years 100% parts, labor, and freight on motor, electronics, roller & hardware. Warranty covers manufacturer's defects only. Wind and rain damage are not covered.

A red flashing or rotating light located in the driving compartment shall be illuminated automatically whenever the vehicles parking brake is not fully engaged, indicating that the awning is not in stowed position, as required by NFPA 1901.

- The Firesist HUV awning fabric color shall be crimson red (#88003-000).

The specified awning above shall be recess mounted into upper body side. An aluminum box enclosure shall be fabricated and recessed into upper body side for awning mounting and painted same color as upper body. The recessed awning shall add approximately 1.5" to body width.

AWNING HOUSING COLOR

The awnings standard white housing color shall be re-painted to match upper body color.

AWNING LED LIGHTS

The specified awning shall be provided with white LED lights under lead rail. Lights shall be turned on automatically when awning is extended, and turned off when awning is stowed.

LOW VOLTAGE ELECTRICAL SYSTEM- 12 VDC

General

Any low voltage electrical systems or warning devices installed on the fire apparatus shall be appropriate for the mounting location and intended electrical load.

Where wire passes through sheet metal, grommets shall be used to protect wire and wire looms. Electrical connections shall be with double crimp water-tight heat shrink connectors.

All 12 VDC wiring running from front to back of vehicle body shall be run in full length electrical wiring raceway down each side of body.

Wiring

All electrical circuit feeder wiring supplied and installed by the fire apparatus manufacturer shall meet the requirements of NFPA Chapter 13.

The circuit feeder wire shall be stranded copper or copper alloy conductors of a gauge rated to carry 125% of the maximum current for which the circuit is protected. Voltage drops in all wiring from the power source to the using device shall not exceed 10%. The use of star washers for circuit ground connections shall not be permitted.

All circuits shall otherwise be wired in conformance with SAE J1292, *Automobile, Truck, Truck-Tractor, Trailer, and Motor Coach Wiring*.

Wiring and Wire Harness Construction

All insulated wire and cable shall conform to SAE J1127, *Low Voltage Battery Cable*, or SAE J1128, *Low Voltage Primary Cable*, type SXL, GXL, or TXL.

All conductors shall be constructed in accordance with SAE J1127 or SAE J1128, except where good engineering practice dictates special strand construction. Conductor materials and stranding, other than copper, shall be permitted if all applicable requirements for physical, electrical, and environmental conditions are met as dictated by the end application. Physical and dimensional values of conductor insulation shall be in conformance with the requirements of SAE J1127 or SAE J1128, except where good engineering practice dictates special conductor insulation. The overall covering of conductors shall be moisture-resistant loom or braid that has a minimum continuous rating of 194°F (90°C) except where good engineering practice dictates special consideration for loom installations exposed to higher temperatures. The overall covering of jacketed cables shall be moisture resistant and have a minimum continuous temperature rating of 194°F (90°C), except where good engineering practice dictates special consideration for cable installations exposed to higher temperatures.

All wiring connections and terminations shall use a method that provides a positive mechanical and electrical connection. The wiring connections and terminations shall be installed in accordance with the device manufacturer's instructions. All ungrounded electrical terminals shall have protective covers or be in enclosures. Wire nut, insulation displacement, and insulation piercing connections shall not be used.

Wiring shall be restrained to prevent damage caused by chafing or ice buildup and protected against heat, liquid contaminants, or other environmental factors.

Wiring shall be uniquely identified at least every 2 ft (0.6 m) by color coding or permanent marking with a circuit function code. The identification shall reference a wiring diagram.

Circuits shall be provided with properly rated low voltage over-current protective devices. Such devices shall be readily accessible and protected against heat in excess of the over-current device's design range, mechanical damage, and water spray. Circuit protection shall be accomplished by utilizing fuses, circuit breakers, fusible links, or solid state equivalent devices.

If a mechanical-type device is used, it shall conform to one of the following SAE standards:

- 1) SAE J156, *Fusible Links*
- 2) SAE J553, *Circuit Breakers*
- 3) SAE J554, *Electric Fuses (Cartridge Type)*
- 4) SAE J1888, *High Current Time Lag Electric Fuses*
- 5) SAE J2077, *Miniature Blade Type Electrical Fuses*

Switches, relays, terminals, and connectors shall have a direct current (dc) rating of 125% of maximum current for which the circuit is protected.

Power Supply

A 12 V or greater electrical alternator shall be provided. The alternator shall have a minimum output at idle to meet the minimum continuous electrical load of the vehicle, at 200°F (93°C) ambient temperature within the engine compartment, and shall be provided with full automatic regulation.

Minimum Continuous Electrical Load

The minimum continuous electrical load shall consist of the total amperage required to simultaneously operate the following in a stationary mode during emergency operations:

- 1) The propulsion engine and transmission
- 2) All legally required clearance and marker lights, headlights, and other electrical devices except windshield wipers and four-way hazard flashers
- 3) The radio(s) at a duty cycle of 10 percent transmit and 90% receive (for calculation and testing purposes, a default value of 5 A continuous)
- 4) The lighting necessary to produce 2 fc (20 lx) of illumination on all walking surfaces on the apparatus and on the ground at all egress points onto and off the apparatus, 5 fc (50 lx) of illumination on all control and instrument panels, and 50 percent of the total compartment lighting loads
- 5) The minimum optical warning system, where the apparatus is blocking the right-of way
- 6) The continuous electrical current required to simultaneously operate any fire pumps, aerial devices, and hydraulic pumps
- 7) Other warning devices and electrical loads defined by the purchaser as critical to the mission of the apparatus

If the apparatus is equipped to tow a trailer, an additional 45 A shall be added to the minimum continuous electrical load to provide electrical power for the federally required clearance and marker lighting and the optical warning devices mounted on the trailer.

The condition of the low voltage electrical system shall be monitored by a warning system that provides both an audible and a visual signal to persons on, in, or near the apparatus of an impending electrical system failure caused by the excessive discharge of the battery set.

The charge status of the battery shall be determined either by direct measurement of the battery charge or indirectly by monitoring the electrical system voltage.

If electrical system voltage is monitored, the alarm shall sound if the system voltage at the battery or at the master load disconnect switch drops below 11.8 V for 12 V nominal systems, 23.6 V for 24 V nominal systems, or 35.4 V for 42 V nominal systems for more than 120 seconds.

A voltmeter shall be mounted on the driver's instrument panel to allow direct observation of the system voltage.

Electromagnetic Interference

Electromagnetic interference suppression shall be provided, as required, to satisfy the radiation limits specified in SAE J551/1, *Performance Levels and Methods of Measurement of Electromagnetic Compatibility of Vehicles, Boats (up to 15 m), and Machines (16.6 Hz to 18 GHz)*.

Wiring Diagram

A complete electrical wiring schematic of actual system shall be provided with finished apparatus. Similar or generic type electrical schematics shall NOT BE ACCEPTABLE.

Low Voltage Electrical System Performance Test

A low voltage electrical system test certification shall be provided with delivered apparatus.

12 VOLT MULTIPLEX CONTROL CENTER

The apparatus shall be equipped with a Weldon V-MUX multiplexed 12 volt electrical system that will provide complete diagnostic capability, No Exception. The system shall have the capability of delivering multiple signals via a CAN bus, utilizing specifications set forth by SAE J1939. The system shall be node based to maximize stability so that failure of one node does not affect the operation of the other nodes. The system shall use shielded twisted-pair wire for transmission of system function signals. The shielded wire shall provide protection against EMI and RFI noise interruptions.

The multiplex system shall be responsible for providing power management functions as well as load shedding. The warning light system shall be controlled by the multiplex system. The system shall be capable of displaying text and/or graphic messages on a display module. The system shall be based on solid-state technology and shall include self-contained diagnostic indicators.

WELDON CERTIFICATION

A letter shall be provided with bid submittal that the Contractor has successfully completed the Weldon training requirements for Level 1 of the V-MUX Certified Supplier Program and is authorized to design, build, and service V-MUX electrical systems.

The apparatus shall be equipped with a Weldon V-MUX multiplexed 12 volt electrical system that will provide complete diagnostic capability, No Exception. The system shall have the capability of delivering multiple signals via a CAN bus, utilizing specifications set forth by SAE J1939. The system shall be node based to maximize stability so that failure of one node does not affect the operation of the other nodes. The system shall use shielded twisted-pair wire for transmission of system function signals. The shielded wire shall provide protection against EMI and RFI noise interruptions.

The multiplex system shall be responsible for providing power management functions as well as load shedding. The warning light system shall be controlled by the multiplex system. The system shall be capable of displaying text and/or graphic messages on a display module. The system shall be based on solid-state technology and shall include self-contained diagnostic indicators.

MULTIPLEX SYSTEM INTERFACE DISPLAY

The Weldon V-MUX Vista IV multiplex system interface display(s) shall be provided by the cab/chassis manufacturer. The full-color Vista interface display allows the user to control warning and scene lighting, HVAC controls (when specified), and view on-board diagnostics including service information. This display has a wide operating temperature range, automatic screen switching in response to current conditions, and a sleep mode option to eliminate night glare. The following features shall be included;

- 800 x 480 resolution
- Four video ports
- Flash updates with USB memory stick
- Display inside and outside temperature (when specified)
- Automatic climate control (when specified)
- 100% Configurable (OEM Level)
- Field re-programmable
- Peer to peer network
- On-board diagnostics / service information
- Colors change to indicate button status
- Video Ready for: Backup camera, Thermal camera, DVD, GPS...

BATTERY SYSTEM

The battery connectors shall be heavy duty type with cables terminating in heat shrink loom. Heavy duty battery cables shall provide maximum power to the electrical system. Where required, the cables shall be shielded from exhaust tubing and the muffler. Large rubber grommets shall be provided where cables enter the battery compartment.

Batteries shall be of the high-cycle type. With the engine off, the battery system shall be able to provide the minimum continuous electrical load for 10 minutes without discharging more than 50 percent of the reserve capacity and then to restart the engine. The battery system cold cranking amps (CCA) rating shall meet or exceed the minimum CCA recommendations of the engine manufacturer. The batteries shall be mounted to prevent movement during fire apparatus operation and shall be protected against accumulations of road spray, snow, and road debris. The batteries shall be readily accessible for examination, testing, and maintenance.

A means shall be provided for jump-starting the engine if the batteries are not accessible without lifting the cab of a tilt-cab apparatus.

Where an enclosed battery compartment is provided, it shall be ventilated to the exterior to prevent the buildup of heat and explosive fumes. The batteries shall be protected against vibration and temperatures that exceed the battery manufacturer's recommendation.

An onboard battery conditioner or charger or a polarized inlet shall be provided for charging all batteries. Where an onboard conditioner or charger is supplied, the associated line voltage electrical power system shall be installed in accordance with Chapter 22.

One of the following master disconnect switches shall be provided:

- 1) A master body disconnect switch that disconnects all electrical loads not provided by the chassis manufacturer
- 2) A master load disconnect switch that disconnects all electrical loads on the apparatus except the starter

Electronic control systems and similar devices shall be permitted to be otherwise connected if so specified by their manufacturer.

The alternator shall be wired directly to the batteries through the ammeter shunt(s), if one is provided, and not through the master load disconnect switch.

A green “battery disconnect on” indicator light that is visible from the driver’s position shall be provided.

Rechargeable hand lights, radios, and other similar devices shall be permitted to be connected to the electrical system ahead of the master disconnect switch.

A sequential switching device shall be permitted to energize the optical warning devices and other high current devices required in minimum continuous electrical load, provided the switching device shall first energize the electrical devices required in minimum continuous electrical load within 5 seconds.

BATTERY SWITCH

One (1) battery disconnect switch shall be provided in cab located within easy reach of driver with green indicator light that is visible from the driver’s position. The switch and indicator light shall be supplied and installed by the cab/chassis manufacturer.

BATTERY SOLENOID

Battery switch shall consist of a minimum 200 ampere, constant duty solenoid to feed from positive side of battery.

BATTERY CONDITIONER

One (1) Blue Sea model P12 battery charger with 120 VAC input, and 40 amp 12 VDC output shall be provided. The P12 is a four stage, three output, dry mount charger designed for use in harsh environments where reliability, ease of use, and high performance are of primary importance. Backed by a 5-year warranty.

Five Critical Features Extend Battery Life

- User Defined Charge Profiles for setting voltages to match the battery manufacturer’s recommendations
- User Defined Absorption Stage Values determine when the charger should exit Absorption Stage in order to prevent overcharging
- Charge Coordination™ integrates with Blue Sea Systems’ Automatic Charging Relays to separate battery banks while the P12 is operational
- PreFloat™ Stage prevents over charging by individually moving batteries out of Absorption Stage
- Battery Temperature Compensation adjusts charging voltage up (for colder batteries) or down (for warmer batteries) as recommended by battery manufacturers for proper battery performance

Additional Features

- Rugged finned aluminum case dissipates heat
- Universal line voltage 90–265V AC, 45–65 Hz for worldwide use
- Large bright full graphic control screen with user interface
- Plain-language text in English, French, Italian, German and Spanish
- Intuitive screens provide fault alerts and plain language diagnostics

BATTERY CHARGE INDICATOR

A Blue Sea EV battery charger display shall be provided and located near driver's door area. It can display a graphical representation of voltage with or without connection to a P12 battery charger. When connected to a P12 battery charger it can display the charger's summary screen, displaying voltage, current charging stage, and faults from the charger with other features as follows;

- Drop in replacement for traditional rectangular displays
- Automatically detects 1-3 battery banks
- AC charge indication verifies that power is connected and the battery charger is charging
- Plain language fault indication relays if there is a fault with the battery charger
- Dip switch selectable screen configuration allows the display to show voltage bar graphs or the P12 Battery Charger summary screen
- Displays voltage bar graphs even when AC power is not present
- Optional standby mode shuts off screen after 4 hours of inactivity
- Automatic ON based on motion with integrated knock sensor
- Bright, daylight readable, OLED display
- **INSTALLED IN DRIVER MID STEP**

SHORE POWER INLET

The shore power inlet for battery conditioner shall be supplied and installed by the cab chassis manufacturer.

- The shore power plug shall be located near the Driver door area.

ENGINE COMPARTMENT LIGHT

Engine compartment light(s) shall be supplied and installed by the cab chassis manufacturer.

CAB HAZARD WARNING LIGHT

A red flashing or rotating light, located in the driving compartment. The light shall be furnished by the cab/chassis manufacturer. The light shall be illuminated automatically whenever the vehicles parking brake is not fully engaged and any of the following conditions exist:

- Any passenger or equipment compartment door is not closed.
- Any ladder or equipment rack is not in the stowed position.
- Stabilizer system is not in its stowed position.
- Powered light tower is not stowed.
- Any other device permanently attached to the apparatus is open, extended, or deployed in a manner that is likely to cause damage to the apparatus if the apparatus is moved.

Compartments and equipment meeting all of the following conditions shall be permitted to be exempt from being wired to the hazard light:

- The volume is less than or equal to 4 ft³ (0.1 m³).
- The compartment has an opening less than or equal to 144 in.² (92,900 mm²).
- The open door does not extend sideways beyond the mirrors or up above the top of the fire apparatus.
- All equipment in the compartment is restrained so that nothing can fall out if the door is open while the apparatus is moving.

- Manually raised pole lights with an extension of less than 5 ft (1.5 m).

The hazard light shall be labeled "DO NOT MOVE APPARATUS WHEN FLASHING".

BACK-UP ALARM

An electronic back-up alarm shall be supplied and installed by the cab/chassis manufacturer. The back-up alarm shall actuate automatically when the transmission gear selector is placed in reverse.

REAR VIEW CAMERA

The cab chassis provided rear view box camera shall be installed on the rear of the body.

- **Camera will be mounted in a recessed aluminum pocket, painted job color, floor of pocket shall have a floor sloped down to outboard face to aid in water drainage. Slope shall be a minimum of 10 degrees.**

TAIL LIGHTS

Rear body tail lights shall be vertically mounted and located per Federal Motor Vehicle Safety Standards, FMVSS and Canadian Motor Vehicle Safety Standards CMVSS. The following lights shall be furnished;

- Two (2) Whelen specified lower Zone "C" warning lights
- Two (2) Whelen M6 Series M6T amber LED turn signal lights
- Two (2) Whelen M6 Series M6BTT red LED stop/tail lights
- Two (2) Whelen M6 Series M6BUW LED back-up lights with clear lens

Each of the lights above shall be mounted in an M6FCV4, 4-light chrome finish bezels.

MIDSHIP MARKER/TURN SIGNAL

Two (2) Whelen model T0A00MAR 2" round amber LED midship body clearance marker/turn signal lights shall be provided and installed, one (1) light on each side of the body, in forward wheel well of rear axle. Midship marker/turn lights shall be wired to the headlight circuit of the chassis.

MARKER LIGHTS

The body shall be equipped with all necessary side and rear clearance lights and reflectors in accordance with Federal Motor Vehicle Safety Standards (FMVSS) and Canadian Motor Vehicle Safety Standards (CMVSS). Clearance lights on body shall be connected to the clearance light circuit of the chassis.

REAR BUMPER MARKER LIGHTS

Two (2) Britax style dual face flexible mounted rear bumper markers shall be located, one (1) each side lower rear corner of body visible from driver mirrors.

CAB STEP LIGHTS / GROUND LIGHTS

The step lights and/or ground lights shall be supplied and installed by the cab/chassis manufacturer. Light(s) shall be capable of providing illumination at a minimum level of 2 fc (20 lx) on ground areas within 30 in. (800 mm) of the edge of the vehicle in areas designed for personnel to climb onto or descend from the vehicle to the ground level.

Lighting designed to provide illumination on areas under the driver and crew riding area exits shall be switchable but activated automatically when the exit doors are opened.

LICENSE PLATE MOUNTING BRACKET

There shall be one (1) Cast Products aluminum license plate mounting with chrome shielded license plate light mounted on the rear of the body.

REAR LED SCENE LIGHTS

Two (2) Whelen M9 Series Model M9LZC , 9" x 7" surface mounted scene light(s) shall be provided on the upper rear body to light the work area. The M9LZC configuration shall consist of 24 clear Super-LEDs and a clear gradient optic polycarbonate lens with chrome flange. The M9LZC series light shall have 6,500 useable lumens each. The scene light is covered by a five year factory warranty

The above scene lights shall light to a level of at least 3 fc (30 lx), measured at 25 equally spaced points on a 2.5 ft (750 mm) grid with in a 10 ft x 10 ft (3 m x 3m) square to the rear of vehicle.

The lights shall be controlled at the multiplex display(s) in the cab.

The rear scene lights shall also be activated when the apparatus is in reverse.

TRAFFIC ADVISOR LIGHTS

A traffic advisor system shall be provided on rear of vehicle using;

- Eight (8) Whelen Wide-angle ION series amber Super-LED lights with clear lens.
- Chrome flanges.
- Lights shall be individually mounted and evenly distributed.

The lights shall be controlled by a Whelen TACTL5 control located in cab dash or center console area and provide; Left Arrow, Right Arrow, Center Out, and Wig-Wag patterns. The LED display on the control head shall replicate the Traffic Advisor's directional sequence. The TACTL5 shall have a rear panel dip switch for the ability to set eight additional Scan-Lock™ flash patterns. The wig-wag light pattern shall be activated with the E-Master and can be switched to the other patterns at any time through the control panel.

WARNING LIGHT PACKAGE

Each apparatus shall have a system of optical warning devices that meets or exceeds the requirements of this section.

The optical warning system shall consist of an upper and a lower warning level. The requirements for each level shall be met by the warning devices in that particular level without consideration of the warning devices in the other level.

For the purposes of defining and measuring the required optical performance, the upper and lower warning levels shall be divided into four (4) warning zones. The four zones shall be determined by lines drawn through the geometric center of the apparatus at 45 degrees to a line drawn lengthwise through the geometric center of the apparatus. The four (4) zones shall be designated A, B, C, and D in a clockwise direction, with zone A to the front of the apparatus.

Each optical warning device shall be installed on the apparatus and connected to the apparatus's electrical system in accordance with the requirements of this standard and the requirements of the manufacturer of the device.

A master optical warning system switch that energizes all the optical warning devices shall be provided.

The optical warning system on the fire apparatus shall be capable of two (2) separate signaling modes during emergency operations. One (1) mode shall signal to drivers and pedestrians that the apparatus is responding to an emergency and is calling for the right-of-way. One (1) mode shall signal that the apparatus is stopped and is blocking the right-of-way. The use of some or all of the same warning lights shall be permitted for both modes provided the other requirements of this chapter are met.

A switching system shall be provided that senses the position of the parking brake or the park position of an automatic transmission. When the master optical warning system switch is closed and the parking brake is released or the automatic transmission is not in park, the warning devices signaling the call for the right-of-way shall be energized. When the master optical warning system switch is closed and the parking brake is on or the automatic transmission is in park, the warning devices signaling the blockage of the right-of-way shall be energized. The system shall be permitted to have a method of modifying the two (2) signaling modes.

The optical warning devices shall be constructed or arranged so as to avoid the projection of light, either directly or through mirrors, into any driving or crew compartment(s). The front optical warning devices shall be placed so as to maintain the maximum possible separation from the headlights.

Steadily burning, non flashing optical sources shall be permitted to be used.

UPPER LEVEL OPTICAL WARNING DEVICES

The upper-level optical warning devices shall be mounted as high and as close to the corner points of the apparatus as is practical to define the clearance lines of the apparatus. The upper-level optical warning devices shall not be mounted above the maximum height, specified by the device manufacturer.

ZONE A - FRONT WARNING LIGHTS

The light bar shall be supplied and installed by the cab/chassis manufacturer.

The lightbar(s) shall be separately controlled at multiplex display(s) in the cab.

ZONES B AND D - SIDE WARNING LIGHTS

UPPER REAR CORNER WARNING LIGHTS

There shall be two (2) Whelen M9 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

Each light shall have a chrome flange.

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

UPPER FORWARD CORNER WARNING LIGHTS

There shall be two (2) Whelen M9 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

Each light shall have a chrome flange.

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONE C - REAR WARNING LIGHTS

There shall be two (2) Whelen M9 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

Each light shall have a chrome flange.

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

LOWER LEVEL OPTICAL WARNING DEVICES

To define the clearance lines of the apparatus, the optical center of the lower-level optical warning devices in the front of the vehicle shall be mounted on or forward of the front axle centerline and as close to the front corner points of the apparatus as is practical.

The optical center of the lower-level optical warning devices at the rear of the vehicle shall be mounted on or behind the rear axle centerline and as close to the rear corners of the apparatus as is practical. The optical center of any lower-level device shall be between 18 in. and 62 in. (460 mm and 1600 mm) above level ground for large apparatus, and 18 in. and 48 in. (460 mm and 1600 mm) above level ground.

A midship optical warning device shall be mounted right and the left sides of the apparatus if the distance between the front and rear lower-level optical devices exceeds 25 ft (7.6 m) at the optical center. Additional midship optical warning devices shall be required, where necessary, to maintain a horizontal distance between the centers of adjacent lower-level optical warning devices of 25 ft (7.6 m) or less. The optical center of any midship mounted optical warning device shall be between 18 in. and 62 in. (460 mm and 1600 mm) above level ground.

ZONE A - FRONT WARNING LIGHTS

The warning lights shall be supplied and installed by the cab/chassis manufacturer. They shall be Whelen lights to complete an NFPA compliant lower level warning light system.

- Flash pattern shall be as supplied by the cab and chassis manufacturer.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONES B AND D - CAB INTERSECTOR LIGHT (CAB FRONT CORNERS)

There shall be two (2) Whelen M6 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

Each light shall have a chrome flange.

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONES B AND D - BODY LIGHT (BODY WHEELWELL AREA)

There shall be two (2) Whelen M6 V-series combination 180° red linear Super-LED warning lights with 45° perimeter scene lights (M6V2R) provided, one (1) each side. Perimeter scene lights will be turned on with specified scene lighting. Each light shall have a red lens over warning light and clear lens over perimeter light and chrome flange.

The lights shall be controlled at the multiplex display(s) in the cab.

- **Puddle/Scene lighting shall be activated by the reverse signal, the respective side turn signal and the ground light circuit.**

ZONES B AND D - BODY LIGHT (BODY WHEELWELL AREA)

There shall be ~~two (2)~~ **four (4)** Whelen surface mount ION Series LED light(s) with wide angle optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns. Component shall be covered by a five year Whelen factory warranty.

Each light shall have:

- Red LEDs
- Clear Lens
- Chrome Flange

To be located one (1) each under S3, S4, C3, C4 compartments.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONES B AND D - BODY INTERSECTOR LIGHT (BODY REAR CORNERS)

There shall be two (2) Whelen M6 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

Each light shall have a chrome flange.

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

ZONE C - REAR WARNING LIGHTS (LOWER REAR CORNERS)

There shall be two (2) Whelen M6 SurfaceMax, linear super-LED Light(s) with full-fill optic provided, one (1) each side. The light head shall include an integral flasher with programmable flash patterns and Hi/Lo intensities. Component shall be covered by a five year Whelen factory warranty.

Each Light shall have:

- Red LEDs
- Red Lens

- Flash Pattern shall be (factory default) Action Scan.

The lights shall be controlled at the multiplex display(s) in the cab.

LINE VOLTAGE ELECTRICAL SYSTEM

ONAN PTO GENERATOR

The vehicle shall be equipped with an Onan Protec PTO generator system with a capacity of 35,000 watts at 120/240 VAC, 291/145 amps, single phase. Current frequency shall be stable at 60 hertz.

The transmission's PTO port and PTO, or the split shaft PTO, and all associated drive shaft components shall be rated to support the continuous duty torque requirements of the generator's continuous duty rating as stated on the power source nameplate.

Where the generator is driven by the chassis engine and transmission through a split shaft PTO, the driving compartment speedometer shall register when the generator drive system is engaged.

Where the generator is driven by the chassis engine and transmission through a split shaft PTO and a chassis transmission retarder is furnished, it shall be automatically disengaged for generator operations.

The direct drive generator shall be mounted so that it does not change the ramp break-over angle, angle of departure, or angle of approach as defined by other components, and it shall not extend into the ground clearance area.

The direct drive generator shall be mounted away from exhaust and muffler areas or provided with a heat shield to reduce operating temperatures in the generator area.

GENERATOR BONDING

A minimum of four (4) 16" x 2 gauge copper ground straps shall be bolted to body sub-frame and chassis sub-frame for proper bonding of high voltage system. The conductor shall have a minimum amperage rating, as defined in 310.15, "Ampacities for Conductors Rated 0–2000 Volts," of *NFPA 70*, of 115 percent of the rated amperage on the power source specification label.

GENERATOR ENGAGEMENT

A "Generator Engaged" indicator shall be provided in the driving compartment to indicate that the generator shift has been successfully completed.

An "OK to Operate Generator" indicator shall be provided in the driving compartment to indicate that the generator is engaged (if not always engaged), the transmission is in the proper gear (if required, automatic transmissions only), and the parking brake is engaged (if applicable).

An interlock system shall be provided to prevent advancement of the engine speed in the driving compartment or at any operator's panel unless the parking brake is engaged, and the transmission is in neutral or the output of the transmission is correctly connected to a pump or generator instead of the drive wheels.

WARRANTY PERIOD

Provided such goods are operated and maintained in accordance with Onan's written instructions, Onan warrants that the Protec YDCR series PTO generators shall be free from defects in material and workmanship for a period of five (5) years or one thousand (1,000) hours, whichever comes first, from the date of delivery to the first purchaser.

GENERATOR SPLASH GUARD

A powder coat painted splash cover shall be installed to reduce the amount of road spray on the frame mounted PTO generator. A V-ring seal shall also be installed in the cover to provide additional protection against contaminants reaching the generator front seals.

GENERATOR CONTROL

The generator shall be engaged at the multiplex display(s) in the cab.

GENERATOR MOUNTING - ONAN PROTEC

The generator shall be mounted below the chassis frame rails. The generator mounting brackets shall be fabricated using steel plate and/or tubing and powder coat primed and painted black. The generator mounting shall be bolted to the side of the chassis frame rail and removable so that the generator can be lowered from under apparatus for service, if necessary. The generator case shall not extend below the bottom edge of the apparatus body.

MANUALS AND SCHEMATICS

Two (2) complete manuals on parts list, maintenance, wiring schematics, hydraulic schematics, circuit boards, voltage regulator board and other components shall be provided on delivery.

POWER-TAKE-OFF GENERATOR DRIVE

There shall be a "Hot Shift" power-take-off (PTO) installed on the transmission PTO opening of the chassis. The "Hot Shift" PTO is provided to allow the engagement of the PTO at higher engine RPM speeds. The PTO output shall be connected to the generator through hollow tube type driveline with heavy duty universals.

The engagement of the PTO shall be in the chassis cab with a rocker switch and red pilot light to note engagement of the PTO or via the V-Mux screen if so equipped.

The power supply to the PTO engagement control shall be wired to the parking brake and a neutral position transmission switch to prevent engagement unless the vehicle is stopped and transmission has been placed in neutral.

The installation of the engine, transmission, driven accessories (power takeoffs (PTO), etc.) shall meet the engine and transmission manufacturers' installation recommendations for the service intended.

Model part number shall be Chelsea 280 series.

ENGINE SPEED CONTROL

An engine speed auxiliary control device (high idle switch or throttle) shall be installed to maintain a stable cycle output from generator when the apparatus is parked.

An interlock shall prevent the operation of the engine speed auxiliary control device unless the parking brake is engaged and the transmission is in neutral or park, or the parking brake is engaged and the engine is disengaged from the drive wheels.

The engine shall be prevented from regulating its own engine speed during times when engine rpm control is critical for consistent apparatus functions such as generator, water pump, or aerial operation.

LOADCENTER

The loadcenter shall be an Eaton BR Series specifically designed for protection and distribution of AC line voltage such as lighting and small motor branch circuits. The loadcenter enclosure is made of 16 gauge galvanized sheet steel with a galvanized coating provided for corrosion protection. All trims used on BR loadcenters are chromate sealed and finished with an electro-disposition epoxy paint (ANSI-61) which exceeds requirements for outdoor and indoor applications. A combination surface/flush cover with integral door is supplied with indoor loadcenters rated from 100 through 400 amperes. All plug-in loadcenters are CSA listed to file LL98266. CSA Certified to C22.2 No.29, to loadcenter type and CSA listing.

GENERATOR MONITORING PANEL

An Accuenergy Acuvim II multifunction power and energy meter shall be provided to properly monitor the generator performance and load demand during operation. The Accuenergy Acuvim CL includes a digital RS485 communication port running Modbus protocol. The electrical parameters can be viewed on a backlit LCD screen. Unit shall be capable of displaying the following;

- Generator frequency in hertz
- Line 1 current in amperes
- Line 2 current in amperes
- Generator voltage in volts
- Meter running time

SHORE POWER INLET - BATTERY CHARGER

The above mentioned shore power inlet, and battery conditioner shall be specified in the 12 volt section.

INVERTER

- A Kussmaul/**Xantrex** inverter model **Freedom X2000** shall be provided and installed on completed vehicle **with remote panel**.

LINE VOLTAGE ELECTRICAL SYSTEM

GENERAL REQUIREMENTS

Stability

Any fixed line voltage power source producing alternating current (ac) shall produce electric power at 60 Hz, ± 3 Hz when producing power at all levels between no load and full rated power. Any fixed line voltage power source shall produce electric power at the rated voltage ± 10 percent when producing power at all levels between no load and full rated power.

The maximum voltage supplied to portable equipment shall not exceed 275 volts to ground. Higher voltage shall be permitted only when used to operate fixed wired, permanently mounted equipment on the apparatus.

Conformance with National Electrical Code

All components, equipment, and installation procedures shall conform to *NFPA 70, National Electrical Code*, except where superseded by the requirements of this chapter. Where the requirements of this chapter differ from those in *NFPA 70*, the requirements in this chapter shall apply.

Where available, line voltage electrical system equipment and materials included on the apparatus shall be listed and used only in the manner for which they have been listed. All equipment and materials shall be installed in accordance with the manufacturer's instructions.

Location Ratings

Any equipment used in a dry location shall be listed for dry locations. Any equipment used in a wet location shall be listed for wet locations.

Any equipment, except a PTO-driven generator, used in an underbody or under chassis location that is subject to road spray shall be either listed as Type 4 or mounted in an enclosure that is listed as Type 4.

If a PTO-driven generator is located in an underbody or under chassis location, the installation shall include a shield to prevent road spray from splashing directly on the generator.

Grounding

Grounding shall be in accordance with 250.34(A) and 250.34(B) of *NFPA 70*. Ungrounded systems shall not be used.

Only stranded or braided copper conductors shall be used for grounding and bonding.

The grounded current-carrying conductor (neutral) shall be insulated from the equipment-grounding conductors and from the equipment enclosures and other grounded parts.

The neutral conductor shall be colored white or gray in accordance with 200.6, "Means of Identifying Grounded Conductors," of *NFPA 70*.

Any bonding screws, straps, or buses in the distribution panel board or in other system components between the neutral and equipment-grounding conductor shall be removed and discarded.

Bonding

The neutral conductor of the power source shall be bonded to the vehicle frame. The neutral bonding connection shall occur only at the power source. In addition to the bonding required for the low voltage return current, each body and each driving or crew compartment enclosure shall be bonded to the vehicle frame by a copper conductor.

The conductor shall have a minimum ampere rating, as defined in 310.15, "Ampacities for Conductors Rated 0–2000 Volts," of *NFPA 70*, of 115 percent of the rated ampere on the power source specification label.

A single conductor that is sized to meet the low voltage and line voltage requirements shall be permitted to be used.

Ground Fault Circuit Interrupters

In special service vehicles incorporating a lavatory, sink, toilet, shower, or tub, 120 V, 15 or 20 A receptacles within 6 ft (1.8 m) of these fixtures shall have ground fault circuit interrupter (GFCI) protection. GFCIs integrated into outlets or circuit breakers or as stand-alone devices shall be permitted to be used in situations.

Power Source General Requirements

All power source system mechanical and electrical components shall be sized to support the continuous duty nameplate rating of the power source.

The power source shall be shielded from contamination that would prevent the power source from operating within its design specifications.

Power Source Rating

For power sources of 8 kW or larger, the power source manufacturer shall declare the continuous duty rating that the power source can provide when installed on fire apparatus according to the manufacturer's instructions and run at 120°F (49°C) air intake temperature at 2000 ft (600 m) above sea level.

The rating on the power source specification label shall not exceed the declared rating from the power source manufacturer.

Access shall be provided to permit both routine maintenance and removal of the power source for major servicing. The power source shall be located such that neither it nor its mounting brackets interfere with the routine maintenance of the fire apparatus.

Instrumentation

If the power source is rated at less than 3 kW, a "Power On" indicator shall be provided. If the power source is rated at 3 kW or more but less than 8 kW, a voltmeter shall be provided.

If the power source is rated at 8 kW or more, the following instrumentation shall be provided at an operator's panel:

- 1) Voltmeter
- 2) Current meters for each ungrounded leg
- 3) Frequency (Hz) meter
- 4) Power source hour meter

The instrumentation shall be permanently mounted at an operator's panel. The instruments shall be located in a plane facing the operator. Gauges, switches, or other instruments on this panel shall each have a label to indicate their function.

The instruments and other line voltage equipment and controls shall be protected from mechanical damage and not obstructed by tool mounting or equipment storage.

An instruction plate(s) that provides the operator with the essential power source operating instructions, including the power-up and power-down sequence, shall be permanently attached to the apparatus at any point where such operations can take place.

Operation

Provisions shall be made for placing the generator drive system in operation using controls and switches that are identified and within convenient reach of the operator.

Where the generator is driven by the chassis engine and engine compression brakes or engine exhaust brakes are furnished, they shall be automatically disengaged for generator operations.

Any control device used in the generator system power train between the engine and the generator shall be equipped with a means to prevent unintentional movement of the control device from its set position in the power generation mode.

If there is permanent wiring on the apparatus that is designed to be connected to the power source, a power source specification label that is permanently attached to the apparatus at the operator's control station shall provide the operator with the information required.

The power source, at any load, shall not produce a noise level that exceeds 90 dBA in any driving compartment, crew compartment, or onboard command area with windows and doors closed or at any operator's station on the apparatus.

Power Supply Assembly

The conductors used in the power supply assembly between the output terminals of the power source and the main over current protection device shall not exceed 12 ft (4 m) in length.

All power supply assembly conductors, including neutral and grounding conductors, shall have an equivalent amperage rating and shall be sized to carry not less than 115 percent of the amperage of the nameplate current rating of the power source.

If the power supply assembly connects to the vibrating part of a generator (not a connection on the base), the conductors shall be flexible cord or other fine-stranded conductors enclosed in metallic or nonmetallic liquid tight flexible conduit rated for wet locations and temperatures not less than 194°F (90°C).

Over-current Protection

Manually re-settable over current devices shall be installed to protect the line voltage electrical system components.

Power Source Protection

A main over current protection device shall be provided that is either incorporated in the power source or connected to the power source by a power supply assembly.

The size of the main over current protection device shall not exceed 100 percent of the rated amperage stated on the power source specification label or the rating of the next larger available size over current protection device, where so recommended by the power source manufacturer.

If the main over current protection device is subject to road spray, the unit shall be housed in a Type 4-rated enclosure.

Branch Circuit Over-current Protection

Over current protection devices shall be provided for each individual circuit and shall be sized at not less than 15 amps in accordance with 240.4, "Protection of Conductors," of *NFPA 70*.

Any panel board shall have a main breaker where the panel has six or more individual branch circuits or the power source is rated 8 kW or larger.

Each over current protection device shall be marked with a label to identify the function of the circuit it protects.

Dedicated circuits shall be provided for any large appliance or device (air conditioning units, large motors, etc.) that requires 60 percent or more of the rated capacity of the circuit to which it is connected, and that circuit shall serve no other purpose.

Panelboards

All fixed power sources shall be hardwired to a permanently mounted panel board unless one of the following conditions exists:

- 1) All line voltage power connections are made through receptacles on the power source and the receptacles are protected by integrated over current devices.
- 2) Only one circuit is hardwired to the power source, which is protected by an integrated over current device.

The panel shall be visible and located so that there is unimpeded access to the panel board controls. All panel boards shall be designed for use in their intended location. The panel(s) shall be protected from mechanical damage, tool mounting, and equipment storage.

Where the power source is 120/240 V and 120 V loads are connected, the apparatus manufacturer or line voltage system installer shall consider load balancing to the extent that it is possible.

Wiring Methods

Fixed wiring systems shall be limited to the following:

- 1) Metallic or nonmetallic liquid tight flexible conduit rated at temperatures not less than 194°F (90°C) with stranded copper wire rated for wet locations and temperatures not less than 194°F (90°C)
- 2) Type SOW, SOOW, SEOW, or SEOOW flexible cord rated at 600 V and at temperatures not less than 194°F (90°C)

Electrical cord or conduit shall not be attached to chassis suspension components, water or fuel lines, air or air brake lines, fire pump piping, hydraulic lines, exhaust system components, or low voltage wiring and shall be arranged as follows:

- 1) Separated by a minimum distance of 12 in. (300 mm) from exhaust piping or shielded from such piping
- 2) Separated from fuel lines by a minimum distance of 6 in. (150 mm)

A means shall be provided to allow "flexing" between the driving and crew compartment, the body, and other areas or equipment whose movement would stress the wiring.

Electrical cord or conduit shall be supported within 6 in. (150 mm) of any junction box and at a minimum of every 24 in. (600 mm) of run.

Supports shall be made of nonmetallic materials or of corrosion-resistant or corrosion-protected metal. All supports shall be of a design that does not cut or abrade the conduit or cord and shall be mechanically fastened to the apparatus.

Only fittings and components listed for the type of cord or conduit being installed shall be used.

Splices shall be made only in a listed junction box.

Additional Requirements for Flexible Cord Installations

Where flexible cord is used in any location where it could be damaged, it shall be protected by installation in conduit, enclosures, or guards.

Where flexible cord penetrates a metal surface, rubber or plastic grommets or bushings shall be installed.

Wiring Identification

Each line voltage circuit originating from the main panel board shall be identified.

The wire or circuit identification either shall reference a wiring diagram or wire list or shall indicate the final termination point of the circuit.

Where pre-wiring for future power sources or devices exists, the un-terminated ends shall be marked with a label showing their wire size and intended function.

Wiring System Components

Only stranded copper conductors with an insulation rated for temperatures of at least 194°F (90°C) and wet locations shall be used. Conductors in flexible cord shall be sized in accordance with Table 400.5(A) of *NFPA 70*. Conductors used in conduit shall be sized in accordance with 310.15, "Ampacities for Conductors Rated 0–2000 Volts," of *NFPA 70*. Aluminum or copper-clad aluminum conductors shall not be used.

All boxes shall conform to and be mounted in accordance with Article 314, "Outlet, Device, Pull, and Junction Boxes; Conduit Bodies; Fittings; and Manholes," of *NFPA 70*. All boxes shall be accessible using ordinary hand tools. Boxes shall not be permitted behind welded or pop-riveted panels.

The maximum number of conductors permitted in any box shall be in accordance with 314.16, "Number of Conductors in Outlet, Device, and Junction Boxes, and Conduit Bodies," of *NFPA 70*.

All wiring connections and terminations shall provide a positive mechanical and electrical connection. Connectors shall be installed in accordance with the manufacturer's instructions. Wire nuts or insulation displacement and insulation piercing connectors shall not be used.

Each switch shall indicate the position of its contact points (i.e., open or closed) and shall be rated for the continuous operation of the load being controlled. All switches shall be marked with a label indicating the function of the switch. Circuit breakers used as switches shall be "switch rated" (SWD) or better. Switches shall simultaneously open all associated line voltage conductors. Switching of the neutral conductor alone shall not be permitted.

Line voltage circuits controlled by low voltage circuits shall be wired through properly rated relays in listed enclosures that control all non-grounded current-carrying conductors.

Receptacles and Inlet Devices

Wet and Dry Locations

All wet location receptacle outlets and inlet devices, including those on hardwired, remote power distribution boxes, shall be of the grounding type, provided with a wet location cover, and installed in accordance with Section 406.8, "Receptacles in Damp or Wet Locations," of *NFPA 70*.

All receptacles located in a wet location shall be not less than 24 in. (600 mm) from the ground. Receptacles on off road fire apparatus shall be a minimum of 30 in. (750 mm) from the ground. All receptacles located in a dry location shall be of the grounding type and shall be at least 12 in. (300 mm) above the interior floor height. No receptacle shall be installed in a face-up position.

The face of any wet location receptacle shall be installed in a plane from vertical to not more than 45 degrees off vertical.

Receptacle Label

Each receptacle shall be marked with a label indicating the nominal line voltage (120 volts or 240 volts) and the current rating in amps of the circuit. If the receptacle is DC or other than single phase, that information shall also be marked on the label.

All receptacles and electrical inlet devices shall be listed to UL 498, *Standard for Safety Attachment Plugs and Receptacles*, or other recognized performance standards.

Receptacles used for DC voltages shall be rated for DC service.

Wiring Schematics

An "As-Built" Wiring diagrams for line voltage systems shall be provided to include the following information;

- (a) Pictorial representations of circuit logic for all electrical components and wiring
- (b) Circuit identification
- (c) Connector pin identification
- (d) Zone location of electrical components
- (e) Safety interlocks
- (f) Alternator–battery power distribution circuits
- (g) Input/output assignment sheets or equivalent circuit logic implemented in multiplexing systems

120/240 VAC SCENE LIGHTING

SIDE UPPER RECESSED SCENE LIGHTS

Four (4) Fire Research Spectra Max LED Scene Light model SPA260-J20 surface mount light(s) shall be installed. They shall be equally divided between the curbside and streetside. The light(s) shall be mounted with four (4) screws to a flat surface and require a cutout for the electronics box. It shall be no more than 6" high by 14 1/2" wide and have a profile of less than 1 3/4" beyond the mounting surface. Wiring shall extend from the electronics box at the rear of the lamphead.

The lamp head shall sixty (60) ultra-bright white LEDs, 48 for flood lighting and 12 to provide a spot light beam pattern. It shall operate at 240 volts AC, draw 0.7 amp, and generate 20,000 lumens of light. The lamphead shall have a unique lens that directs flood lighting onto the work area and focuses the spot light beam into the distance. The lamphead shall be powder coated. The LED scene light shall be for fire service use.

Scene lights shall be provided with a lens or a means for preventing damage from water spray and listed for wet location usage.

- The above lights shall be controlled by two (2) switch(es) in the lower portion of compartment S1.

REAR UPPER RECESSED SCENE LIGHTS

Two (2) Fire Research Spectra Max LED Scene Light model SPA260-J20 surface mount light(s) shall be installed. They shall be equally divided between the curbside and streetside. The light(s) shall be mounted with four (4) screws to a flat surface and require a cutout for the electronics box. It shall be no more than 6" high by 14 1/2" wide and have a profile of less than 1 3/4" beyond the mounting surface. Wiring shall extend from the electronics box at the rear of the lamphead.

The lamp head shall sixty (60) ultra-bright white LEDs, 48 for flood lighting and 12 to provide a spot light beam pattern. It shall operate at 240 volts AC, draw 0.7 amp, and generate 20,000 lumens of light. The lamphead shall have a unique lens that directs flood lighting onto the work area and focuses the spot light beam into the distance. The lamphead shall be powder coated. The LED scene light shall be for fire service use.

Scene lights shall be provided with a lens or a means for preventing damage from water spray and listed for wet location usage.

- The above lights shall be controlled by one (1) switch(es) in the lower portion of compartment S1.

LIGHT TOWER INSTALLATION

The completed vehicle shall be supplied with one (1) all-electric Command Light flood light tower(s). The unit shall not require tapping into vehicle braking system to be operated, eliminating the chance for vehicle brake problems. Hydraulic or pneumatic type floodlights are not acceptable alternatives to the all-electric light tower specified.

The Command Light light tower(s) shall be purchased and supplied by the Fresno Fire Department or **dealer to the OEM body builder.**

The light tower controls shall be located per the itemized compartment list.

A red flashing or rotating light located in the driving compartment shall be illuminated automatically whenever the vehicles parking brake is not fully engaged, indicating that the light tower is not in stowed position, as required by NFPA 1901.

- **KL415A-FS, (2) light backlight, wired control, amber strobe and standard paint. Will be programmed with VMUX door open detail.**

Light Tower Mounting

The light tower shall be mounted to roof of the custom cab which shall be reinforced as necessary to support weight of the light tower.

Where the light tower is to be mounted above a finished walk-in area; the roof backing plates and structure shall have threaded holes to allow removal of light tower without removal of the interior paneling.

Where the light tower is mounted in close proximity to other roof mounted items (i.e. antennas, air conditioners, and weather stations) the light tower shall be orientated in order to help prevent a operator driven collision.

TREE LIMB GUARD

A three-sided tree limb guard shall be provided fabricated from 1/8" smooth aluminum and painted to match the upper paint color to provide protection to the specified roof mounted equipment from small tree branches.

UTILITY AIR SYSTEM

The completed vehicle shall be provided with a Boss Industries, model 8060-UBI, air compressor rated at 160 CFM @ 110 PSI continuously. The air compressor shall be mounted below chassis frame area and be PTO driven using transmission mounted PTO system. The remote air intake shall be routed through the front rescue body compartmentation to body roof area to minimize intake of dust and debris during operation. An on/off switch shall be provided in cab that will automatically increase engine RPM for maximum air compressor output.

Air compressor system shall have the following features:

- Boss oil flooded, rotary screw air end designed to produce up to 185 CFM @ 110 PSIG continuously.
- Side-by-side gear set incorporated into air-end to achieve conservative engine speeds and greatest ground clearance.
- Two year, unlimited hour, warranty on the air-end.
- Remote mount horizontal oil receiver tank with filler port, lubricant level sight glass and environmentally shielded electronic oil level sender. Exterior shell of vessel to be welded, so as to be one piece. Tank assembly to be attached to frame with easy mount “J” bolts. Tank must be ASME approved.
- Air/oil manifold to include;
 - All electric switches (except oil level), senders, minimum pressure orifice, regulator, and compressor blow down valve.
 - Self-contained separator element capable of 195 CFM @ 295 PSI with easy spin-on housing.
 - Replaceable spin-on compressor lubricant filter with safety bypass and 25-micron rating.
- Engine speed and air inlet controls for automatic modulation of engine speed to match air demand. Engine speed control to interface with the chassis manufactures recommended ECU (Electronic Control Unit). Foot pedal rheostat interface not acceptable.
- Remote mount, self contained, aerodynamically designed cooling package. Venturi housing to be single piece formed ABS plastic.
- Remote mount two-stage, dry-type air intake filter with replaceable filter and gravity evacuator
- Digital instrument panel to include;
 - **General features;** Three (3) bar graph LEDs for monitoring compressor discharge temperature, compressor system pressure and compressor oil level. Eight (8) diagnostic LED indicator lights, one (1) LED hour meter and four (4) seamless push button safety and maintenance buttons.
 - **Safety features;** LED compressor over temperature, high pressure, low oil shutdown indicator lights, an emergency stop button and compressor re-set button.
 - **Diagnostic/ Maintenance features;** Sender fault indicators to activate safety shutdown, LED mode indicating hour meter, test mode to detect faulty system wiring, filter minder LED lights for air filter, oil filter and compressor separator element replacement, check oil level push button, detailed system shutdown memory reviewer, fan LED indicator light to indicate fan operation and regulated air LED indicator light.
- Boss interface module: Pre-wired electronic wiring to main Boss harness to simplify and minimize customer interface connections to engine transmission and PTO.
- Color coded and size differentiated plastic control line tubing, fittings, hoses, single integrated weather-sealed wiring harness for Boss compressor system and hardware necessary for standard installation and operation.
- Necessary warning and information decals.
- Operations, parts and maintenance manual.

UTILITY AIR OUTLETS

Two (2) compartments with hinged aluminum doors shall be provided, one (1) each side of rear apparatus body. Behind each door shall be; one (1) Schrader 1/4" type air fitting, and one (1) 1-1/2" NST male outlet (for use with 1-1/2" fire hose) with matching chrome cap and chain.

A 1/4 turn on/off valve shall be provided in an adjacent interior compartment.

- Controls for utility air compressor shall be located in lower Compartment S1.

Results of the NFPA required utility air system test shall be provided with delivered vehicle.

POWER-TAKE-OFF GENERATOR DRIVE

There shall be a "Hot Shift" power-take-off (PTO) installed on the transmission PTO opening of the chassis. The "Hot Shift" PTO is provided to allow the engagement of the PTO at higher engine RPM speeds. The PTO output shall be connected to the generator through hollow tube type driveline with heavy duty universals.

The engagement of the PTO shall be in the chassis cab with a rocker switch and red pilot light to note engagement of the PTO or via the V-Mux screen if so equipped.

The power supply to the PTO engagement control shall be wired to the parking brake and a neutral position transmission switch to prevent engagement unless the vehicle is stopped and transmission has been placed in neutral.

The installation of the engine, transmission, driven accessories (power takeoffs (PTO), etc.) shall meet the engine and transmission manufacturers' installation recommendations for the service intended.

Model part number shall be Chelsea 280GMFJP-B5XV, 126% Ratio.

EQUIPMENT PAYLOAD WEIGHT ALLOWANCE

In compliance with NFPA 1901 standards, the special service vehicle shall be designed for an equipment loading allowance of 4,000 lbs. of Fresno Fire Department provided equipment based on a 30,001 - 40,000 pound gross vehicle weight rating.

EQUIPMENT

The following equipment shall be furnished with the completed special service vehicle;

- One (1) container of assorted stainless steel nuts, bolts, screws and washers used in the construction of the apparatus shall be provided with the completed apparatus.
- There shall be two (2) Zico SAC-44-E NFPA approved folding aluminum wheel chocks provided for 44" diameter tires that together will hold the vehicle when loaded to its GVWR or GCWR, on a hard surface with a 20 % grade, with the transmission in neutral, and the parking brake released.
 - The wheel chock(s) shall be mounted behind rear wheels, below body on streetside.
- One (1) Little Giant **Overhaul 15197-303 Ladder**
 - The ladder(s) shall be located in specified ladder compartment.
- Two (2) Streamlight FireBox LED flashlight(s) with shoulder strap shall be provided be provided with 540/330 lumen output and 7/15 hour run time.. Each flashlight shall be orange in color and have a 12 volt DC charger and vehicle mount kit. Each flashlight shall have a LED E-Spot spotlight style bulbs and reflectors with 2 ultra-bright LED taillights. The flashlight(s) shall be wired to battery direct unless otherwise specified by Fresno Fire Department.
 - The above specified flashlight(s) shall be shipped loose with the completed unit.

REMAINING NFPA MINOR EQUIPMENT BY PURCHASER

All other minor equipment not specified above, but required by NFPA 1901 for special service vehicles, section 10.9.3 shall be supplied and mounted by Fresno Fire Department before the unit is placed in emergency service.